



MINISTERIO  
DE ECONOMÍA  
Y COMPETITIVIDAD



INSTITUTO PIRENAICO DE ECOLOGIA  
NIF: Q2818002D

Dear Editor Dr. Etienne Berthier,

We are pleased to submit the manuscript entitled: “Thinning of the Monte Perdido Glacier in the Spanish Pyrenees since 1981”.

We are happy about your positive perception of the last submitted version. We also think that the readability has noticeably improved.

We have followed all the mentioned editorial comments you suggested.

Regarding the differences between glaciated surface in 2005 and 2008, we also think that this is mostly due to the methodological approach rather than a dramatic shrinkage in only three years. For this reason, we have only maintained the estimation by René et al. (2013) and we compare their numbers for 2008, with those estimated for 1850. We think this is a good presentation of the following information provided in that paragraph. We have also eliminated the citation to Marti et al. (2015) to the Maladeta Glaciar, and added the reference of the technical report that present these numbers originally (and used by Marti et al., in their discussion).

In name of the other co-authors, we want to sincerely thank your time and thoroughness for handling and improving this manuscript.

Juan-Ignacio López-Moreno and co-authors.

Pyrenean Institute of Ecology, CSIC.

Campus de Aula Dei  
Avenida de Montañana, 1005  
Apartado de correos, 13034  
50.080 ZARAGOZA  
Tfno: 976/369393  
Fax: 976/716019  
nlopez@ipe.csic.es

**THINNING OF THE MONTE PERDIDO GLACIER IN THE SPANISH  
PYRENEES SINCE 1981**

**López-Moreno, J.I.<sup>1</sup>, Revuelto, J.<sup>1</sup>, Rico, I.<sup>2</sup>, Chueca-Cía, J.<sup>3</sup>, Julián, A.<sup>3</sup>, Serreta,  
A.<sup>4</sup>, Serrano, E.<sup>5</sup>, Vicente-Serrano, S.M.<sup>1</sup>, Azorin-Molina, C.<sup>1</sup>, Alonso-González,  
E.<sup>1</sup>, García-Ruiz, J.M.<sup>1</sup>**

1 Dept. Geoenvironmental Processes and Global Change, Pyrenean Institute of Ecology,  
CSIC, Campus de Aula Dei, P.O. Box 13.034, 50.080-Zaragoza, Spain.

2 University of the Basque Country, Department of Geography, Prehistory and  
Archeology, Vitoria, Spain

3 Dept. Geography. University of Zaragoza, Zaragoza, Spain.

4 Dept. Graphic Design and Engineering. University of Zaragoza, Huesca, Spain

5 Dep. Geography, University of Valladolid, Valladolid, Spain.

*Correspondence to:* Juan I. López-Moreno [nlopez@ipe.csic.es](mailto:nlopez@ipe.csic.es)

**Abstract.** This paper analyzes the evolution of the Monte Perdido Glacier, the third largest glacier in the Pyrenees, from 1981 to the present. We assessed the evolution of the glacier's surface area by analysis of aerial photographs from 1981, 1999, and 2006, and changes in ice volume by geodetic methods with digital elevation models (DEMs) generated from topographic maps (1981 and 1999), airborne LIDAR (2010) and terrestrial laser scanning (TLS, 2011, 2012, 2013, and 2014) data. We interpreted the changes in the glacier based on climate data from nearby meteorological stations. The results indicate that the degradation of this glacier accelerated after 1999. The rate of ice surface loss was almost three times greater during 1999-2006 than during earlier periods. Moreover, the rate of glacier thinning was 1.85 times faster during 1999-2010 (rate of surface elevation change =  $-8.98 \pm 1.80$  m, glacier-wide mass balance =  $-0.73 \pm 0.14$  m w.e.  $\text{yr}^{-1}$ ) than during 1981-1999 (rate of surface elevation change =  $-8.35 \pm 2.12$  m, glacier-wide mass balance =  $-0.42 \pm 0.10$  m w.e.  $\text{yr}^{-1}$ ). From 2011 to 2014, ice thinning continued at a slower rate (rate of surface elevation change =  $-1.93 \pm 0.4$  m  $\text{yr}^{-1}$ , glacier-wide mass balance =  $-0.58 \pm 0.36$  m w.e.  $\text{yr}^{-1}$ ). This deceleration in ice thinning compared to the previous 17 years can be attributed, at least in part, to two consecutive anomalously wet winters and cool summers (2012-13 and 2013-14), counteracted to some degree the intense thinning that occurred during the dry and warm 2011-2012 period. However, local climatic changes observed during the study period do not seem sufficient to explain the acceleration in ice thinning of this glacier, because precipitation and air temperature did not exhibit statistically significant trends during the study period. Rather, the accelerated degradation of this glacier in recent years can be explained by a strong disequilibrium between the glacier and the current climate, and likely by other factors affecting the energy balance (e.g. increased albedo in spring) and

feedback mechanisms (e.g. heat emitted from recently exposed bedrock and debris covered areas).

**Keywords:** Glacier shrinkage, glacier thinning, climate evolution, geodetic methods, terrestrial laser scanner (TLS), Pyrenees

## 1 Introduction

Most glaciers worldwide have undergone intense retreat since the culmination of the Little Ice Age (LIA), believed to have been in the mid-19th century, as indicated by measurements of ice surface area and volume (Vincent et al., 2013; Marshall, 2014; Marzeion et al., 2014 and 2015; Zemp et al., 2014). This trend has apparently accelerated in the last three decades (Serrano et al., 2011; Mernild et al., 2013; Carturan et al. 2013a; Gardent et al., 2014; López-Moreno et al., 2014). Marshall (2014) and Zemp et al. (2015) noted that loss of global glacier mass during the early 21<sup>st</sup> century exceeded that of any other decade studied. Several studies have examined this phenomenon in Europe. In the French Alps, glacier shrinkage has accelerated since the 1960s, mainly in the 2000s (Gardent et al., 2014). In the Ötztal Alps (Austria), the loss of glacier area was calculated to be -0.4% per year from 1969 to 1997 and -0.9% per year from 1997 to 2006 (Abermann et al., 2009). In the Central Italian Alps, the average annual decrease in glacier area was found to be approximately 10-fold greater during 1990-2007 than during 1860-1990 (Scotti et al., 2014), while the rate of ice mass loss in the long-term monitored Careser Glacier (Italian Alps) during 1981-2006 (-1.3 meter of water equivalent per year; hereafter m w.e. yr<sup>-1</sup>) was about twice that for the period 1933-1959 (-0.7 m w.e. yr<sup>-1</sup>) (Carturan et al., 2013b). Over a similar period (1980-2010), the rate of ice mass loss calculated for the Swiss Alps was -0.65 m w.e. yr<sup>-1</sup>

(Fischer et al., 2015), which clearly exceeds the values presented by Huss et al. (2010) for the same region over the 20th century (close to  $-0.25 \text{ m w.e. yr}^{-1}$ ). In the Sierra Nevada of southern Spain, the Veleta Glacier, which formed during the LIA, evolved into a rock glacier during the mid-20th century and has suffered marked degradation during the last two decades (Gómez-Ortiz et al., 2014).

The glaciers in the Pyrenees, which are among the southernmost in Europe (Grunewald and Scheithauer, 2010), have also undergone significant retreat. In ~~2005~~1850, these glaciers had an ~~total-estimated~~ area of ~~495-2060~~ hectares (~~González-Trueba et al., 2008~~), but this had decreased to 321 hectares by 2008 (René, 2013). Since ~~1858~~1850, the different massifs have had variable reductions in area covered by ice, with a 59% reduction in the Vignemale Massif and an 84% reduction in the Posets-Llardana Massif (Gellatly et al., 1995; René, 2013). A total of 111 glaciers disappeared in the Pyrenees from ~~1858~~1850 to 2005, and only 31 actual glaciers (with ice motion) remain. There has been a rapid glacial recession since the 1990s, and many of these glaciers face imminent extinction. Chueca et al. (2005 and 2008) reported that the rates of glacial shrinkage during the last two decades of the 20<sup>th</sup> century and the beginning of the 21<sup>st</sup> century were similar to those observed from 1860 to 1900, immediately after the end of the LIA. A similar conclusion has been reached by Marti et al. (2015) for the Ossoue Glacier (French Pyrenees).

Most studies agree that global warming is responsible for the observed glacier shrinkage and the recent acceleration of this shrinkage and glacier thinning. The air temperature increase has been particularly strong since the 1970s in most mountain ranges of the world (Haeberli and Beniston, 1998; Beniston et al., 2003; Nogués-Bravo et al., 2008; Gardent et al., 2014). Global warming has increased the equilibrium line altitudes (ELAs) and reduced the accumulation area ratios (AARs) of glaciers, such that most

glaciers are not in equilibrium with current climate (Mernild et al., 2013) and many cannot persist for much longer (Pelto, 2010). In the case of the Pyrenees, the annual air temperature has increased by a minimum of 0.9°C since the culmination of the LIA (Dessens and Bücher, 1995; Feulliet and Mercier, 2012). More recently, Deaux et al., (2014) reported an increase of 0.2°C decade<sup>-1</sup> for the 1951-2010 period. This air temperature increase explains the ~255 m increase in the elevation of the ELA of the glaciers of the Maladeta Massif since the culmination of the LIA, which is currently close to 2950 m a.s.l. (Chueca et al., 2005). The decreased accumulation of snow and the increase in air temperature during the ablation season are thought to be the principal causes of recent glacier decline on the southern (Spanish) side of the Pyrenees (Chueca et al., 2005).

Glaciers are very good indicators of climate change due to their high sensitivity to anomalies in precipitation and air temperature (Carrivick and Brewer, 2004; Fischer et al., 2015). However, it is not always easy to establish a direct relation between annual fluctuations of climate and the changes in the area and mass of a particular glacier. This is difficult because only glaciers of small size respond rapidly to changes in annual snowfall and snow/ice melt, whereas mid-sized and large glaciers respond much more slowly (Marshall, 2014). Moreover, very small glaciers may develop and evolve for reasons unrelated to the regional long-term, monthly or seasonal climatic evolution, such as, for example avalanches, wind drift and new rock exposure. In the case of shrinking glaciers, the latter can be a key driver of glacier thinning (Chueca and Julián, 2004; Serrano et al., 2011; Carturan et al., 2013c). Local topography also has a considerable effect on the development of ice bodies, and can cause notable variations in the ELAs of different glaciers in the same region (Reinwarth and Escher-Vetter, 1999; Carrivick and Brewer, 2004; López-Moreno et al., 2006). Moreover, many

1 studies of recent changes in glaciers examined the evolution of glacier surface areas or  
2 lengths. These parameters respond to climate fluctuations, but their relationship to  
3 climate is also affected by geometric factors (Haeberli, 1995; Carturan et al., 2013a).  
4 Thus, direct mass-balance estimations or geodetic methods that determine changes in  
5 ice volume provide better information on the relationship between changes in glacier  
6 characteristics and changes in climate (Chueca et al., 2007; Cogley, 2009; Fischer et al.,  
7 2015). In the Pyrenees, only a few estimates of ice volume loss have been published  
8 (Del Río et al., 2014; Sanjosé et al., 2014; Marti et al., 2015), whereas there is abundant  
9 research on recent changes in glaciated surface areas (Chueca et al., 2005; López-  
10 Moreno et al., 2006; González-Trueba et al., 2008). Annual estimates of glacier mass  
11 fluctuations based on the glaciological method have only been performed on the  
12 Maladeta Glacier (Spanish Pyrenees) and on the Ossoue Glacier (French Pyrenees),  
13 with the findings indicating a mean glacier thinning of -14 m during the last 20 years for  
14 the Maladeta Glacier and -22 m for the Ossoue Glacier (Arenillas et al., 2008; René,  
15 2013; Marti et al., 2015). Other studies in the Spanish Pyrenees compared digital  
16 elevation models (DEMs) derived from topographic maps from 1981 and 1999 in the  
17 Maladeta Massif (Chueca et al., 2008) and the Monte Perdido Glacier (Julián and  
18 Chueca, 2007), reporting rates of loss (glacier-wide mass balance) of  $-0.36 \text{ m w.e. yr}^{-1}$   
19 and  $-0.39 \text{ m w.e. yr}^{-1}$ , respectively.

20 This paper focuses on the recent evolution of the Monte Perdido Glacier, the third  
21 largest glacier in the Pyrenees. We document changes in the glacier surface area from  
22 1981 to 2006 and provide updated information on surface elevation changes by  
23 comparing DEMs derived from topographic maps from 1981 and 1999 (Julian and  
24 Chueca, 2007), a new DEM obtained in 2010 from Airborne LIDAR, and four  
25 successive terrestrial laser scanning (TLS) surveys that were performed during the

autumns of 2011, 2012, 2013, and 2014. We examined these data in connection with data on precipitation, snow depth, and air temperature since 1983 from the closest meteorological station, and three longer air temperature and precipitation records (1955-2013) from neighboring stations. Identifying changes during recent years in this region is particularly important because in the 21st century snowfall accumulation has been higher and the air temperatures slightly cooler than in the last decades of the 20<sup>th</sup> century. This shift is associated with a persistently positive North Atlantic Oscillation index during the beginning of the 21st century (Vicente-Serrano et al., 2010; Buisan et al., 2015). The recent response of remnant ice bodies to this climatic anomaly is as yet unknown. Moreover, the availability of annual TLS data in recent years permits detailed examination of the relationship between changes in climate and glaciers.

## **2 Study area and review of previous research on the Monte Perdido Glacier**

The Monte Perdido Glacier (42°40'50"N 0°02'15"E) is located in the Ordesa and Monte Perdido National Park (OMPNP) in the Central Spanish Pyrenees (Figure 1). The ice masses are north-facing, lie on structural flats beneath the main summit of the Monte Perdido Peak (3355 m), and are surrounded by vertical cliffs of 500-800 m in height (García-Ruiz and Martí-Bono, 2002). At the base of the cliffs, the Cinca River flows directly from the glacier and the surrounding slopes, and has created a longitudinal west-east basin called the Marboré Cirque (5.8 km<sup>2</sup>).

Scientists have studied glaciers in the Marboré Cirque since the mid-19th century (Schrader, 1874), and many subsequent studies examined the status and extent of the ice masses and moraine features deposited during the LIA (Gómez de Llarena, 1936; Hernández-Pacheco and Vidal Box, 1946; Boyé, 1952). More recent studies have



established the locations of moraines to deduce the dynamics and extent of LIA glaciers (Nicolás, 1981 and 1986; Martínez de Pisón and Arenillas, 1988; García Ruiz and Martí Bono, 2002; Martín Moreno, 2004) and have analyzed environmental changes during the Holocene through the study of sediments in Marboré Lake (Oliva-Urcía et al., 2013) and by dating of Holocene morainic deposits (García-Ruiz et al., 2014).

The map of Schrader (1874), numerous old photographs, and the location of the LIA moraines (García Ruiz and Martí Bono, 2002) indicate a unique glacier at the foot of the large north-facing wall of the Monte Perdido Massif (Monte Perdido, Cilindro and Marboré peaks) (Figure 1). The map of Schrader (1874) distinguishes the Cilindro-Marboré Glacier, with three small ice tongues that joined at the headwall, from the Monte Perdido Glacier, which was divided into three stepped ice masses connected by serac falls until the mid-20th century. The glacier that existed at the lowest elevation was fed by snow and ice avalanches from the intermediate glacier, but disappeared during the 1970s (Nicolás, 1986; García-Ruiz et al., 2014). The two remaining glacier bodies, which are currently unconnected, are referred to in this paper as the upper and lower Monte Perdido Glaciers. The glacier beneath the Cilindro and Marboré peaks has transformed into three small and isolated ice patches (García-Ruiz et al., 2014). It is noteworthy that Hernández-Pacheco and Vidal Box (1946) previously estimated a maximum ice thickness of 52 m for the upper glacier and 73 m for the lower glacier. In 2008, 82% of the ice cover present at the end of the LIA had already disappeared. The upper and lower ice bodies have mean elevations of 3110 m and 2885 m (Julián and Chueca, 2007). Despite the high elevation of the upper glacier, snow accumulation is limited due to the minimal avalanche activity above the glacier and its marked steepness ( $\approx 40^\circ$ ).

No direct observation has been made of the current location of the ELA in the upper Cinca valley, but studies at the end of the 20th and beginning of the 21st century placed it at about 2800 m in the Gállego Valley, west of the OMPNP (López-Moreno, 2000), and at about 2950 m in the Maladeta Massif, east of the OMPNP (Chueca et al., 2005). The mean annual air temperature at the closest meteorological station (Góriz at 2250 m a.s.l., 2.7 km from the glacier) is 5.03°C, although this station is on the south-facing slope of the Monte Perdido Massif. Assuming a lapse rate of 0.55°C to 0.65°C every 100 m, the annual 0°C isotherm should be roughly at 2950 to 3150 m a.s.l. The climate in this region can be defined as high-mountain Mediterranean. Precipitation as snow can fall on the glacier at any time of year, but most snow accumulation is from November to May, and most ablation is from June to September.

### **3 Data and methods**

#### **3.1 Comparison of DEMs**

Digital elevation models (DEMs) from different dates can be used to calculate surface elevation changes. This technique is well established for the study of glaciers in mountainous areas (Favey et al., 2002), and we have previously applied it in several studies of the Pyrenees (Chueca et al., 2004, 2007; Julián and Chueca, 2007). Thus, we used three DEMs to estimate the surface elevation changes in the Monte Perdido Glacier. Two DEMs (1981 and 1999) were derived from topographic maps and one (2010) was from airborne LIDAR measurements. All three DEMs had a cell size of 2x2 m, and they were used in the context of a geographic information system (GIS), working under the European Datum ED50 (UTM projection, zone 30).

1 The 1981 DEM was obtained from the cartography published by the Spanish *Instituto*  
2 *Geográfico Nacional* (IGN) (Sheet 146-IV, Monte Perdido; Topographic National Map  
3 Series, scale 1:25000). This map was published in 1997 and its cartographic restitution  
4 was based on a photogrammetric flight in September 1981. The 1999 DEM was also  
5 derived from cartography published by the IGN (Sheet 146-IV, Monte Perdido;  
6 Topographic National Map Series MTN25, scale 1:25000). It was published in 2006  
7 and its cartographic restitution was based on a photogrammetric flight in September  
8 1999. The 2010 DEM was obtained from an airborne LIDAR flight (MDT05-LIDAR)  
9 made by the IGN in September 2010 in the context of the National Plan for Aerial  
10 Orthophotography (NPAO).

11 The root mean squared error (RMSE) in elevation calculated by the IGN for their digital  
12 cartographic products at 1:25000 scale is  $\pm 1.5$  m and  $\pm 0.2$  m for their LIDAR derived  
13 DEMs. To verify these accuracies, we compared 2010-1999, 2010-1981 and 1999-1981  
14 pairs of DEMs in areas of ice-free terrain situated near the studied glaciers. The results  
15 showed good agreement with the accuracy indicated by the IGN in almost all areas,  
16 although larger vertical errors were identified in several sectors with very steep terrain  
17 (slopes  $> 65^\circ$  in most cases) located in the Monte Perdido glacial cirque (sharp-edged  
18 crests and abrupt cliffs linked to the geological and structural disposition of the area). In  
19 those sectors, differences between the DEMs reached 10-15 m. As both the Upper and  
20 Lower Monte Perdido glaciers are placed well outside those areas and have smoother  
21 topographical surfaces, it was assumed that the altimetric data provided by the IGN has  
22 an appropriate consistency over the glaciated terrain.

23 The combined vertical RMSE for DEM differences was  $< 2.5$  m for 1999 minus 1981,  
24 and  $< 2.0$  m for 2010 minus 1999. In the latter case it must be noted that different  
25 geodetic methods (photogrammetric and airborne LIDAR) were used in the comparison

and that this may affect the accuracy of the surface elevation changes (Rolstad et al., 2009). In any case, both these errors were considered precise enough for the purposes of the present work as the surface elevation changes obtained in our analysis were generally much greater than these errors. The estimation of surface elevation changes was performed in ArcGIS comparing, by cut and fill procedures, pairs of glacier surface DEMs (1981-1999 and 1999-2010). The glacial perimeters associated with each DEM date were retrieved from aerial photographs (1981: *Pirineos Sur* Flight, September 1981, scale of 1:30000, black and white; 1999: *Gobierno de Aragón* Flight, September 1999, scale of 1:20000, color). There were no high quality flights for 2010, so 2006 aerial photographs were used (PNOA2006 Flight, August 2006, scale of 1:5000, color). The 1999 and 2006 photographs were already orthorectified, but we had to correct the geometry and georeference the aerial survey of 1981 by use of the georeferencing module of ArcGIS. The reference for the control points was from the orthophotos and DEM data from 1999. The horizontal RMSE accuracy of the set of control points ranged from 2.1 to 4.7 m, and was considered sufficiently precise for our study. The maximum horizontal error was used to calculate the uncertainty in the glaciated areas and their temporal changes. This uncertainty was calculated using the *buffer* tool in ArcGIS. This tool allowed quantification of the area of the polygon generated with the maximum horizontal error around the perimeter of the glacier. A resampling procedure using cubic convolution was used to generate the final rectified images.

The most recent estimates of the evolution of the glacier were from annual TLS surveys. LIDAR technology has developed rapidly in recent years, and terrestrial and airborne LIDAR have been used in diverse geomorphology studies, including monitoring changes in the volume of glaciers (Schwalbe et al. 2008, Carturan et al., 2013b). The device employed in the present study is a long-range TLS (RIEGL LPM-321) that uses

time-of-flight technology to measure the time between the emission and detection of a light pulse to produce a three-dimensional point cloud from real topography. The TLS used in this study employed light pulses at 905 nm (near-infrared), which is ideal for acquiring data from snow and ice cover (Prokop, 2008; Grünewald et al., 2010; Egli et al., 2011), a minimum angular step of  $0.0188^\circ$ , a laser beam divergence of  $0.0468^\circ$ , and a maximum working distance of 6000 m.

When TLS is used for long distances, various sources of error must be considered, in particular the instability of the device and errors from georeferencing the clouds of points (Reshetyuk, 2006). We used an almost frontal view of the glacier (similar to the view used for the photos shown in Figure 4) with minimal shadow zones in the glacier and a scanning distance of 1500 to 2500 m. We also used indirect registration, also called target-based registration (Revuelto et al., 2014), so that scans from different dates (September of 2011 to 2014) could be compared. Indirect registration uses fixed reference points (targets) that are located in the study area. Eleven reflective targets of known shape and dimensions (cylinders of 10x10 cm for targets located closer than 200 m, and 50x50 cm squares for longer distances) were placed at reference points on rocks situated 200 to 500 m from the scan station. Using standard topographic methods, we obtained accurate global coordinates for the targets by use of a differential global positioning system (DGPS) with post-processing. The global coordinates were acquired in the UTM 30 coordinate system in the ETRS89 datum. The final precision for the set of target coordinates was  $\pm 0.05$  m in planimetry and  $\pm 0.10$  m in altimetry. A total of 65 reference points around the ice bodies (identifiable sections of rocks and cliffs) were used to assess measurement accuracy. Ninety percent of the reference points had an error of less than 0.40 m. Thus ~~0.440~~ 0.40 m was taken as the uncertainty (error bars) when calculating the ice thinning and mass loss rates. The conversion of mean surface

elevation change to annual mass budget rate was performed by applying a mean density of 900 kg m<sup>-3</sup> (Chueca et al., 2007; Marti et al., 2015). Use of this value assumes the absence of firn, which has a lower density. This assumption was mostly valid at the end of the study period, but likely some firn was present during the early 1980s (Figure 3A suggests the presence of firn). Unfortunately, a lack of additional information forced us to adopt this generalization, which may have led to a slight overestimation of the mass loss rate for 1981–1999.

### 3.2 Climatic data

The Spanish Meteorological Agency (AEMET) provided climatic data from the Góriz manual weather station, located at 2250 m a.s.l. on the southern slope of the Monte Perdido Massif. The absence of changes in instrumentation and observation practices in the meteorological station since 1983, and the proximity of the meteorological station to the glacier (2.7 km), suggest that the station accurately recorded the climate variability over the glacier. The climatic record consists of daily data of air temperature, precipitation, and snow depth. From these data, we derived annual series of maximum and minimum air temperatures for the main periods of snow accumulation (November–May) and ablation (June–September), precipitation during the accumulation season, and maximum snow depth in April (generally the time of maximum snowpack at this meteorological station). The lack of detailed meteorological or mass balance data over the glacier made it necessary to define the accumulation and the ablation seasons in a subjective manner based on our experience. We are aware that May and October are transitional months between accumulation and ablation conditions depending on specific annual conditions. However, we set these periods because June and November

are the months when ablation and accumulation respectively become generally evident over the surface of the glacier. The statistical significance of the linear climate trends was assessed using the non-parametric correlation coefficient of Mann-Kendall's tau-b (Kendall and Gibbons, 1990). Results obtained for Góriz were contrasted with those from three other observatories (see Figure 1) with precipitation (Pineta, Aragnouet and Canfranc), and air temperature (Mediano, Aragnouet and Canfranc) data for 1983-2013, and also for 1955-2013. The non-parametric Mann-Whitney U test (Fay and Proschan, 2010) was used to detect statistically significant differences in the medians of precipitation and air temperature when the 1983-1999 and 2000-2010 periods were compared.

## **4 Results**

### **4.1 Climatic evolution and variability from 1983 to 2014**

Figure 2 illustrates the high interannual variability of climate at Góriz station since 1983. The average maximum air temperatures at Góriz during the snow accumulation and ablation seasons showed no significant trends, with tau-b values close to 0 (Figures 2a and 2b). The range between the highest and lowest average seasonal anomalies during the study period exceeded 3°C and 4°C during the accumulation and ablation periods, respectively, for maximum and minimum air temperatures. The average minimum air temperatures exhibited very weak increases in both seasons, but these were not statistically significant ( $p < 0.05$ ). The interannual air temperature range was larger for the accumulation period (~5°C) than for the ablation period (~2.5°C). Table 1 shows that the evolution of air temperature at Góriz is in line with that observed at the three other meteorological stations (Mediano, Aragnouet and Canfranc). No statistically

significant trends were observed for maximum or minimum air temperature during the 1983-2013 period. When maximum and minimum air temperature data were considered on a monthly basis, the four analyzed observatories exhibited statistically significant increases only in May and June, and statistically significant decreases only in November and December. The Mann-Whitney test did not reveal statistically significant differences in the medians of the series for the accumulation and ablation seasons at any observatory when the periods 1983-1999 and 2000-2010 were compared.

Precipitation at Góriz during the accumulation period also exhibited strong interannual variability, with a range of approximately 600 mm to 1500 mm (Fig. 2e). The trend line showed a slight increase, but this was not statistically significant. Similarly, maximum snow accumulation during April varied from less than 50 cm to 250 cm, and there was no evident trend during the study period (Fig. 2f). Monthly trend analysis (Table 1) found a significant increase in precipitation at Góriz only during May, and near zero tau-b coefficients for most other months. Very similar results were obtained for the other three analyzed stations (Pineta, Aragnouet and Canfranc), with no statistically significant trends for the accumulation and ablation periods. Significant increases in precipitation were observed at Aragnouet only in May, and at Pineta only in March. No statistically significant differences in the median precipitation during the accumulation and ablation seasons of the 1983-1999 and 2000-2010 periods were found at any of the analyzed meteorological stations.

Figure 3 shows the interannual evolution of air temperature and precipitation series for a longer time period (1955-2013). The data illustrate that the climate observed during the main study period (1983-2013) is not necessarily representative of the longer climate series. Thus, the 1955-2013 period exhibited statistically significant ( $p<0.05$ ) warming during the ablation period, and the accumulation exhibited positive tau-b values but did



not reach statistical significance. Precipitation during the accumulation period did not exhibit statistically significant trends during the period 1955-2013 in any of the three observatories analyzed.

Figure 2 also shows that 2011-2014, the period for which TLS measurements of annual glacier evolution were available, showed extremely variable conditions. Mid-September 2011 to mid-September 2012 was one of the warmest recorded years (especially during the ablation period, which was in the 96th and 74th percentiles for maximum and minimum air temperature, respectively) and with a rather dry accumulation period (27th percentile). The period of 2012 to 2013 had an accumulation period that was more humid than average (59th percentile) and the coolest recorded summer (1st and 18<sup>th</sup> percentiles for maximum and minimum air temperatures respectively), and the accumulation period of 2013 to 2014 was very wet (78th percentile) and slightly cooler than average, with air temperatures around or below the average (22th and 48th percentiles for maximum and minimum temperature, respectively) during the ablation period.

#### **4.2 Glacier evolution from 1981 to 2010**

Figure 4 shows photographs of the Monte Perdido Glacier taken in late summer in 1981 and 2011. A simple visual assessment shows the degree of degradation of the glacier during this 30 year period. In 1981, the upper and lower glaciers were no longer united (they became disconnected between 1973 and 1978), and they exhibited a convex surface and significant ice depth with noticeable seracs hanging from the edges of the cliffs. Both ice bodies were heavily crevassed, with evidence of ice motion over the whole glacier. The photograph from 2011 shows that the two ice bodies are further

separated, as well as showing a dramatic reduction in ice thickness, evident in the concave surface, the disappearance of almost all seracs, and the retreat of ice from the edges of the cliffs. Crevasses are only observed in the eastern part of the lower glacier, indicating that the motion of the glacier has slowed or stopped in most of the two ice bodies. Moreover, there are rocky outcrops in the middle of the lower glacier and areas that are partially covered by debris deposits presumably originating from crevasses and rock falls in the upper glacier.

Table 2 shows the surface area of the ice in 1981, 1999, and 2006. From 1981 to 1999 the glacier losses were  $-4.50 \pm 1.27$  ha (a change of  $-1.50 \pm 0.52$  ha in the upper glacier and  $-3.00 \pm 1.21$  ha in the lower glacier), corresponding to an overall rate of  $-0.25 \pm 0.07$  ha yr<sup>-1</sup>. From 1999 to 2006, the glacier losses were  $-5.40 \pm 1.20$  ha (a change of  $-2.00 \pm 0.46$  ha in the upper glacier and  $-3.40 \pm 1.16$  ha in the lower glacier), corresponding to an overall rate of  $-0.77 \pm 0.17$  ha yr<sup>-1</sup>, more than three times the rate of the previous 18 years.

Comparison of the elevation of the glacier's surfaces derived from the DEMs (1981 to 1999 vs. 1999 to 2010) also indicates an acceleration of glacier thinning over time (Figure 5). During the 1981-1999 period, the ice thinning was  $-6.20 \pm 2.12$  m in the upper glacier and  $-8.79 \pm 2.12$  m in the lower glacier ( $-8.35 \pm 2.12$  m overall); thus, the mean rates of glacier thinning were  $-0.34 \pm 0.11$  m yr<sup>-1</sup> and  $-0.48 \pm 0.11$  m yr<sup>-1</sup> ( $-0.46 \pm 0.11$  m yr<sup>-1</sup> overall, or  $-0.42 \pm 0.10$  m w.e. yr<sup>-1</sup> as a glacier-wide mass balance), respectively. Moreover, the changes in glacier elevation surface were not spatially homogeneous. No sector of either glacier showed increased thickness, but some small areas of the lower glacier showed only minor thinning, with declines in thickness of less than 5 m. The largest losses of glacier thickness were in the lower elevations and western regions of the upper and lower glaciers, with decreases that exceeded 25 m and 35 m, respectively.

During the 1999-2010 period, the thinning was  $-7.95 \pm 1.8$  m in the upper glacier and  $-9.13 \pm 1.8$  m in the lower glacier ( $-8.98 \pm 1.80$  m overall); corresponding to rates of  $-0.72 \pm 0.16$  m yr<sup>-1</sup> and  $-0.83 \pm 0.16$  m yr<sup>-1</sup> ( $-0.82 \pm 0.16$  m yr<sup>-1</sup> overall, or  $-0.73 \pm 0.14$  m w.e. yr<sup>-1</sup>), respectively. The spatial pattern of thinning resembled the pattern from 1981-1999, but areas of noticeable glacier losses were also observed further eastward. The smallest decreases were observed in the higher elevation parts of the lower glacier and upper glacier, probably due to more effective shading of these areas, and the greatest decreases were observed in the lower reaches and central-eastern parts of both ice bodies.

#### **4.3 Evolution of the Monte Perdido Glacier from 2011 to 2014 from TLS measurements**

Figure 6 shows the differences in glacier surface elevation between consecutive annual scans (September 2011-12, September 2012-13, and September 2013-14) and the total change from 2011 to 2014. Figure 7 shows the frequency distribution of change in surface elevation measured over the glacier for these periods.

The period of mid-September 2011 to mid-September 2012 was very dry during the accumulation period and very warm during the ablation period. These conditions led to dramatic glacier thinning, with an average decrease of  $-2.10 \pm 0.40$  m ( $-2.08 \pm 0.40$  m in the upper glacier and  $-2.12 \pm 0.40$  m in the lower glacier). Ice thinning affected almost the entire glacier (AAR = 3.5%), and was particularly intense in the western sectors of the upper and lower glaciers, where thinning exceeded four meters. The few scattered points indicating depth increases in the middle of the lower glacier likely derive from rising of the ice surface due to motion of existing crevasses.

1 Conditions were very different from 2012 to 2013, with a rather wet accumulation  
2 period and very cool ablation period. These conditions led to changes that contrasted  
3 sharply with those of the previous year, in that large areas of the glacier showed  
4 increased surface elevation. Most of these increases did not exceed 1.5 meters, and most  
5 were in the highest elevation areas of both ice bodies. Nonetheless, during this year,  
6 large areas remained stable (AAR = 54%) and some areas even exhibited noticeable ice  
7 thinning (more than -1.5 m in the upper and lower glaciers). Despite the excellent  
8 conditions for glacier development from 2012 to 2013, the average increase in glacier  
9 surface elevation was only  $+0.24 \pm 0.40$  m ( $+0.22 \pm 0.40$  m in the upper glacier and  
10  $+0.28 \pm 0.40$  m in the lower glacier). Very similar conditions occurred in 2013-2014,  
11 with very wet accumulation months and below average air temperature during the  
12 ablation period. Again, large areas exhibited moderate increases in surface elevation  
13 (AAR was 41%, sometimes exceeding three meters), although there were still areas that  
14 showed significant ice loss, with an average thinning of  $-0.07 \pm 0.40$  m ( $-0.08 \pm 0.40$  m in  
15 the upper glacier and  $-0.07 \pm 0.40$  m in the lower glacier).

16 The overall result of a very negative year (2011-2012) for glacier development followed  
17 by two years (2012-2013 and 2013-2014) of positive conditions led to a net average  
18 thinning of  $-1.93 \pm 0.40$  m ( $-0.58 \pm 0.36$  m w.e.  $\text{yr}^{-1}$  as glacier-wide mass balance), with  
19 some regions experiencing thinning that exceeded six meters. Only the areas of the  
20 eastern part of the lower glacier that were at high elevations (around the bergschrund)  
21 exhibited some surface elevation gain during this period (AAR for the three years was  
22 16%), and this was typically less than +1.5 meters. Interestingly, the areas with highest  
23 and lowest thinning during 1981-2010 were similar to those with the highest and lowest  
24 thinning during 2011-2014, indicating a consistent spatial pattern of glacier shrinkage  
25 over time.

1

## 2 **5 Discussion and conclusions**

3 The results of this study indicate that the recent evolution of the Monte Perdido Glacier  
4 was similar to that of many other glaciers worldwide (Marshall, 2014; Vincent et al.,  
5 2013), especially those in Europe (Gardent et al., 2014; Abermann et al., 2009; Scotti et  
6 al., 2014; Marti et al., 2015) where glacier shrinkage has been occurring since the  
7 culmination of the LIA and has clearly accelerated since 2000. More specifically, the  
8 annual loss of area of the Monte Perdido Glacier was near three times greater during  
9 1999-2006 than 1981-1999, and the glacier thinning from 1999 to 2010 was almost  
10 double that observed from 1981 to 1999. Acceleration in glacier thinning has also been  
11 reported for the Ossoue Glacier (French Pyrenees), where the mass balance during the  
12 period 2001-2013 ( $-1.45 \text{ m w.e. yr}^{-1}$ ) was almost 50% greater compared to that during  
13 1983-2014 ( $-1 \text{ m w.e. yr}^{-1}$ ), (Marti et al., 2015). Climatic analyses suggest that the  
14 recent acceleration in the thinning of the Monte Perdido Glacier cannot be explained  
15 solely by an intensification of climate warming or by a decline in snow accumulation.  
16 Climate data (1983-2014) of a nearby meteorological station, and three other Pyrenean  
17 meteorological stations, suggest that during most of the year air temperature has not  
18 exhibited statistically significant trends. The Mann-Whitney test did not reveal  
19 statistically significant differences in air temperature when the period 1983-1999 was  
20 compared to 2000-2010. Precipitation in the four analyzed stations during the  
21 accumulation period and maximum annual snow depth at Góriz were also stationary or  
22 slightly increased. Previous studies of the Pyrenees and surrounding areas showed that  
23 air temperature increased significantly throughout the 20<sup>th</sup> century, especially after the  
24 relatively cold period from the 1960s to the mid-1970s (López-Moreno et al., 2008; El  
25 Kenawy et al., 2012; Deaux et al., 2014). Similar trends were detected in the three air

temperature series analyzed for this study covering the 1955-2013 period. At the same time, there was a regional significant decline in snow accumulation from mid-March to late-April/early-May from 1950 to 2000 in the Pyrenees (López-Moreno, 2005). The trends during this period of decreasing precipitation and milder air temperatures during winter and early spring can be related to changes in the North Atlantic Oscillation (NAO) index (López-Moreno et al., 2008). More recent studies that used updated databases (including data of the 21<sup>st</sup> century) confirmed that a shift towards more negative NAO has affected the recent evolution of air temperature and precipitation over the Pyrenees. Thus, for the period 1983 to 2013, which does not include the effects of the cold and wet period of the 1960s to 1970s, no temporal trends of either variable are found near Monte Perdido. Vicente-Serrano et al. (2010) found that the increased occurrence of very wet winters during the 2000s was associated with frequent strong negative NAO winters. In agreement, Buisan et al. (2015) reported that for the period 1980-2013 the overall number of snow days in the Pyrenees remained stationary and even slightly increased in some locations. In a more recent study, Buisan et al. (under review) observed stationary behavior or slight increases in snow water equivalent for the period 1985-2015 in the central Spanish Pyrenees. The findings of Macias et al. (2014) support the view that southern Europe and some other regions of the world have undergone clear moderations of the warming trends that were recorded at the end of the 20<sup>th</sup> century. Nonetheless, it is necessary to bear in mind that the longest climatic records or dendroclimatological reconstructions for the Pyrenees still point to the period considered in this study (1980-2014) as a very strong positive anomaly of air temperature and a dry period compared to the period since the end of the LIA (Büntgen et al., 2008; Deaux et al., 2014; Marti et al., 2015). More research is needed to fully assess the implications of the air temperature increase detected in May

and June at the four analyzed meteorological stations. This warming could lead to less snow accumulation at the end of the accumulation season and a longer ablation period, and an early rise of albedo that may affect the mass and energy balance of the glacier (Qu et al., 2014). Another factor that should be considered in future research is the effect of increases in the slope of the glacier due to greater thinning in the lower reaches. Increasing slope is expected to affect snow accumulation on the glacier and might constitute another feedback mechanism underlying the recent evolution of the glacier.

The glacier-wide mass balance rates presented in this study for 1980-1999 and 1999-2010 ( $-0.42 \pm 0.1$  and  $-0.73 \pm 0.14$  m w.e.  $\text{yr}^{-1}$ , respectively) are similar to those reported by Chueca et al. (2007) and ~~Marti-Pastor et al. (2015)~~2013 for the Maladeta massif ( $-0.36$  m w.e.  $\text{yr}^{-1}$  for 1981-1999 and  $-0.7$  m w.e.  $\text{yr}^{-1}$  for 1991-2013). The most recent mass balance values obtained for the Monte Perdido Glacier are more similar to those reported for glaciers in the Swiss Alps (Fischer et al., 2015), or for the best preserved glaciers in some areas of the Italian Alps (Carturan et al., 2013a), but are lower than those of the fastest retreating glaciers in the Alps (Carturan et al., 2013b) or that reported for the Ossoue Glacier (French Pyrenees,  $-1.45$  m w.e.  $\text{yr}^{-1}$  for 1983-2014). The smaller rates of mass loss on the Spanish side of the Pyrenees than on the French side may be explained by the location of the remnant ice bodies on the Southern side of the range, confined to the most elevated and the least exposed locations in their respective cirques (López-Moreno et al., 2006). In contrast, the Ossoue ~~G~~lacier has maintained a considerable glacier tongue with an eastward slope. In this context, the only explanation for the rapid degradation of the Monte Perdido Glacier after 1999 is that the progressive warming observed since the end of the LIA was responsible for a dramatic reduction in the AAR, and most of this glacier is below the current ELA (at 3050 m a.s.l. during the

1 three-year period 2011-2014, Figure 6). Such a reduction in AAR would lead to an  
2 imbalance that would likely be exacerbated by negative feedbacks. Because of this  
3 imbalance, the glacier is not able to recover ice losses during periods with favorable  
4 conditions (high accumulation and/or little ablation in the frame of the 1983-2014  
5 period). This hypothesis is strongly supported by our detailed TLS measurements from  
6 the last four years. In particular, these TLS data showed that two consecutive  
7 anomalously positive years (2012/13 and 2013/14) did not allow the glacier to recover  
8 the losses from a negative year (2011/12). Thus the glacier thinning during this three-  
9 year period was  $-1.93 \pm 0.4$  m ( $-0.58 \pm 0.36$  m w.e.  $\text{yr}^{-1}$ ), approximately one-quarter of the  
10 loss during 1981-1999, and during 1999-2010. The AAR for 2011-2014 was 16%, and  
11 during a warm and dry year the ice thinning affects almost the whole glacier (AAR =  
12 3.5%), indicating the lack of a persistent accumulation zone. Peltó (2010) observed that  
13 this is a symptom of a glacier that cannot survive. There can be years with mass gain,  
14 but mass loss occurs in most years and the retained snowpack of positive years is lost in  
15 negative years, such that there is no cumulative accumulation. Thus, the behavior  
16 observed for the Monte Perdido Glacier during the study period is very likely explained  
17 by very negative mass balance in some years, as can be seen in Figure 2. For example,  
18 air temperatures were very high in 2003, 2005 and 2012, and in the latter two years the  
19 high air temperatures were accompanied by low winter precipitation. The feedback from  
20 decreased albedo and increasing glacier slope may also have played a key role in the  
21 recent acceleration of glacier thinning. Together, these findings indicate that the future  
22 of the Monte Perdido Glacier is seriously threatened, even under stationary climatic  
23 conditions. A ground-penetrating radar (GPR) survey of the lower glacier in 2010  
24 reported a maximum ice depth close to 30 m in the westernmost part of the lower  
25 glacier (unpublished report), suggesting that large areas of this glacier may disappear



1 within the next few years. This process may be accelerated by negative feedback  
2 associated with the recent rise of rocky outcrops in the middle of the glacier and the thin  
3 cover of debris, both of which may accelerate glacier ablation by decreasing the albedo  
4 and increasing the emissivity of long-wave radiation. The highly consistent spatial  
5 pattern of ice thinning in the last 30 years suggests that the westernmost part of this  
6 glacier will disappear first; the easternmost part will survive longer as a small residual  
7 ice mass because of greater snow accumulation during positive years and a lower rate of  
8 degradation. When the glacier is restricted to this smaller area, it is likely that its rate of  
9 shrinkage will decrease, as observed for other Pyrenean glaciers (López-Moreno et al.,  
10 2006).

11 The future long-term monitoring of the Monte Perdido Glacier should provide important  
12 information on the year-to-year response of its mass balance to a variety of climatic  
13 conditions, and will allow detailed analysis of the role of positive and negative  
14 feedbacks in this much-deteriorated glacier. Thus, this glacier may serve as a model for  
15 studies of the evolution of glaciers in other regions of the world that have similar  
16 characteristics.

17  
18 *Acknowledgements.* This study was funded by two research grants: “CGL2014-52599-P,  
19 *Estudio del manto de nieve en la montaña española, y su respuesta a la variabilidad y*  
20 *cambio climático*” (IBERNIEVE-Ministry of Economy and Competitiveness), and “*El*  
21 *glaciar de Monte Perdido: estudio de su dinámica actual y procesos criosféricos*  
22 *asociados como indicadores de procesos de cambio global*” (MAGRAMA 844/2013).  
23 The authors are grateful for the support provided by the “Dirección General de

Conservación del Medio Natural (Government of Aragón)” and to the staff of the Ordesa and Monte Perdido National Park during our field campaigns.

#### References

Abermann, J., Lambrecht, A., Fischer, A., and Kuhn, M.: Quantifying changes and trends in glacier area and volume in the Austrian Ötztal Alps (1969–1997–2006). *The Cryosphere*, 3, 205– 215, 2009.

Arenillas, M., Cobos, G., Navarro, J.: Datos sobre la nieve y los glaciares en las cordilleras españolas. El programa ERHIN (1984-2008). Ed. Ministerio de Medio Ambiente y Medio Rural y Marino, Madrid, 231pp, 2008.

Beniston M.: Climatic change in mountain regions: a review of possible impacts. *Climatic Change* , 59, 5–31, 2003.

Boyé, M.: Névés et érosion glaciaire.: *Revue de Géomorphologie Dynamique* 2, 20-36, 1952.

Buisan, S.T., Saz, M.A., López-Moreno, J.I.: Spatial and temporal variability of winter snow and precipitation days in the western and central Spanish Pyrenees. *International Journal of Climatology*, 35 (2), 259-274, 2015.

Buisan, S.T., López-Moreno, J.I., Saz, M.A., Kochendorfer, J.: Impact of weather type variability on winter precipitation, temperature and snowpack in the Spanish Pyrenees. *Climate Reserach*, under review.

Büngten, U., Frank, D., Grudd, H., Esper, J.: Long-term summer temperature variations in the Pyrenees. *Clymate Dynamics*, 31 (6), 615-631, 2008.

- 1 Carrivick, J. L., Brewer, T. R.: Improving local estimations and regional trends of  
2 glacier equilibrium line altitudes. *Geografiska Annaler: Series A, Physical Geography*,  
3 86: 67–79, 2004.
- 4 Carturan, L., Filippi, R., Seppi, R., Gabrielli, P., Notarnicola, C., Bertoldi, L., Paul, F.,  
5 Rastner, P., Cazorzi, F., Dinale, R., Dalla-Fontana, G.: Area and volume loss of the  
6 glaciers in the Ortles-Cevedale group (Eastern Italian Alps): controls and imbalance of  
7 the remaining glaciers, *The Cryosphere*, 7, 1339-1359, 2013a.
- 8 Carturan, L., Baroni, C., Becker, M., Bellin, A., Cainelli, O., Carton, A., Casarotto, C.,  
9 Dalla Fontana, D., Godio, A., Martinelli, T., Salvatore, M.C., Seppi, R.: Decay of a  
10 long-term monitored glacier: Careser Glacier (Ortles-Cevedale, European Alps). *The*  
11 *Cryosphere*, 7, 1819-1838, 2013b.
- 12 Carturan L., Baldassi, G.A., Bondesan, A., Calligaro, S., Carton, A., Cazorzi F., Dalla  
13 Fontana, G., Francese, R., Guarnieri, A., Milan, N., Moro, D. Tarolli, P.: Current  
14 behavior and dynamics of the lowermost Italian glacier (Montasio Occidentale, Julian  
15 Alps). *Geografiska Annaler: Series A, Physical Geography*, 95(1), 79-96, 2013c.
- 16 Chueca, J., Julián, A.: Relationship between solar radiation and the development and  
17 morphology of small cirque glaciers (Maladeta Mountain massif, Central Pyrenees,  
18 Spain). *Geografiska. Annaler*, 86 A (1), 81-89, 2004.
- 19 Chueca, J., Julián, A., Saz, M.A., Creus, J., López-Moreno, J.I.: Responses to climatic  
20 changes since the Little Ice Age on Maladeta Glacier (Central Pyrenees).  
21 *Geomorphology*, 68(3–4), 167–182, 2005.

- 1 Chueca, J., Julián A., López-Moreno, J.I.: Recent evolution (1981–2005) of the  
2 Maladeta glaciers, Pyrenees, Spain: extent and volume losses and their relation with  
3 climatic and topographic factors. *Journal of Glaciology*, 53 (183), 547-557, 2007.
- 4 Chueca, J., Julián Andrés, A., López Moreno, J.I.: The retreat of the Pyrenean Glaciers  
5 (Spain) from the Little Ice Age: data consistency and spatial differences. *Terra*  
6 *Glacialis*, 2008, 137-148, 2008.
- 7 Cogley, J.G.: Geodetic and direct mass-balance measurements: comparison and joint  
8 analysis. *Annals of Glaciology*, 50(50), 96-100, 2009.
- 9 Deaux, N., Soubayroux, J. M., Cuadrat, J. M., Cunillera, J., Esteban, P., Prohom, M.,  
10 Serrano-Notivoli, R.: Homogénéisation transfrontalière des températures sur le massif  
11 des Pyrénées, XXVII Colloque de l'Association Internationale de Climatologie, 2–5  
12 Julliet 2014, Dijon, France, 344–350, 2014.
- 13 Del Río, M., Rico, I., Serrano, E., Tejado, J.J.: Applying GPR and Laser Scanner  
14 Techniques to Monitor the Ossoue Glacier (Pyrenees). *Journal of Environmental &*  
15 *Engineering Geophysics*, 19 (4), 239–248, 2014.
- 16 Dessens, J., Bücher, A.: Changes in minimum and maximum temperatures at the Pic du  
17 Midi in relation with humidity and cloudiness, 1882–1984. *Atmospheric Research*, 37,  
18 147–162, 1995.
- 19 Egli, L., Griessinger, N., Jonas, T.: Seasonal development of spatial snow depth  
20 variability across different scales in the Alps. *Annals of Glaciology*, 52 (58), 216-222,  
21 2011.

1 El Kenawy, A., López-Moreno, JI., Vicente-Serrano, S.M.: Trend and variability of  
2 surface air temperature in northeastern Spain (1920–2006): linkage to atmospheric  
3 circulation. *Atmospheric Research*. 106, 159-180, 2012.

4 Favey, E., Wehr, A., Geiger, A., Kahle, H.G.: Some examples of European activities in  
5 airborne laser techniques and an application in glaciology. *Journal of Geodynamics*, 34,  
6 347-355, 2002.

7 Fay, M.P.: Proschan, M.A.: Wilcoxon–Mann–Whitney or t-test? On assumptions for  
8 hypothesis tests and multiple interpretations of decision rules. *Statistics Surveys* 4, 1–  
9 39, 2010.

10 Feuillet, Th., Mercier, D.: Post-Little Ice Age patterned ground development on two  
11 Pyrenean proglacial areas: from deglaciation to periglaciation. *Geografiska Annaler*:  
12 Series A, 94, 363–376, 2012.

13 Fischer, M., Huss, M., Hoelzle, M.: Surface elevation and mass changes of all Swiss  
14 glaciers 1980–2010. *The Cryosphere*, 9, 525-540, 2015.

15 García Ruiz, J.M., Martí Bono, C.E.: Mapa geomorfológico del Parque Nacional de  
16 Ordesa y Monte Perdido. Organismo Autónomo de Parques Nacionales, Madrid, 106  
17 pp, 2002.

18 García-Ruiz, J.M., Palacios D., De Andrés N, Valero-Garcés BL, López-Moreno JI,  
19 Sanjuán Y.: Holocene and ‘Little Ice Age’ glacial activity in the Marboré Cirque, Monte  
20 Perdido Massif, Central Spanish Pyrenees. *The Holocene* 24 (11), 1439–1452, 2014.

21 Gardent, M., Rabatel, A., Dedieu, J.P., Deline, P.: Multi-temporal glacier inventory of  
22 the French Alps from the late 1960s to the late 2000s, *Global and Planetary Change*,  
23 120, 24–37, 2014.

- 1 Gellatly A.F., Grove, J.M., Bücher, A., Latham, R., Whalley, W.B.: Recent historical  
2 fluctuations of the Glacier du Taillon. *Physical Geography*, 15 (5), 399-413, 1995.
- 3 Gómez de Llarena, J.: Algunos datos sobre el glaciar actual del Monte Perdido  
4 (Pirineos). *Boletín de la Real Sociedad Española de Historia Natural* 36, 327-343, 1936.
- 5 Gómez-Ortiz, A., Oliva, M., Salvador-Franch, F., Salvà-Catarineu, M., Palacios, D., de  
6 Sanjosé-Blasco, J.J., Tanarro-García, L.M., Galindo-Zaldívar, J., Sanz de Galdeano, C.:  
7 Degradation of buried ice and permafrost in the Veleta cirque (Sierra Nevada, Spain)  
8 from 2006 to 2013 as a response to recent climate trends. *Solid Earth* 5, 979-993, 2014.
- 9 González-Trueba, J.J., Martín Moreno, R., Martínez de Pisón, E., Serrano E.: Little Ice  
10 Age glaciation and current glaciers in the Iberian Peninsula. *The Holocene* 18 (4), 569-  
11 586, 2008.
- 12 Grunewald, K., Scheithauer, J.: Europe's southernmost glaciers: response and adaptation  
13 to climate change. *Journal of Glaciology*, 56 (195), 129-142, 2010.
- 14 Grünewald, T., Schirmer, M., Mott, R., Lehning, M.: Spatial and temporal variability of  
15 snow depth and ablation rates in a small mountain catchment, *The Cryosphere*, 4, 215-  
16 225, 2010.
- 17 Haeberli, W.: Glacier fluctuations and climate change detection. *Geografia Fisica e*  
18 *Dinamica Quaternaria*, 18, 191-195, 1995.
- 19 Haeberli, W., Beniston, M.: Climate change and its impacts on glaciers and permafrost  
20 in the Alps. *Ambio*, 27 (4), 258-265, 1998.

Con formato: Inglés (Estados Unidos)

- 1 Hernández-Pacheco, F., Vidal Box, C.: La tectónica y la morfología del macizo de  
2 Monte Perdido y de las zonas de cumbres inmediatas en el pirineo Central. Pirineos 4,  
3 69-108, 1946.
- 4 Huss, M., Hock, R., Bauder A., Funk M.: 100-year mass changes in the Swiss Alps  
5 linked to the Atlantic Multidecadal Oscillation. Geophys. Res. Lett., 37, L10501, 2010.
- 6 Julián, A., Chueca J.: Pérdidas de extensión y volumen en los glaciares del macizo de  
7 Monte Perdido (Pirineo central español): 1981-1999. Boletín Glaciológico Aragonés, 8,  
8 31-60, 2007.
- 9 Kenawy, A., López-Moreno, J.I., Vicente-Serrano, S.M.: Trend and variability of  
10 surface air temperature in northeastern Spain (1920–2006): linkage to atmospheric  
11 circulation. Atmospheric Research. 106, 159-180, 2012.
- 12 Kendall, M.G., Gibbons, J. D.. Rank correlation methods. Oxford University Press, 272  
13 pp, 1990.
- 14 López-Moreno, J.I.: Los glaciares del alto valle del Gállego (Pirineo central) desde la  
15 Pequeña Edad de Hielo. Implicaciones en la evolución de la temperatura, Geoforma  
16 Ediciones, Logroño, 77 p, 2000.
- 17 López-Moreno, J.I. Recent variations of snowpack depth in the central Spanish  
18 Pyrenees. Arctic Antarctic and Alpine Research, 37 (2), 253–260, 2005.
- 19 López-Moreno, J.I., Nogués-Bravo D, Chueca-Cía J., Julián-Andrés A.: Change of  
20 topographic control on the extent of cirque glaciers since the Little Ice Age.  
21 Geophysical Research Letters, 33, L24505, 2006.

- 1 López-Moreno, J. I., García-Ruiz, J. M., Beniston, M.: Environmental Change and  
2 water management in the Pyrenees. Facts and future perspectives for Mediterranean  
3 mountains. *Global and Planetary Change*, 66(3–4), 300–312, 2008.
- 4 López-Moreno, J.I., Fontaneda, S., Bazo, J., Revuelto, J., Azorín-Molina, C., Valero-  
5 Garcés, B., Morán-Tejeda, E., Vicente-Serrano, S.M., Zubieta, R., Alejo-Cochachín, J.:  
6 Recent glacier retreat and climate trends in cordillera Huaytapallana, Peru. *Global and*  
7 *Planetary Change*, 112, 1-12, 2014.
- 8 Macias, D., Stips, A., Garcia-Gorritz, E.: Application of the Singular Spectrum Analysis  
9 Technique to Study the Recent Hiatus on the Global Surface Temperature Record.  
10 *PLOS ONE*, 9 (9), 2014.
- 11 Marshall S.: Glacier retreat crosses a line. *Science*, 345 (6199), 872, 2014
- 12 Martín-Moreno, R.: Comparación de dos glaciares: Longyearbeen (Spitsbergen) y  
13 Monte Perdido (Pirineos). Características y evolución desde la Pequeña Edad del Hielo.  
14 *Ería* 63, 5-22, 2004.
- 15 Marti, R., Gascoin, S., Houet, T., Ribière, O., Laffly, D., Condom, T., Monnier, S.,  
16 Schmutz, M., Camerlynck, C., Tihay, J.P., Soubeyroux, S.M., René, P.: Evolution of  
17 Ossoue Glacier (French Pyrenees) since the end of the Little Ice Age. *The Cryosphere*,  
18 9, 1773-1795, 2015
- 19 Martínez de Pisón, E., Arenillas, M.: Los glaciares actuales del pirineo español. En *La*  
20 *nieve en el pirineo español*. MOPU, Madrid, 287 pp. 29-98, 1988.
- 21 Marzeion, B., Cogley, J. G., Richter, K., Parkes, D.: Attribution of global glacier mass  
22 loss to anthropogenic and natural causes, *Science*, 345, 919–921, 2014.



Marzeion, B., Leclercq, P.W., Cogley, J.G., Jarosch, A.H.: Global glacier mass loss reconstructions during the 20th century are consistent. *The Cryosphere*, 9, 2399-2404, 2015.

Mernild, S.H., Lipscomb, W.H., Bahr, D.B., Radic, V., Zemp, M.: Global glacier changes: a revised assessment of committed mass losses and sampling uncertainties. *The Cryosphere*, 7, 1565-1577, 2013.

Nicolás, P.: Morfología del circo de Tucarroya. Macizo de Monte Perdido, Pirineo Aragonés. *Cuadernos de Investigación Geográfica*, 7, 51-80, 1981.

Nicolás, P.: Morfología de un aparato glaciar: el glaciar nororiental de Monte Pedido. Pirineo de Huesca. In: *Atlas de Geomorfología*. Alianza Editorial, Madrid, pp. 189-207, 1986.

Nogués-Bravo, D., Lasanta, T., López-Moreno, J.I., Araujo: Climate change in Mediterranean mountains during the 21st century. *Ambio*, 37(4), 280-285, 2008.

Oliva-Urcía, B., Moreno, A., Valero-Garcés, B., Mata, P.: Magnetismo y cambios ambientales en registros terrestres: el lago de Marboré, Parque Nacional de Ordesa y Monte Perdido (Huesca). *Cuadernos de Investigación Geográfica* 39 (1), 117-140, 2013.

Pastor, F.: Determinación del balance anual de masa y movimiento del hielo en el glaciar de la Maladeta. Año hidrológico 2012-2013. Technical report from ERHIN, Madrid, 68 pp, 2013.

Pelto, M.S.: Forecasting temperate alpine glacier survival from accumulation zone observations. *The Cryosphere*, 3, 323-350, 2010.

Con formato: Inglés (Estados Unidos)

Con formato: Español (alfab. internacional)

Con formato: Inglés (Estados Unidos)

Con formato: Inglés (Estados Unidos)

- 1 Prokop, A.: Assessing the applicability of terrestrial laser scanning for spatial snow  
2 depth measurements. *Cold Regions Science and Technology*, 54 (3), 155–163, 2008.
- 3 Qu, B., Ming, J., Kang, S.-C., Zhang, G.-S., Li, Y.-W., Li, C.-D., Zhao, S.-Y., Ji, Z.-M.,  
4 and Cao, J.-J.: The decreasing albedo of the Zhadang glacier on western  
5 Nyainqentanglha and the role of light-absorbing impurities, *Atmos. Chem. Phys.*, 14,  
6 1117-11128, doi:10.5194/acp-14-11117-2014, 2014.
- 7 Reinwarth, O., Escher-Vetter, H.: Mass Balance of Vernagtferner, Austria, From  
8 1964/65 to 1996/97: Results for Three Sections and the Entire Glacier. *Geografiska*  
9 *Annaler*, Series A, Physical Geography, 81: 743–751, 1999.
- 10 René, P.: *Le réchauffement climatique en images*. Ed. Cairn. Pau (France), 167 pp,  
11 2013.
- 12 Reshetyuk, Y.: Calibration of Terrestrial Laser Scanners Callidus 1.1, Leica HDS 3000  
13 and Leica HDS 2500. *Survey Review*, 38 (302), 703-713, 2006.
- 14 Revuelto, J., López-Moreno J.I., Azorín-Molina C., Zabalza J., Arguedas G., Vicente-  
15 Serrano S.M.: Mapping the annual evolution of snow depth in a small catchment in the  
16 Pyrenees using the long-range terrestrial laser scanning. *Journal of Maps*, 10 (3), 359-  
17 373, 2014.
- 18 Rolstad, C., Haug, T., Denby, B.: Spatially integrated geodetic glacier mass balance and  
19 its uncertainty based on geostatistical analysis: application to the western Svartisen ice  
20 cap, Norway. *Journal of Glaciology*, 55 (192), 666-680, 2009.
- 21 Sanjosé, J.J.; Berenguer, F.; Atkinson, A.D.J.; De Matías, J.; Serrano, E.; Gómez-Ortiz,  
22 A.; González-García, M.; Rico, I.: Geomatics techniques applied to glaciers, rock

- 1 glaciers and ice-patches in Spain (1991-2012). *Geografiska Annaler, Series A, Physical*
- 2 *Geography* 96, 3, 307-321, 2014.
- 3 Schwalbe, E., Maas, H.-G., Dietrich, R., Ewert, H.: Glacier velocity determination from
- 4 multi-temporal long range laser scanner point clouds. *International Archives of*
- 5 *Photogrammetry and Remote Sensing*, 18, B5, 2008.
- 6 Schrader, F.: Carte du Mont-Perdu et de la region calcaire des Pyrénées. Expart des
- 7 Mémoires de la Société des Sciences Physiques et Naturelles de Bordeaux. Bordeaux,
- 8 Journal de L'imprimerie Chariol, 1874.
- 9 Scotti, R., Brardinoni, F., Crosta, G.B.: Post-LIA glacier changes along a latitudinal
- 10 transect in the Central Italian Alps. *The Cryosphere*, 8, 2235-2252, 2014.
- 11 Serrano, E., González-Trueba, J.J., Sanjosé, J.J., Del Río, L.M.: Ice patch origin,
- 12 evolution and dynamics in a temperate high mountain environment: the Jou Negro,
- 13 Picos de Europa (NW Spain). *Geografiska Annaler-A*, 93 (2), 57-70, 2011.
- 14 Vicente-Serrano, S. M., Trigo, R. T., López-Moreno, J. I., Liberato, M. L. R., Lorenzo-
- 15 Lacruz, J., Beguería, S.: The 2010 extreme winter north hemisphere atmospheric
- 16 variability in Iberian precipitation: anomalies, driving mechanisms and future
- 17 projections. *Climate Research*, 46, 51–65, 2011
- 18 Vincent, C., Ramanathan, A.L., Wagnon, P., Dobhal, D.P., Linda, A., Berthier, A.,
- 19 Sharma, P., Arnaud, Y. F., Azam, M., Gardelle J.: Balanced conditions or slight mass
- 20 gain of glaciers in the Lahaul and Spiti region (northern India, Himalaya) during the
- 21 nineties preceded recent mass loss. *The Cryosphere*, 7, 569-582, 2013.
- 22 Zemp, M., Haeberli, W., Hoelzle, M., Usabaliev, R., Azisov, E., Caceres, B., Ceballos,
- 23 J.L.: Mountain glaciers: on thinning ice. In: Kohler, T., Wehrli, A. and Jurek, M. (eds.):

Mountains and Climate Change: a global concern. Sustainable Mountain Development Series. Swiss Centre for Development and Environment (CDE), Swiss Agency for Development and Cooperation (SDC), and Geographica Bernensia, Bern, Switzerland: p. 51-59, 2014.

Zemp, M., Frey, H., Gärtner-Roer, I., Nussbaumer, S.U., Hoelzle, M., Paul, F., Haeberli, W., Denzinger, F., Ahlstrom, A.P., Anderson, B., Bajracharya, S., Baroni, C., Braun, L.N., Caceres, B.E., Casassa, G., Cobos, G., Davila, L.R., Delgado Granados, H., Demuth, M.N., Espizua, L., Fischer, A., Fujita, K., Gadek, B., Ghazanfar, A., Hagen, J.O., Holmlund, P., Karimi, N., Li, Z., Pelto, M., Pitte, P., Popovnin, V.V., Portocarrero, C.A., Prinz, R., Sangewar, C.V., Severskiy, I., Sigurdsson, O., Soruco, A., Usubaliev, R., Vincent, C.: Historically unprecedented global glacier decline in the early 21st century. *Journal of Glaciology*, 61 (228), 745-762, 2015.

13

## Figure captions

**Figure 1.** Monte Perdido study area and extent of ice cover at the culmination of the Little Ice Age (according to the map of Schrader [1874]) and in 2008. Red squares mark the scanning positions, numbered points indicate the positions of the fixed targets used for georeferencing and merging the different clouds of points. Red circles in the right panel inform of the location of the analyzed meteorological stations.

**Figure 2.** Interannual fluctuations and overall trends (straight lines) of minimum and maximum air temperatures during the accumulation and ablation periods, precipitation during the accumulation period, and maximum snow depth during April based on data from the Góriz meteorological station (1983 to 2014). Boxplots at the right of each panel show the interannual variability during the last 3 years of the study period (2011/12, 2012/13, and 2013/14) when terrestrial laser scanning measurements were available. Box: 25th and 75th percentiles, bars: 10th and 90th percentiles, dots: 5th and 95th percentiles, black line: median, red line: average.

**Figure 3.** Interannual fluctuations of minimum and maximum air temperatures during the accumulation and ablation periods and precipitation during the accumulation period at the Aragnouet, Canfranc, Mediano (only air temperature) and Pineta (only precipitation) stations for 1955-2013. Numbers give the Tau-b values of the trends. Asterisks indicate statistically significant trends ( $p < 0.05$ )

**Figure 4.** Photographs of the Monte Perdido Glacier during late summer in 1981 and 2011.

**Figure 5.** Surface elevation change in the upper and lower Monte Perdido Glacier from 1981 to 1999 and from 1999 to 2010 based on comparison of DEMs.

**Figure 6.** Surface elevation change based in the upper and lower Monte Perdido Glacier based on terrestrial laser scanning from September of 2011 to 2012 (Fig. 5A), 2012 to 2013 (Fig 5B), 2013 to 2014 (Fig. 5C), and 2011 to 2014 (Fig. 5D).

**Figure 7.** Surface elevation changes over the whole glacier, lower glacier, and upper glacier for the same 4 time periods examined in Figure 5. Box: 25th and 75th percentiles, black line: median, red line: average, bars: 10th and 90th percentiles, dots: 5th and 95th percentiles.

**Table 1.** Tau-b values of the trends for the period 1983-2013 for air temperature and precipitation in the analyzed stations. Asterisks indicate statistically significant trends ( $p < 0.05$ ). Bold numbers are statistically significant differences in the medians of the period 1983-1999 and 2000-2010 according to the Mann-Whitney test.

	Aragnouet			Canfranc			Mediano		Pineta	Góriz		
	Tmx	Tmn	Precip	Tmx	Tmn	Precip	Tmx	Tmn	Precip	Tmx	Tmn	Precip
<b>January</b>	0.08	0.02	0.04	-0.03	-0.13	0.03	0.06	0.04	0.06	0.07	0.11	0.02
<b>February</b>	0.04	0.06	0.02	0.05	-0.01	-0.08	0.03	-0.03	<b>0.39*</b>	0.04	0.02	0.00
<b>March</b>	0.11	0.11	0.14	0.03	-0.03	0.26	-0.02	0.03	0.31	0.02	0.06	0.20
<b>April</b>	<b>0.28*</b>	0.25	0.08	0.24	0.19	-0.15	0.02	0.12	0.02	0.15	0.21	-0.17
<b>May</b>	0.23	0.24	0.31*	0.30*	0.18	0.14	-0.01	0.04	0.12	<b>0.34*</b>	<b>0.33*</b>	0.27
<b>June</b>	<b>0.28*</b>	<b>0.31*</b>	0.14	<b>0.35*</b>	<b>0.47*</b>	0.04	0.09	-0.05	0.10	<b>0.32*</b>	0.25*	-0.05
<b>July</b>	-0.12	0.06	0.13	0.11	0.15	0.16	-0.07	-0.21	0.15	-0.07	-0.05	-0.11
<b>August</b>	0.07	0.13	-0.02	-0.02	0.01	0.03	-0.12	-0.25	0.32	0.10	0.07	-0.02
<b>September</b>	0.05	0.05	0.02	-0.06	-0.23	0.10	-0.18	-0.23	0.10	0.01	-0.02	0.04
<b>October</b>	0.08	0.19	0.19	0.06	0.04	0.14	0.04	-0.14	0.08	0.01	0.04	0.11
<b>November</b>	-0.06	-0.06	0.18	-0.18	-0.23	0.10	-0.08	<b>-0.30*</b>	-0.02	-0.11	-0.09	0.00
<b>December</b>	-0.15	-0.10	-0.03	<b>-0.37*</b>	-0.42*	0.08	-0.25	-0.23	0.13	-0.27*	-0.23	-0.06
<b>Accumulation period</b>	0.10	0.11	0.12	0.04	0.11	0.01	-0.22	-0.22	0.00	0.06	0.15	0.05
<b>Ablation period</b>	0.10	0.10		0.17	0.11		-0.26	-0.26		0.13	0.12	

**Table 2.** Surface area (ha), change of surface area (ha), and annual rate of surface area loss ( $\text{ha yr}^{-1}$ ) of the Monte Perdido Glacier.

	Surface Area			Change of Surface Area	
	1981	1999	2006	1981-1999	1999-2006
Upper glacier (ha)	8.30 $\pm$ 0.27	6.80 $\pm$ 0.25	4.80 $\pm$ 0.21	-1.50 $\pm$ 0.52	-2.00 $\pm$ 0.46
Lower glacier (ha)	40.10 $\pm$ 0.59	37.10 $\pm$ 0.62	33.70 $\pm$ 0.54	-3.00 $\pm$ 1.21	-3.40 $\pm$ 1.16
Entire glacier (ha)	48.40 $\pm$ 0.65	43.90 $\pm$ 0.62	38.50 $\pm$ 0.58	-4.50 $\pm$ 1.27	-5.40 $\pm$ 1.20
Entire glacier ( $\text{ha yr}^{-1}$ )				-0.25 $\pm$ 0.07	-0.77 $\pm$ 0.17









Figure 1.




**Figure 2.**




**Figure 3.**




**Figure 4.**



**Figure 5.**



**Figure 6.**



**Figure 7.**