

Dear Dr. Demidov,

Thank you for your edits. The tables are in good shape now.

The only problem that I see is with respect to Skakun et al. (in review) and the data for river and tributary water of the Grøn River. The methods section indicates that your team did all of the sampling, but the table descriptions indicate that there are additional data from Skakun et al. This needs to be made more transparent.

It would be best if your article is not contingent on another manuscript that is not published and in review. Manuscript preparation guidelines for authors indicate in the References section that "Works cited in a manuscript should be accepted for publication of published already." However, if there is no alternative, you can cite work that is "in review", but this is not ideal.

Please either make it more clear in the methods section that you have no alternative to using this data and add the appropriate citation, or contact Skakun et al. and make arrangements to publish the data here (they can then refer to your published work).

I regret that I did not catch this earlier, but there is time as you are waiting for the DOI to be assigned to your Original data.

Best regards,

Peter

Dear Peter Morse,

we apologize for our delayed reply due to travel in the last two weeks. Following your latest comments, we checked the recent publication stage of the Skakun et al. manuscript and are happy to report that this publication got accepted and is planned to be published in the first volume of Лёд и Снег in 2020. The according citation reads now:

Skakun, A.A., Chikhachev, K.B., Ekaykin, A.A., Kozachek, A.V., Vladimirova, D.O., Veres, A.N., Verkulich, S.R., Sidorova, O.R., Demidov, N.E.: Stable isotopic content of atmospheric precipitation and natural waters in the vicinity of Barentsburg (Svalbard) (Изотопный состав атмосферных осадков и природных вод в районе Баренцбурга (Шпицберген)), Ice and Snow (Лёд и Снег), 60(1), accepted, <https://ice-snow.igras.ru/jour/issue/archive, 2020> (in Russian).

Because the Лёд и Снег journal (<https://ice-snow.igras.ru/jour/issue/archive>) does not provide 'in press' (online available) publications prior to final production, we unfortunately cannot provide any better information yet. However, we hope this reference as accepted paper is now in accordance with the guidelines of The Cryosphere. If there will be more information available such as page numbers and DOI before the final production of our ms, we will include those during the proofreading process latest.

We furthermore added the following sentence to section 3.3 Stable water isotopes: "Additional samples from surface waters (Grøn River and tributaries) and precipitation (2016-2017) were likewise analysed and are presented in detail by Skakun et al. (2020)." to make clear that precipitation and surface water data refer to the study by Skakun et al.

We updated the revised manuscript accordingly and further added the data DOI from the PANGAEA database for our original dataset.

Best regards, Nikita Demidov and Sebastian Wetterich

# Geochemical signatures of pingo ice and its origin in Grøndalen, West Spitsbergen

Nikita Demidov<sup>1</sup>, Sebastian Wetterich<sup>2</sup>, Sergey Verkulich<sup>1</sup>, Aleksey Ekaykin<sup>1,3</sup>, Hanno Meyer<sup>2</sup>, Mikhail Anisimov<sup>1,3</sup>, Lutz Schirrmeister<sup>2</sup>, Vasily Demidov<sup>1</sup>, Andrew J. Hodson<sup>4,5</sup>

<sup>1</sup>Arctic and Antarctic Research Institute, Bering St. 38, 199397 St. Petersburg, Russia

<sup>2</sup>Alfred Wegener Institute Helmholtz Center for Polar and Marine Research, Telegrafenberg A45, D-14473 Potsdam, Germany

<sup>3</sup>St. Petersburg State University, 10<sup>th</sup> Line 33-35, 199178 St. Petersburg, Russia

<sup>4</sup>University Centre in Svalbard, N-9171 Longyearbyen, Norway

<sup>5</sup>Western Norway University of Applied Sciences, Røyrgata 6, N-6856 Sogndal, Norway

*Correspondence to:* Nikita Demidov (nikdemidov@mail.ru)

**Abstract.** Pingos are common features in permafrost regions that form by subsurface massive-ice aggradation and create hill-like landforms. Pingos on Spitsbergen have been previously studied to explore their structure, formation timing, connection to springs as well as their role in post-glacial landform evolution. However, detailed hydrochemical and stable-isotope studies of massive ice samples recovered by drilling has yet to be used to study the origin and freezing conditions in pingos. Our core record of 20.7 m thick massive pingo ice from Grøndalen differentiates into four units: two characterised by decreasing  $\delta^{18}\text{O}$  and  $\delta\text{D}$  and increasing  $d$  (units I and III), and two others show the opposite trend (units II and IV). These delineate changes between episodes of closed-system freezing with only slight recharge inversions of the water reservoir, and more complicated episodes of groundwater freezing under semi-closed conditions when the reservoir got recharged. The water source for pingo formation shows similarity to spring water data from the valley with prevalent  $\text{Na}^+$  and  $\text{HCO}_3^-$  ions. The sub-permafrost groundwater originates from subglacial meltwater that most probably followed the fault structures of Grøndalen and Bøhmdalen. The presence of permafrost below the pingo ice body suggests that the talik is frozen, and the water supply and pingo growth are terminated. The maximum thaw depth of the active layer reaching the top of the massive ice leads to its successive melt with crater development and makes the pingo extremely sensitive to further warming.

## 1 Introduction

Pingos are widespread landforms that occur within the permafrost zone of the Earth (Grosse and Jones, 2011) and likely on Mars (Burr et al., 2009). The distribution of pingos is closely linked to permafrost history, underground hydrology and climate conditions. Two pingo types are commonly distinguished, which are (1) hydrostatic (closed) system and (2) hydraulic (open)

system pingos (van Everdingen, 1998). Hydrostatic pingos form when a distinct volume of pore water in water-saturated deposits expulses towards the freezing front and freezes. Hydraulic pingos occur where pressurised groundwater inflow from within or below permafrost freezes at the freezing front. Both processes result in a massive ice body composed of injection (intrusive) and/or segregation ice that heaves the surface and form conical elevations (Mackay, 1979). Pingos have a characteristic elliptical to circular planar shape reaching diameters of up to several hundred meters and heights of up to several dozen meters.

Pingos are rather well studied in Alaska and Canada in terms of formation (e.g. Mackay, 1962), structure (e.g. Yoshikawa et al., 2006) and distribution (e.g. Jones et al., 2012). Pingo growth and decay rates, pingo age, and past distribution of those landforms have been used for the reconstruction of past periglacial landscape conditions (e.g. Mackay, 1986). Pingo ice and sedimentary inventories were investigated and furthermore employed in palaeoenvironmental reconstructions in the Mackenzie Delta in Canada (Hyvärinen and Ritchie, 1975), on Seward Peninsula in Alaska (Wetterich et al., 2012; Palagushkina et al., 2017), in Siberia (Ulrich et al. 2017; Chizhova and Vasil'chuk, 2018; Wetterich et al., 2018), where they are called 'bulgunniakhs', and in northern Mongolia (Yoshikawa et al., 2013; Ishikawa and Yamkhin, 2016).

Pingos on Spitsbergen (76 identified pingos by Hjelle, 1993) are commonly attributed to open-system conditions (Liestøl, 1977), and have previously been studied by geophysical techniques (e.g. Ross et al., 2005; Rossi et al., 2018) and combined chemical and physical investigation of the properties of pingo ice (e.g. Yoshikawa, 1993; Yoshikawa and Harada, 1995). Unlike in other permafrost regions, stable isotope properties of the pingo ice were rarely studied on Spitsbergen (Matsuoka et al., 2004).

Yoshikawa and Harada (1995) proposed three formation mechanisms for open-system pingos on Spitsbergen. They differentiate into group I pingos fed by sub-permafrost groundwater along geologic faults, group II pingos fed by artesian flow of migrating sub-glacial groundwater mainly in river valley positions (*in sensu* Liestøl, 1977) and group III pingos (*in sensu* Yoshikawa and Harada, 1995). The latter are found in nearshore environments of post-glacial isostatic uplift and fed through small-scale discontinuities 'groundwater dikes' or taliks in aggrading permafrost within in marine deposits (Yoshikawa and Harada, 1995). Yoshikawa and Harada (1995) regard the pingos of the Grøndalen as ancient group III pingos, which formed in Holocene marine sediments quickly after sea regression. However, as Liestøl (1996) recognised 'In connection with formation of pingos there are a great many unsolved questions. Drillings and temperature measurements through the pingo mound and also through the surrounding permafrost are needed before the problems can be better understood'. This is still valid due to the scarcity of data from the inner structure of pingos because of rarely undertaken drilling. To shed light on the Grøndalen pingo formation in comparison to other pingo records from Spitsbergen, we here present the stable isotope and hydrochemical inventories of an entirely cored pingo in Grøndalen near Barentsburg (West Spitsbergen, Fig. 1). Additional data for consideration of postglacial landform evolution in the Grøndalen were obtained from neighbouring sedimentary cores. The aims of our study are (1) to capture the morphometric, cryolithologic and thermic properties of the Grøndalen pingo in comparison to other pingos on Spitsbergen and (2) to reconstruct the formation conditions of the pingo massive ice by applying stable isotope and hydrochemical approaches.

## 2 Study area

The Grøndalen study area on the western coast of Nordenskiöld Land (West Spitsbergen) is in about 10 km distance south-east of Barentsburg in whose vicinity the Russian Scientific Arctic Expedition on Spitsbergen Archipelago (RAE-S), maintains ground temperature and active-layer monitoring sites of the Global Terrestrial Network for Permafrost (GTN-P) and the Circumpolar Active Layer Monitoring (CALM) programs (Demidov et al., 2016; Christiansen et al., 2019). The Grøndalen is a trough valley in bedrock of Middle Jurassic–Palaeogene argillite and sandstone (Geological map Svalbard, 1991). Late Pleistocene and Holocene deposits in the lower part of Grøndalen reach more than 20 m thickness and likely represent sedimentation since at least the last glacial maximum (Verkulich et al., 2018). The mountains surrounding the valley reach up to 700–800 m above sea level (asl). The Grøn River is fed by many tributaries, which collect meltwater discharge from small hanging glaciers. In the upper valley part occur two larger glaciers, Tavlebreen and Passfjellbreen, as well as their terminal moraines.

The meteorological station in Barentsburg (WMO station #20107) at 75 m asl recorded a mean annual air temperature of  $-2.2^{\circ}\text{C}$  and a mean annual precipitation of 849 mm for 2016–2017. The ground temperatures reach  $-2.37^{\circ}\text{C}$  at 15 m depth below surface (bs) and the active layer thickness at the CALM site (3 km north of Barentsburg) measured in the end of September 2016 varied from 1.15 to 2.60 m with an average of 1.56 m (Demidov et al., 2016). Permafrost thickness in Barentsburg area varies along with morphology from 8–10 m near the seashore up to 300–450 m in the mountain and upland areas. According to measurements in the central part of Grøndalen the mean annual ground temperature amounts to  $-3.56^{\circ}\text{C}$  at depth of 15 m (borehole #8).

In the central part of Grøndalen, a group of seven pingos occurs reaching diameters of 150 to 300 m and heights above their surroundings from 6.5 to 12.5 m (Fig. 1b). They are informally named as follows (west to east on Fig. 1b): Nori, Ori, Dori, Fili, Kili, Oin, Gloin after John R.R. Tolkien (1954–1955). The pingo Fili of 9.5 m maximum height (56 m asl) was chosen for drilling. It shows a clearly defined uppermost water-filled degradation crater of 5.5 m depth. The maximum water depth of the lake was  $>1$  m. At the point of drilling, the ice thickness was 0.15 m. The drilled Fili pingo is to the northeast and the southwest connected to Dori pingo and Kili pingo (Fig. 1b) and its slope shows radial dilation cracks.

## 25 3 Materials and methods

### 3.1 Drilling and ground temperature measurements

The drilling of the Fili pingo in May 2017 started from the surface of central crater at 52.5 m asl and reached a depth of 11.5 m bs (core #9,  $77.99355^{\circ}\text{N}$ ,  $14.66211^{\circ}\text{E}$ ). The borehole was conserved by installing a plastic tube down to 3 m bs to prevent meltwater flow from the active layer during thaw season and tightly closed by a lid to prevent rain or snow input. However, the first 0.5 m core of the re-drilling in spring 2018 were neglected to account for any unexpected contamination. The drilling was continued in the same borehole down to a depth of 25 m bs. The drilling position on top of the pingo was chosen in its

centre to assure that the centroid of the pingo ice body was captured in the core. The coring angle was held vertical. Additional cores were drilled on the pingo top reaching a depth of 12 m (core #10, from 56 m asl, 77.99332 °N, 14.66114 °E) and in the pingo surroundings reaching a depth of 6 m (core #11, from 47 m asl, 77.99531 °N, 14.66538 °E). Continuous temperature measurements in borehole #9 on Fili pingo were installed on 15 May 2018 using a 15-m long Geo Precision logger chain (M-Log5W cable) equipped with sensors every 0.75 m.

The cores were obtained with a portable gasoline-powered rotary drilling rig (UKB 12/25, Vorovskiy Machine Factory, Ekaterinburg, Russia) that allows performing operations without impact on the ecosystem. The device uses no drilling fluid, and relies on maintaining the frozen condition of the core for stratigraphic integrity and to prevent downhole contamination of the biogenic and sedimentological characteristics of the core. Core diameters were 109 mm for the upper parts and 73 mm for the lower ones. The core pieces were lifted to the surface every 30–50 cm. After documentation and cryolithological description (French and Shur, 2010) core pieces were sealed. The ice and permafrost deposits were sampled from within intervals of about 0.5 to 1 m for hydrochemical and stable isotope analysis. Ice samples were kept frozen for transportation while sediment samples were kept unfrozen.

To obtain spring water samples at the foot of the Oin pingo near the right bank of the Grøn River drilling was performed through ca. 1 m of ice to pressurised water beneath an ice blister that formed at the spring source on 20 April 2018. Samples were then taken of the water discharging through the 5 cm drill hole.

### 3.2 Mapping

The topographic mapping on 21 August 2018 covered an area of 0.25 km<sup>2</sup> using Global Navigation Satellite System (GNSS) Sokkia GRX2 devices and an Archer 2 base station. The obtained coordinates have planar accuracy of 1.5 cm and altitude accuracy of 2.5 cm.

### 3.3 Stable water isotopes

The concentration of ground ice water isotopes ( $\delta D$  and  $\delta^{18}O$ ) was measured at Climate and Environmental Research Laboratory (CERL, AARI St. Petersburg, Russia) using a Picarro L2120-*i*analyzer. The working standard (SPB-2), measured after every five samples, was made of the distilled St. Petersburg tap water and calibrated against the IAEA standards VSMOW-2, GISP and SLAP-2. The reproducibility of results defined by re-measurements of randomly chosen samples was 0.08 ‰ for  $\delta^{18}O$  and 0.4 ‰ for  $\delta D$ , which is two orders of magnitude less than the common natural variability of the pingo ice isotopic composition and thus satisfactory for the purposes of the study. Additional samples from surface waters (Grøn River and tributaries) and precipitation (2016-2017) were likewise analysed and are presented in detail by Skakun et al. (2020). ~~Additional~~ Samples from Grøndalen spring water were collected as unfiltered 20 ml aliquots in a screw-top HDPE bottle and analysed 6 times using a Picarro V 1102-I and a 2.5 µl injection volume with a precision error of 0.1 ‰ for  $\delta^{18}O$  and 0.3 ‰ for  $\delta D$ . The  $\delta^{18}O$  and  $\delta D$  values are given as per mil (‰) difference to the Vienna Standard Mean Ocean Water (VSMOW) standard. The deuterium excess ( $d$ ) is calculated as  $d = \delta D - 8\delta^{18}O$  (Dansgaard, 1964).

### 3.4 Hydrochemistry

Sedimentary permafrost samples of cores #9, #10 and #11 were dried and sieved at 1 mm at the analytical laboratory of RAE-S, Barentsburg. Afterwards about 20 g of the dry sediment were suspended in 100 ml de-ionised water and filtered through 0.45 µm nylon mesh within 3 minutes after stirring to estimate the ion content after water extraction. Electrical conductivity (EC measured in µS cm<sup>-1</sup>) and pH values were estimated with Mettler Toledo Seven Compact S 220. EC values were transformed automatically by the instrument in to general ion content values given as mg l<sup>-1</sup>. Major anions and cations in the water extracts were analysed by ion chromatography (Shimadzu LC-20 Prominence) equipped with the conductometric detector Shimadzu CDD-10AVvp and ion exchange columns for anions (Phenomenex Star-ion A300) and for cations (Shodex ICYS-50). Likewise melted pingo ice samples from core #9, snow and Grøn River water were analysed for pH, EC and ion composition after filtration through 0.45 µm nylon mesh ([Skakun et al., 2020](#)). Spring water analysis of anions Cl<sup>-</sup>, NO<sub>3</sub><sup>-</sup>, PO<sub>4</sub><sup>3-</sup> and SO<sub>4</sub><sup>2-</sup> employed a Dionex ICS90 ion chromatography module calibrated in the range 0 – 2 mg l<sup>-1</sup> for NO<sub>3</sub><sup>-</sup> and PO<sub>4</sub><sup>3-</sup> and in the range 0 – 50 mg l<sup>-1</sup> for Cl<sup>-</sup> and SO<sub>4</sub><sup>2-</sup> (which required dilution). Precision errors were between 0.9 % (SO<sub>4</sub><sup>2-</sup>) and 1.6 % (PO<sub>4</sub><sup>3-</sup>), whilst the detection limit (three times the standard deviation of ten blanks) was ≤ 0.05 mg l<sup>-1</sup>. Alkalinity was deduced by headspace analysis of an acidified (pH 1.7) sample of 10 ml immediately after return to the laboratory using a PP Systems EGM 4 infra-red gas analyser (precision errors 4.5%). Immediately in the field, the spring water outflow was analysed using Hach HQ40D meters for electrical conductivity and pH by gel electrode. To prevent the electrodes from freezing, this water was also injected by syringe into a pre-heated flow cell which maintained the water at about 7 °C. EC values in µS cm<sup>-1</sup> were transformed into general ion content values given as mg l<sup>-1</sup> by multiplication on 0.65.

## 4 Results

### 4.1 Ground temperature

The ground temperatures in borehole #9 on 12 September 2018 are shown in Fig. 2. At the lowermost sensor at 14.25 m bs the ground temperature reached –2.5 °C and varied at the same depth between –2.5 and –2.37 °C in the period from 15 May to 12 September 2018. The 0 °C point was observed at 1.5 m bs at the upper border of the massive pingo ice showing that the active-layer maximum depth reached the massive ice on 12 September 2018.

### 4.2 Cryolithology

#### 4.2.1 Core #9

The 25 m long core #9 drilled from the pingo top crater exposed cover and basal sedimentary horizons enclosing massive pingo ice (Fig. S1). From 0 to 1.5 m bs gravelly loam was found, which is assumed origin from the pingo top and moved downslope by cryoturbation and solifluction. Below this redeposited cover layer from 1.5 to 12 m bs transparent massive ice without any inclusions is observed. The visible air bubble content reaches up to 10 percent per volume (vol%) in single ice

layers. In this particular layer and in all other layers of pingo massive ice bubbles are spherical and irregularly distributed. Most common are bubbles with diameters near 1 mm but some bubbles reach diameters up to 5 mm. Between 12 and 22.2 m bs the pingo ice remains transparent, but contains layers with 1-2 to 10-20 mm long large dark silty flakes in subvertical orientation (up to 0.5 vol%). Alternating layers include rounded air bubbles (up to 10 vol%). The total thickness of the massive pingo ice amounts to 20.7 m. Its lower contact to the basal deposits is well defined in the core. Massive pingo ice near the contact was not rich in air bubbles and had small admixture of previously mentioned dark silty flakes. The lowermost part of the massive pingo ice in core #9 was found at depth of 22.2 m bs. Below down to a depth of 25 m bs dark clay with regular reticulate and irregular reticulate cryostructures (ice lenses 2 to 20 mm thick) was found in the core. At 23.8-24.3 m bs ice lenses were absent but 2-4 mm long lenses of black clay material were present. At 22.3-23.5 m bs and at 23.7-23.8 m bs layers of transparent ice without inclusions and without air bubbles were found.

#### 4.2.2 Core #10

The core #10 drilled on top of the crater rim down to 12 m bs exposes sedimentary horizons (Fig. S1). The uppermost part from 0 to 2.5 m bs includes the modern top soil at 0 to 0.1 m bs with living shrub material and a buried soil formation at 0.25 to 0.4 m bs with decomposed similar shrub material. The minerogenic material is present by fine sand and loam including gravel. The cryostructures are wavy lenticular with ice lenses up to 2 cm thick. Toward 2.5 m bs the clay content increases as the gravel content decreases. From 2.5 to 12 m bs, the clay shows subhorizontal lenticular cryostructures up to 2 cm thick and includes ice-oversaturated deposits and ice with admixture of clay at 4.7- 5.9 m bs, at 6.65-7.05 m bs and at 8.2-8.6 m bs although the massive ice of the pingo was not reached. This ice and ice oversaturated deposits contain also sporadic gravel particles. In the layer 8.2-8.6 m ice contained up to 10 vol% of spherical air bubbles with diameter near to 1 mm. At 5.9 to 6.2 m bs a layer of sand and gravel (up to 3 cm in diameter) with organic remains is observed.

#### 4.2.3 Core #11

The core #11 was drilled in the surroundings of the pingo and reached a depth of 6 m bs, and is composed of gravelly sand and loam with structureless cryostructures (Fig. S1).

### 4.3 Isotopic and hydrochemical properties of the massive pingo ice and spring water

According to trends in stable water isotopic composition of the massive ice obtained in core #9, four units are distinguished, which are unit I to unit IV (Fig. 2; Table 1).

Unit I (1.1-9.8 m bs) shows a down-core decreasing trend in  $\delta^{18}\text{O}$  and  $\delta\text{D}$  from  $-9.6$  to  $-16.8$  ‰ and from  $-68$  to  $-117$  ‰, respectively, while the  $d$  increases from 8 to 18 ‰. Small inversions are notable at depths of 3.5 and 6.5 m bs (Fig. 2). The freezing of unit I is clearly expressed by  $\delta^{18}\text{O}$ - $\delta\text{D}$  and  $\delta\text{D}$ - $d$  slopes of 6.7 and  $-0.2$ , respectively (Fig. 3). The ion composition of unit I is dominated by  $\text{Na}^+$  and  $\text{K}^+$  in cations and  $\text{Cl}^-$  and  $\text{HCO}_3^-$  in anions. Variations in total ion content (mean 22 mg  $\text{l}^{-1}$ ) are triggered by variations in  $\text{Na}^+$  (0-24 mg  $\text{l}^{-1}$ ),  $\text{Cl}^-$  (1-14 mg  $\text{l}^{-1}$ ) and  $\text{HCO}_3^-$  (1-40 mg  $\text{l}^{-1}$ ) concentrations (Fig. 2, Table 2) while

$\text{NO}_3^-$  and  $\text{SO}_4^{2-}$  contents vary little around  $1 \text{ mg l}^{-1}$  each.  $\text{Ca}^{2+}$  occurs solely in the lowermost part of unit I with low concentration. The pH varies between 6.6 and 7.9.

The isotopic composition of the pingo ice in unit II (9.8-16.1 m bs) exhibits down-core the opposite pattern as in unit I with increasing trend in  $\delta^{18}\text{O}$  and  $\delta\text{D}$  from  $-16.7$  to  $-11.1$  ‰ and from  $-116$  to  $-79$  ‰, respectively, while the  $d$  decreases from 17 to 10 ‰ reaching almost the isotopic composition of the upper part of unit I (Fig. 2). The  $\delta^{18}\text{O}$ - $\delta\text{D}$  slope of 6.6 is slightly lower as in unit I while the  $\delta\text{D}$ - $d$  slope of  $-0.2$  is very close to that of unit I (Fig. 3). The pH increases down-core from 7 to 8.8 as the ion content does from 14 to  $138 \text{ mg l}^{-1}$  (mean  $72 \text{ mg l}^{-1}$ , Table 2). The latter correlates to increasing concentrations of  $\text{Na}^+$ ,  $\text{Cl}^-$ ,  $\text{SO}_4^{2-}$  and  $\text{HCO}_3^-$ , while  $\text{NO}_3^-$  remains almost stable and  $\text{K}^+$  decreases (Fig. 2).

The stable isotope composition of unit III (16.1-20.8 m bs) resembles those of unit I with down-core decreasing  $\delta^{18}\text{O}$  and  $\delta\text{D}$  from  $-10.8$  to  $-15.2$  ‰ and from  $-77$  to  $-106$  ‰, respectively. The  $d$  increases from 9 to 15 ‰. An inversion occurs at depth of 19.9 m bs (Fig. 2). The  $\delta^{18}\text{O}$ - $\delta\text{D}$  and  $\delta\text{D}$ - $d$  slopes are almost the same as in unit II with values of 6.6 and  $-0.2$ , respectively (Fig. 3). The ion content reaches highest values up to  $428 \text{ mg l}^{-1}$  (mean of  $202 \text{ mg l}^{-1}$ , Table 2) in the lower part of unit III due to increased  $\text{Na}^+$ ,  $\text{Cl}^-$  and  $\text{HCO}_3^-$  concentrations, where also Mg occurs (Fig. 2). The pH varies between 7.8 and 8.9.

The lowermost unit IV (20.8-22.2 m bs) shows down-core increase in  $\delta^{18}\text{O}$  and  $\delta\text{D}$  and decrease  $d$  (Fig. 2) as unit II. The slopes of  $\delta^{18}\text{O}$ - $\delta\text{D}$  ( $-7.26$ ) and  $\delta\text{D}$ - $d$  ( $-0.23$ ) are the lowest all pingo ice units (Fig. 3). The mean ion content of  $53 \text{ mg l}^{-1}$  is low (Table 2) due to largely reduced  $\text{Na}^+$ ,  $\text{K}^+$ ,  $\text{HCO}_3^-$  and  $\text{Cl}^-$  concentration (Fig. 2). The mean pH amounts to 7.8.

The overall pattern of the down-core isotopic composition of the pingo ice differentiates into two modes of decreasing  $\delta^{18}\text{O}$  and  $\delta\text{D}$  and increasing  $d$  in units I and III and the opposite trends in units II and IV. The contents of  $\text{Na}^+$ ,  $\text{Cl}^-$  and  $\text{HCO}_3^-$  ions increase from unit I to III, while  $\text{K}^+$  decreases from unit I to II and increases again in unit III,  $\text{NO}_3^-$  and  $\text{SO}_4^{2-}$  show rather low variation, and  $\text{Mg}^{2+}$  and  $\text{Ca}^{2+}$  occur only occasionally with concentrations above  $0.25 \text{ mg l}^{-1}$ .

The spring water sampled in the vicinity of the Oin pingo in 2018 is characterized by  $\delta^{18}\text{O}$  of  $-13.01$  ‰,  $\delta\text{D}$  of  $-93.5$  ‰ and  $d$  of  $10.6$  ‰ (Table 1). The ion content amounts to  $1192 \text{ mg l}^{-1}$ , with predominance of  $\text{HCO}_3^-$  in anions (as indicated by the high alkalinity  $2.2 \text{ mM l}^{-1}$ ), while  $\text{Cl}^-$  and  $\text{SO}_4^{2-}$  are found in concentrations of 15.3 and  $3.8 \text{ mg l}^{-1}$  respectively. The pH in the spring amounts to 8.8 (Table 2).

## 4.4 Hydrochemical properties of sedimentary water extracts

### 4.4.1 Core #9

The hydrochemical signature of deposits underlying the massive ice of the pingo at 22.2 to 25 m bs is notable for high ion content reaching up to  $1335 \text{ mg l}^{-1}$  and the prevalence of  $\text{Na}^+$  and  $\text{HCO}_3^-$  ions. (Fig. 4a, Table 3). Distinct ion content variations are driven by  $\text{Na}^+$  and  $\text{K}^+$  cations and  $\text{HCO}_3^{2-}$  and  $\text{Cl}^-$  anions.  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  have not been found and the anion composition resembles those of unit III. The pH is alkaline and varies between 9.2 and 9.9.

### 4.4.2 Core #10



Core #10 drilled at the uppermost position of the pingo shows a different hydrochemical composition compared to the sedimentary water extracts than the bottom sediments of core #9 drilled nearby. The ion content is about nine times lower with mean values of about 99.6 mg l<sup>-1</sup> in core #10 and of about 1335 mg l<sup>-1</sup> in core #9 (Fig. 4a, b). The composition of major ions is also different with predominant SO<sub>4</sub><sup>2-</sup> and HCO<sub>3</sub><sup>-</sup> for anions while prevalent cations are still Na<sup>+</sup> and K<sup>+</sup>. It is notable that Ca<sup>2+</sup> and Mg<sup>2+</sup> reach mean values of about 22 mg l<sup>-1</sup> and 2 mg l<sup>-1</sup>, respectively (Table 3). The mean pH is neutral with 7.3±0.5.

#### 4.4.3 Core #11

The hydrochemical composition of major ions in core #11 generally resembles those of core #10 (Fig. 4b, c) although the ion content is much lower with a mean value of 38 mg l<sup>-1</sup> driven by more than two times lower SO<sub>4</sub><sup>2-</sup>, ten times lower Cl<sup>-</sup>, six times lower Na<sup>+</sup> and seven times lower Ca<sup>2+</sup> (Table 3). The pH is similar to those of core #10 with mean 7.2±0.3.

## 5 Discussion

### 5.1 Water sources of the massive pingo ice in Grøndalen

Following the current hypotheses on pingo growth on Spitsbergen, there are three possible main water sources for pingo massive ice formation, which are deep sub-permafrost groundwater for group I pingos connected to geologic fault structures, sub-permafrost groundwater fed by sub-glacial melt for group II pingos and marine-originated groundwater for group III pingos (Matsuoka et al. 2004). Marine sources are assumed for hydraulic connections between groundwater of uplifted valleys after deglaciation and the sea (Yoshikawa and Harada, 1995). Sea ice, which is a result of seawater freezing is known to be sodium-chloride-dominated and shows ion contents between 2000 and 20000 mg l<sup>-1</sup> (Shokr and Sinha, 1995; Nazintsev and Panov, 2000) depending on freezing velocity, temperature and age. The massive ice of the pingo in Grøndalen shows prevalent Na<sup>+</sup>-HCO<sub>3</sub><sup>-</sup> contents and ion content with maximum values of 428 mg l<sup>-1</sup> (mean of 78±101 mg l<sup>-1</sup>, Table 2). Thus, marine sources for the pingo massive ice are excluded and the previous assignment of the Grøndalen pingos to ancient group III pingos by Yoshikawa and Harada (1995) seems unlikely. Precipitation and surface waters in Grøndalen have lower ion contents and different composition if compared to the pingo massive ice (Table 2), which also excludes these sources as the main ones for the pingos of Grøndalen. The role of artesian flow resulting from the migration of sub-glacial groundwater for pingo formation on Spitsbergen has been previously studied by Liestøl (1977, 1996) and Yoshikawa and Harada (1995). The original hydrochemical signature of water released from glacial melt is certainly altered by subsurface migration through various deposits. Pressurised spring water from beneath an ice blister sampled in 2018 shows predominance of HCO<sub>3</sub><sup>-</sup> in anions and ion content of 1192 mg l<sup>-1</sup> (Table 2). Furthermore, in 1921 the Norwegian geologist Anders K. Orvin described a spring in Grøndalen and sampled spring water in 1926 (Orvin, 1944), approximately at the northern side of today's Gloin pingo (Fig. 1). This data from spring found in 2018 and 1926 seem meaningful to explore the potential water source for the pingo formations. The spring water analysed by Orvin was characterised by prevalent Na<sup>+</sup> and HCO<sub>3</sub><sup>-</sup> ions, which is typical for freshwater hydrogeological structures below permafrost (Romanovskiy, 1983), and an ion content of 879 mg l<sup>-1</sup> (Table 2). The

sedimentary water-extract data from deposits underlying the massive ice shows likewise prevalent  $\text{Na}^+$  and  $\text{HCO}_3^-$  ions (Table 3). The similarity of the ion compositions of the spring water and the water extract of deposits underlying the massive ice to those of the Fili pingo ice is striking although the absolute concentrations are much higher in the spring (1192  $\text{mg l}^{-1}$  in 2018 and 879.2  $\text{mg l}^{-1}$  in 1926) than in the massive ice (mean of all core#9 units  $79.0 \pm 102.4$ ). This difference between the ion concentrations in the spring water and in the pingo ice is most likely explained by salt expulsion during freezing, which is typical for ice formation from fresh groundwater (Romanovskiy, 1983). We therefore conclude that the groundwater feeding the springs observed by Orvin (1944) and later within this study represents the main source water for the massive pingo ice. This interpretation is further supported by the chain-like distribution of spring and pingos from east to west across the Grøndalen (Fig. 1b), which might delineate connectivity for sub-permafrost groundwater by the fault zone further protruding towards the Bøhmdalen.

It was suggested that groundwater recharge in Spitsbergen is related to the warm-based glaciers as there are no other potential taliks where groundwater recharge can occur (Orvin, 1944; Liestøl, 1976). Glaciers on the mounts surrounding the valley occur just several kilometres to the north from the Grøndalen pingos (Fig. 1), namely Irabreen and Stolleybreen. The water temperature is close to 0 °C when it is recharged below the glacier. Taking into account geothermal gradient of ~2 °C per 100 m in the coal survey wells in Barentsburg closest to the studied pingo (Ershov, 1998) and the fact that the base of surrounding glaciers is approximately at 500 m asl and pingos and spring are located between 100 and 50 m asl, geothermal heat will increase water temperature melted on the glacier base during its transit through the aquifer to the spring location directly to 9 °C as was observed by Orvin in 1921 (Orvin, 1944). Together with low salt content of the spring water, this observation allow suggesting that the source of sub-permafrost water discharged by the spring (and responsible for pingo formation) was sub-glacial melt heated and slightly salted during its rather fast transport through the aquifer to the discharge area.

## 5.2 Stable water isotope composition of the pingo massive ice in Grøndalen

Assuming a conical geometry of the pingo ice body that grew equally to all sides, the chosen central drilling position on top of the pingo and the strictly vertical drilling allowed us to capture the freezing stages of the massive ice. Variations in the isotopic composition of the four massive pingo-ice units and between them might be explained by three main controls. Firstly, isotopic variations in the pingo ice might correspond to differing water sources migrating towards the freezing front during different periods of ice formation. Secondly, the source water of the pingo ice was constant, but had distinctly differing isotopic signatures over time. And thirdly, the isotopic variations of the pingo ice represent changes in closed, (semi-closed) and open system condition, i.e. freezing of a fixed or a (partly) renewed water volume. Estimations of pingo growth rate in Siberia and North America may reach values on the order of decimetres per year (Mackay, 1979; Chizhova and Vasil'chuk, 2018). Assuming the Fili pingo has a similarly fast growth and rather short period of formation, it is likely that there were little to no changes in isotopic composition of the water source. Thus, we assume the second controls on isotopic composition of the Fili pingo massive ice of less importance. The isotopic composition of spring water sampled in Grøndalen in 2018 shows -13.01 ‰ in  $\delta^{18}\text{O}$ , -93.5 ‰ in  $\delta\text{D}$  and a  $d$  of 10.6 ‰, which is very close to the respective mean values of the massive pingo ice (all

units) of  $-12.56 \pm 2.14\text{‰}$  in  $\delta^{18}\text{O}$ ,  $-89.0 \pm 14.2\text{‰}$  in  $\delta\text{D}$  and a  $d$  of  $11.5 \pm 4.1\text{‰}$  (Table 1, Figure 3b, c). This observation makes it likely that the sub-permafrost groundwater feeding the spring also maintained the massive pingo-ice formation. Thus, the most probable explanation for the observed isotopic composition of the massive pingo ice relates to subsurface hydrologic conditions, i.e. the system state of closed or open conditions, which are further controlled by local groundwater pressure and the position of the permafrost table. Concurrent changes in the system character from closed to open as deduced from the isotopic and chemical compositions of the pingo ice units are outlined and discussed below.

The isotopic stratification of the massive pingo ice differentiates into four stages of pingo growth. The earliest stage of massive ice formation is represented in unit I (1.5-9.8 m bs). The down-core strong decline within unit I by about  $7\text{‰}$   $\delta^{18}\text{O}$ ,  $49\text{‰}$  in  $\delta\text{D}$  accompanied by a strong rise of  $10\text{‰}$  in  $d$  (Fig. 2) indicates a high near-surface temperature gradient, fast freezing and fast formation the about 8-m-thick unit I. If compared to a closed-system freezing model of Ekaykin et al. (2016), the down-core isotopic depletion in unit I is close to the modelled one (Fig. 5a) if an initial isotopic composition of  $-12.6\text{‰}$  in  $\delta^{18}\text{O}$  and  $-88\text{‰}$  in  $\delta\text{D}$  is assumed. This is much lower than the modern mean annual precipitation values in the Barentsburg region with  $-9.0 \pm 4.2\text{‰}$  in  $\delta^{18}\text{O}$  and  $-64 \pm 30\text{‰}$  in  $\delta\text{D}$ , and closer to mean values of the Grøn River and its tributaries with about  $-11.7 \pm 0.3\text{‰}$  in  $\delta^{18}\text{O}$  and  $-78 \pm 3\text{‰}$  in  $\delta\text{D}$  (Table 1). Thus, if precipitation was the main source of the massive ice, its onset took place during a colder period than today. More likely, the underground water source feeding the spring near the pingo was the same source for the massive pingo ice. According to the model, the lowermost (last formed) ice of unit I at a depth of 9.6 m bs corresponds to  $85\text{‰}$  frozen water of the initial volume. If so the remaining unfrozen water would have had a highly depleted composition of about  $-19.0\text{‰}$  in  $\delta^{18}\text{O}$  and  $-130\text{‰}$  in  $\delta\text{D}$  (Fig. 5b). However, the modelled data do not entirely catch the real distribution of unit I isotopic composition where the  $\delta^{18}\text{O}$  values are slightly below and the  $d$  values slightly above the respective modelled lines (Fig. 5b). Because the model uses the maximum fractionation coefficient (Souchez and Jouzel, 1984), higher fractionation during freezing than modelled is impossible. Therefore, the system during freezing of unit I was likely not completely closed and new source water entered the system when about  $50\text{‰}$  of the water was already frozen and changed the isotopic composition of the remaining unfrozen water. This is supported by the slight reversal in  $\delta^{18}\text{O}$  and  $\delta\text{D}$ , a more distinct reversal in  $d$ , and higher ion concentrations at depth of 6.5 m bs (Fig. 2). In Fig. 5a is shown that the last six most depleted  $\delta^{18}\text{O}$  data points after about  $50\text{‰}$  of the water are frozen (corresponding to the lowermost data points of unit I in Fig. 2) increasingly deviate from the modelled data. Freezing of large parts of the unit I massive ice at least in only two stages under closed-system conditions is deduced.

The massive ice of unit II (9.8-16.1 m bs) is characterised by down-core increasing  $\delta^{18}\text{O}$  and  $\delta\text{D}$  by about  $5.6\text{‰}$  and  $37\text{‰}$ , respectively. The  $d$  decreases by about  $8\text{‰}$  (Fig. 2). Such down-core pattern might be explained by freezing under semi closed-system conditions when the water reservoir got episodically renewed with isotopically less depleted subsurface water. The observed down-core increase in solute concentrations of the unit II ice (Fig. 2) further indicates ion enrichment in the source water during ongoing freezing, and therefore questions the occurrence of a completely open system fed by constant water supply.

The down-core isotopic composition of unit III (16.1-20.8 m bs) resembles those of unit I with declining  $\delta^{18}\text{O}$  by about 4.4 ‰ and  $\delta\text{D}$  by about 29 ‰ concurrent with a rising  $d$  by about 6 ‰ (Fig. 2). Reversals in  $\delta^{18}\text{O}$  and  $\delta\text{D}$  and corresponding  $d$  are observed at depth of 19.9 m bs (Fig. 2), pointing to similar changes of the recharge reservoir as described for unit I. If compared to the freezing model under closed-system conditions (Fig. 5c) the water forming the ice of unit III would have had an initial composition of -14.4 ‰ in  $\delta^{18}\text{O}$  and -101 ‰ in  $\delta\text{D}$ . The more depleted isotopic values if compared to unit I are likely explained by fractionation of the available water volume due to previous freezing and formation of the older massive ice units. The lowermost ice of unit II (-11.1 ‰  $\delta^{18}\text{O}$ , -79 ‰  $\delta\text{D}$ ) is isotopically very close to the uppermost ice of unit III (-10.8 ‰  $\delta^{18}\text{O}$ , -77 ‰  $\delta\text{D}$ ), pointing to freezing of the same source water. The lowermost (last formed) ice of unit III at a depth of 20.5 m bs represents about 75 % frozen water of the initial reservoir (Fig. 5d) and points as the record of unit I again to freezing of a substantial part of the massive pingo ice (4.7 m thickness) of under prevailing closed-system conditions. The down-core increase in solute concentrations with highest values in the lowermost part of unit III supports closed-system freezing conditions of a fixed water volume.

The lowermost unit IV (20.8-22.2 m bs) exhibits down-core increasing  $\delta^{18}\text{O}$  by about 2 ‰ and  $\delta\text{D}$  by about 15 ‰ while  $d$  decreases by about 3 ‰ similarly to unit II but at less ranges. A drop in solute concentrations is striking (Fig. 2). Both, hydrochemical and isotopic composition of unit IV point to freezing conditions of a semi-closed system.

In summary, the pingo ice record obtained in core #9 delineates two closed-system freezing episodes (units I and III) with only slight recharge inversions of the water reservoir and two episodes (units II and IV) with more complicated freezing of subsurface water under semi-closed conditions when the reservoir got renewed from the same source.

Nowadays, the pingo has already accomplished its active growth as seen by the degradation crater on top of the pingo and the occurrence frozen deposits underlying the massive pingo ice. The latter induces that the freezing front where the pingo ice formed disappeared when the ground got deeply frozen. The relatively warm ground temperature of only -2.5 °C at 14.25 m bs in borehole #9 and the active layer reaching the top of the massive ice lead to its successive melt and intensified solifluction further lowering the thickness of the protective layer above the massive ice. As a further consequence of ongoing degradation of the pingo, the crater lake (20 x 30 m) might develop into a larger thermokarst lake as the massive ice melt proceeds. Such solifluction and thermokarst degradation processes are common for Spitsbergen pingos (Liestøl, 1996).

### 5.3 Some aspects of pingo formation in the context of Grøndalen valley history

The elongated outer shape of the Fili pingo cone is also observed for other pingos on Spitsbergen (Liestøl, 1996) while the revealed information on the internal structure of Fili pingo is unique in the sense that it is the only pingo completely drilled in its centre. The Riverbed pingo in Adventdalen, as referred in Matsuoka et al. (2004), was unfortunately studied for other purposes, and a distal exposure of its frozen core in does not allow it to be compared directly with the Fili pingo in Grøndalen, where the borehole is in the centre of mound.

The shape of the massive pingo ice can be deduced in vertical extension from its upper and lower boundaries observed in core #9 between 1.5 and 22.2 m bs. In lateral extension, the core #10 drilled from the crater top down to 12 m bs in about 35 m

distance from the core #9 position did not reach the massive ice and suggests a rather steep slope of the massive ice body. The assumed shape of the pingo and its massive ice is shown in Fig. 1c. The thickness of the massive ice (20.7 m) exceeds the height of the pingo of 9.5 m, which is explained by massive ice growth when the ongoing subsurface freezing pushed the previously formed ice and cover deposits upward. The latter moved subsequently from the pingo top down-slope by solifluction. Thus, the 9.5 m amplitude of surface uplift seen in the modern stage of pingo evolution became less than the 20.7 m thickness of the massive ice. Solifluction further explains the presence of the buried soil observed at 0.25-0.4 m bs in core #10. If these assumptions are reliable, the massive ice formation started at the freezing front at a depth of about 15 m bs. Because the ongoing freezing of new ice below the previously formed massive ice is only possible at the contact between ice and unfrozen waterlogged deposits, it seems likely that the advance of the freezing front got compensated by the growth of the massive ice and the pingo heave as well as by geothermal heat transported by groundwater. Consequently, the ground temperature at the base of the massive ice remained at the freezing point during the pingo growth. Even if the advance of the freezing front slowed somewhat down by massive ice formation, pingo growth and geothermal heat from groundwater, the latter did not slow down the freezing of the cover deposits along the shape of the aggrading hill, which likely promoted lateral freezing from the slopes, and terminated pingo growth.

Because information on the origin and ages of the deposits surrounding the pingos of Grøndalen are still lacking, such aspects will be addressed in future work. Nevertheless, tentative assumptions of the pingo formation stages in context of the valley evolution can already be drawn. Yoshikawa and Harada (1995) conclude from the position of the Grøndalen pingos at about 50 m asl that their formation started quickly after retreat of the sea (Fig. 6).

After retreat of the sea and establishment of the Grøn River system, we assume a sedimentation period of non-marine gravelly sand and loam deposits observed in core #11. These deposits also covers the top and the slopes of the Fili pingo (core #10) and represent therefore the non-marine ground in which the Grøndalen pingos formed, contradicting the interpretation of Yoshikawa and Harada (1995) who proposed pingo growth within refreezing marine sediments after sea regression. Based on the finding of lower ice body boundary at the depth 15 m under the surrounding surface (Fig. 1c), the position of the freezing front is assumed to have reached this depth before start of pingo growth. To reach such depth, we further assume a certain period of time that was also needed to disconnect the groundwater hydrology of the valley from the sea since seawater is unlikely to have been the source of the pingo massive ice as discussed above. The aggrading permafrost in Grøndalen likely restructured the groundwater hydrogeology of the valley and created groundwater flow in the fault zone connected to Bøhmdalen and Grøndalen that fed the pingos and explains their chain-like occurrence (Fig. 1b). Comparable to the pingo formation in Adventdalen, where the oldest pingos developed at higher positions (Fig. 6b), more distant from the sea (Yoshikawa and Nakamura, 1996). If this assumption is correct for Grøndalen, Nori pingo is the youngest and Gloin pingo is the oldest in the pingo chain of Grøndalen (Fig. 1b). While the taliks feeding the oldest pingos (above 50 m asl) froze subsequently, the next connectivity at lower topography became the place for new pingo formation and thus creating a chain of pingos following fault zone and the downslope topographic gradient and hence the availability of groundwater (Fig. 6c). The activity of groundwater springs related to warm-based glaciers might reflect their shrinking by less discharge of even

disappearance of the springs (Haldersen et al., 2011). This is because glacier size decrease and surface lowering induce shrinking accumulation area and further decreasing warm-based area terminating the recharge of springs. In this context, in the study of Chernov and Muraviev (2018) it was shown that the loss in glacier area in Nordenskiöld Land (West Spitsbergen) between 1936 and 2017 reached 49.5 %. Water discharge by the spring in Grøndalen does not necessarily mean that surrounding glaciers are warm-based at current time. They are probably cold-based today because of their current small size, but meltwater from the stage when they were warm-based may still be discharged by Grøndalen springs due to low discharge rates. Pingos in Grøndalen accomplished their growth not because of stop of ground water flow but because of freezing of sediments below the massive ice inhabiting the water supply. Today Grøndalen pingos exhibit clear degradation features such as the crater lake on top of Fili pingo (Fig. 6d).

## 6 Conclusions

For the first time a pingo on Spitsbergen was completely drilled to obtain records of the massive ice and the deposits above and the permafrost below it. The massive pingo ice is almost clear and reaches a thickness of 20.7 m while the pingo reaches a height above the surrounding surface of 9.5 m at present. Both, pingo ice thickness and pingo height were reduced by degradation. The lowermost measured ground temperature at 14.25 m bs close to the zero-amplitude temperature showed only little variation between  $-2.5$  and  $-2.37$  °C from May to September 2018. The maximum thaw depth of 1.5 m in September 2018 reached the uppermost massive ice, which indicates the ongoing fast degradation of the pingo. This is further seen in the crater lake on top of the pingo and strong solifluction that removes cover deposits downslope.

The stable water isotope record of the massive ice shows two episodes of closed-system freezing and two episodes of semi-closed freezing when the source water feeding the massive ice formation recharged. The hydrochemical composition of the massive ice and the permafrost below is dominated by  $\text{Na}^+$  and  $\text{HCO}_3^-$  ions, thus of terrestrial origin and similar to those of historical and modern observations of springwater in Grøndalen.

Our current understanding of pingo-related processes and conditions in Grøndalen makes it difficult to align them to the pingo categories for Spitsbergen proposed by Yoshikawa and Harada (1995). In the Fili pingo record of Grøndalen we concurrently identified pingo-formation characteristics such as fault-related groundwater discharge (typical for group I pingos) and groundwater origin from warm-based glaciers (typical for group II pingos). The proposed pingo formation in Grøndalen is connected to epigenetic refreezing of marine deposits (typical for group III pingos) but not immediately after sea regression due to the reworking of marine sediments seen in deposits surrounding the Grøndalen pingos.

The origin and distribution of pingos in Grøndalen depends on the complex interaction of hydrogeological conditions and sea level, glaciers and permafrost dynamics superimposed by climate variability over time. The latter may be typical for vast archipelago and makes investigation of pingos important for understanding key stages of cryosphere evolution of Spitsbergen.

## Author contributions

ND and SV initiated and designed the present study. They further drilled and documented the cores together with VD. AE carried out stable isotope analyses. AE and AJH contributed hydrochemical and stable isotope data of the modern environment, such as from precipitation, surface waters and sources. MA, LS and HM supported the overall data analysis and interpretation. ND and SW wrote the paper with input from the other co-authors, who contributed equally to the final discussion of the results and interpretations.

### Competing interests

The authors declare that they have no conflict of interest.

### 10 Acknowledgements

This work is supported by the Russian Science Foundation (grant № 19-77-10066). We acknowledge support for field logistics and lab analytics from the Russian Scientific Arctic Expedition on Spitsbergen Archipelago (RAE-S), Barentsburg. Ekaterina Poliakova (Arctic and Antarctic Research Institute, St. Petersburg, Russia) provided useful translations of Norwegian original literature. SW was supported by Deutsche Forschungsgemeinschaft (grant no. WE4390/7-1). AH acknowledges JPI-Climate Topic 2: Russian Arctic and Boreal Systems, Award No. 71126 (LowPerm). We thank our referees Trevor Porter and Go Iwahana as well as the handling editor Peter Morse for critical and helpful comments to improve the final version of the paper.

### Data availability

Original data are available at ~~<https://www.pangaea.de>~~ after acceptance of this paper <https://doi.pangaea.de/10.1594/PANGAEA.907530>.

### 20 References

- Burr, D.M., Tanaka, K.L., and Yoshikawa, K.: Pingos on Earth and Mars, *Planetary and Space Science*, 57(5-6), 541-555, <https://doi.org/10.1016/j.pss.2008.11.003>, 2009.
- Chernov, R.A., and Muraviev, A.Ya.: Contemporary changes in the area of glaciers in the western part of the Nordenskjöld Land (Svalbard), *Ice and Snow (Лёд и Снег)*, 58(4), 462-472, doi: 10.15356/2076-6734-2018-4-462-472, 2018 (in Russian).
- 25 Chizhova Ju.N., and Vasil'chuk Yu.K.: Use of stable water isotopes to identify stages of the pingo ice core formation, *Ice and Snow (Лёд и Снег)*, 58 (4), 507–523, doi: 10.15356/2076-6734-2018-4-507-52, 2018 (in Russian).
- Christiansen, H.H., Gilbert, G.L., Demidov, N., Guglielmin, M., Isaksen, K., Osuch, M., and Boike, J.: Permafrost thermal snapshot and active-layer thickness in Svalbard 2016-2017, In: SESS report 2018, The State of Environmental Science in Svalbard – an annual report, Eds.: Orr, E., Hansen, G., Lappalainen, H., Hübner, C., Lihavainen, H., SIOS, Longyearbyen,

- Svalbard, pp. 26-47, [https://www.sios-svalbard.org/sites/sios-svalbard.org/files/common/SESSreport\\_2018\\_FullReport.pdf](https://www.sios-svalbard.org/sites/sios-svalbard.org/files/common/SESSreport_2018_FullReport.pdf), 2019.
- Dansgaard, W.: Stable isotopes in precipitation, *Tellus*, 16(4), 436-468, <https://doi.org/10.3402/tellusa.v16i4.8993>, 1964.
- Demidov, N.E., Verkulich, S.R., Karaevska, E.S., Nikulina, A.L., and Savatyugin, L.M.: First results of permafrost  
 5 observations at the monitoring site of the Russian Scientific Centre on Spitsbergen (Первые результаты мерзлотных наблюдений на криосферном полигоне Российского научного центра на архипелаге Шпицберген (РНИЦШ)), *Problems of the Arctic and Antarctic (Проблемы Арктики и Антарктики)*, 2016 № 4(110), 67-79, 2016 (in Russian).
- Ekaykin, A.A., Lipenkov, V.Ya., Kozachek, A.V., and Vladimirova, D.O.: Stable water isotopic composition of the Antarctic  
 10 subglacial Lake Vostok: implications for understanding the lake's hydrology, *Isotopes in Environmental and Health Studies*, 52 (4-5), 468-476, <http://dx.doi.org/10.1080/10256016.2015.1129327>, 2016.
- French, H., and Shur, Y.: The principles of cryostratigraphy, *Earth-Science Reviews*, 101, <https://doi.org/10.1016/j.earscirev.2010.04.002>, 190-206, 2010.
- Geological map Svalbard 1:100 000, Spitsbergen Norsk Polarinstitut Temakart nr. 16, 1991
- 15 Ershov, E.D. (Ed.): *Fundamentals of Geocryology. Volume III. Regional and historical geocryology of the world (Основы геокриологии. Ч. 3. Региональная и историческая геокриология Мира)*. Moscow University Publishing House, Moscow, 575 pp., 1998 (in Russian).
- Grosse, G., and Jones, B.M.: Spatial distribution of pingos in northern Asia. *Cryosphere*, 5, 13-33, <https://doi.org/10.5194/tc-5-13-2011>, 2011.
- 20 Haldorsen S., Heim M., and van der Ploeg M. J.: Impacts of climate change on groundwater in permafrost areas: case study from Svalbard, Norway. In: *Climate change effects on groundwater resources: A global synthesis of findings and recommendations*, Eds.: Treidel, H., Martin-Bordes, J.L., and Gurdak, J.J., CRC Press, Boca Raton, FL, USA, pp. 323-338, 2011.
- Hjelle, A.: *Geology of Svalbard, Polar håndbok No. 7*, Norsk Polarinstitut, Oslo, Norway, 1993.
- 25 Hyvärinen, H., and Ritchie, J.C.: Pollen stratigraphy of Mackenzie pingo sediments, N.W.T., Canada. *Arctic and Alpine Research*, 7, 261-272, doi:10.1080/00040851.1975.12003832, 1975.
- Ishikawa, M., and Jambaljav, Ya.: Formation chronology of Arsain pingo, Darhad Basin, Northern Mongolia, *Permafrost Periglacial Process.*, 27(3), 297-306, <https://doi.org/10.1002/ppp.1877>, 2016.
- Jones, B.M., Grosse, G., Hinkel, K.M., Arp, C.D., Walker, S., Beck, R.A., and Galloway, J.P.: Assessment of pingo distribution  
 30 and morphometry using an IfSAR derived DSM, western Arctic Coastal Plain, northern Alaska, *Geomorphology*, 138, 1-14, <https://doi.org/10.1016/j.geomorph.2011.08.007>, 2012.
- Souchez, R., and Jouzel, J.: On the isotopic composition in  $\delta D$  and  $\delta^{18}O$  of water and ice during freezing. *J. Glaciol.*, 30(106), 369-372, <https://doi.org/10.3189/S0022143000006249>, 1984.
- Liestøl, O.: Pingos, springs, and permafrost in Spitsbergen. *Norsk Polarinstitut Årbok* 1975, 7-29, 1977.



- Liestøl, O.: Open-system pingos in Spitsbergen. *Norsk Geografisk Tidsskrift*, 50(1), 81-84, <https://doi.org/10.1080/00291959608552355>, 1996.
- Mackay, J.R.: Pingos of the Pleistocene Mackenzie Delta area, *Geographical Bulletin*, 18, 21-63, 1962.
- Mackay, J.R.: Pingos of the Tuktoyaktuk Peninsula Area, Northwest Territories. *Géographie physique et Quaternaire*, 33 (1), 3-61, <https://doi.org/10.7202/1000322ar>, 1979.
- Mackay, J.R.: Growth of Ibyuk Pingo, western Arctic coast, Canada, and some implications for environmental reconstructions, *Quat. Res.*, 26(1), 68-80, [https://doi.org/10.1016/0033-5894\(86\)90084-0](https://doi.org/10.1016/0033-5894(86)90084-0), 1986.
- Matsuoka N., Sawaguchi S., and Yoshikawa K.: Present-day periglacial environments in Central Spitsbergen, Svalbard, *Geographical Review of Japan*, 77(5), 276-300, <https://doi.org/10.4157/grj.77.276>, 2004
- 10 Nazintsev U.L., and Panov V.V.: Phase composition and thermophysical properties of sea ice (Фазовый состав и теплофизические характеристики морского льда), *Gidrometeoizdat*, St. Petersburg, Russia, 83 pp., 2000 (in Russian).
- Orvin A.K.: Litt om Kilder pa Svalbard, *Norsk Geografisk Tidsskrift*, X(1), 16-38, 1944 (in Norwegian).
- Palagushkina, O., Biskaborn, B., Wetterich, S., Schirrmeister, L., Nazarova, L., and Grosse, G.: Modern and fossil freshwater diatoms (Bacillariophyceae) in periglacial environments of the Seward Peninsula (northwestern Alaska), *Paleogeogr. Paleoclimatol. Paleocol.*, 479, 1-15, <https://doi.org/10.1016/j.palaeo.2017.04.006>, 2017.
- 15 Romanovskiy, N.N.: Underground ~~Waters-waters~~ of the ~~Permafrost permafrost Zone-zone~~ (Подземные воды криолитозоны). Moscow State University Press, Moscow, Russia, 232 pp., 1983 (in Russian).
- Ross, N., Harris, C., Christiansen, H.H., and Brabham, P.J.: Ground penetrating radar investigations of open system pingos, Adventdalen, Svalbard, *Norsk Geografisk Tidsskrift*, 59(2), 129-138, <https://doi.org/10.1080/00291950510020600>, 2005.
- 20 Rossi, G., Accaino, F., Boaga, J., Petronio, L., Romeo, R., and Wheeler, W.: Seismic survey on an open pingo system in Adventdalen Valley, Spitsbergen, Svalbard, *Near Surface Geophysics*, 16(1), 1-15, doi: 10.3997/1873-0604.2017037, 2018.
- Shokr, M., and Sinha, N.: Sea ice: physics and remote sensing, John Wiley and Sons, Chichester, UK, 2015.
- ~~Skakun, A.A., Chikhachev, K.B., Ekaykin, A.A., Kozachek, A.V., Vladimirova, D.O., Veres, A.N., Verkulich, S.R., Sidorova, O.R., Demidov, N.E.: Stable isotopic content of atmospheric precipitation and natural waters in the vicinity of Barentsburg (Svalbard) (Изотопный состав атмосферных осадков и природных вод в районе Баренцбурга (Шпицберген))~~  
~~Skakun, A.A., Chikhachev, K.B., Ekaykin, A.A., Kozachek, A.V., Vladimirova, D.O., Veres, A.N., and Verkulich, S.R., Sidorova, O.R., and Demidov, N.E.: Stable isotopic content of atmospheric precipitation and natural waters in the vicinity of Barentsburg (Svalbard), Ice and Snow (Лёд и Снег), 60(1), in review accepted, <https://ice-snow.igras.ru/jour/issue/archive>, 2020- (in Russian).~~
- 25  
30 Tolkien, J.R.R.: The Lord of the Rings. Allen and Unwin, Norwich, UK, 1954-1955.
- Ulrich, M., Wetterich, S., Rudaya, N., Frolova, L., Schmidt, J., Siegert, C., Fedorov, A.N., and Zielhofer, C.: Rapid thermokarst evolution during the mid-Holocene in Central Yakutia, Russia, *Holocene*, 27(12), 1899-1913, <https://doi.org/10.1177/0959683617708454>, 2017.

- van Everdingen, R.E.: Multi-language glossary of permafrost and related ground-ice terms (revised 2005), Boulder, USA: National Snow and Ice Data Center/World Data Center for Glaciology, 1998.
- Verkulich, S., Zazovskaya, E., Pushina, Z., Savelieva, L., Soloveva, D., Demidov, N., Shishkov, V., and Dercon, G.: The postglacial environmental changes in vicinity of the Barentsburg settlement (West Spitsbergen), EGU General Assembly, Vienna, Austria, 8-13 April 2018, EGU 2018-7729, 2018.
- Wetterich, S., Grosse, G., Schirrmeister, L., Andreev, A.A., Bobrov, A.A., Kienast, F., Bigelow, N.H., and Edwards, M.E.: Late Quaternary environmental and landscape dynamics revealed by a pingo sequence on the northern Seward Peninsula, Alaska, *Quat. Sci. Rev.*, 39, 26-44, <https://doi.org/10.1016/j.quascirev.2012.01.027>, 2012.
- Wetterich, S., Schirrmeister, L., Nazarova, L., Palagushkina, O., Bobrov, A., Pogosyan, L., Savelieva, L., Syrykh, L., Matthes, H., Fritz, M., Günther, F., Opel, T., and Meyer, H.: Holocene thermokarst and pingo development in the Kolyma Lowland (NE Siberia). *Permafrost Periglacial Process.*, 29(3), 182-198, <https://doi.org/10.1002/ppp.1979>, 2018.
- Yoshikawa, K.: Notes on Open-System Pingo Ice, Adventdalen, Spitsbergen. *Permafrost Periglacial Process.*, 4(4), 327-334, <https://doi.org/10.1002/ppp.3430040405>, 1993.
- Yoshikawa, K., and Harada, K.: Observations on nearshore pingo growth, Adventdalen, Spitsbergen, *Permafrost Periglacial Process.*, 6(4), 361-372, <https://doi.org/10.1002/ppp.3430060407>, 1995.
- Yoshikawa, K., and Nakamura, T.: Pingo growth ages in the delta area, Adventdalen, Spitsbergen. *Polar Record*, 32(183): 347-352, <https://doi.org/10.1017/S0032247400067565>, 1996.
- Yoshikawa, K., Leuschen, C., Ikeda, A., Harada, K., Gogineni, P., Hoekstra, P., Hinzman, L., Sawada, Y., and Matsuoka, N.: Comparison of geophysical investigations for detection of massive ground ice (pingo ice), *J. Geophys. Res.*, 111, E06S19, [doi:10.1029/2005JE002573](https://doi.org/10.1029/2005JE002573), 2006.
- Yoshikawa, K., Natsagdorj, S., and Sharkhuu, A.: Groundwater hydrology and stable isotope analysis of an open-system pingo in northwestern Mongolia. *Permafrost Periglacial Process.*, 24(3), 175-183, <https://doi.org/10.1002/ppp.1773>, 2013.

Tables

Table 1: Stable isotope ( $\delta^{18}\text{O}$ ,  $\delta\text{D}$ , and  $d$ ) minimum, mean, maximum values, standard deviations (std), and slopes, intercept and correlation coefficient ( $r^2$ ) of  $\delta^{18}\text{O}$ - $\delta\text{D}$  and  $\delta\text{D}$ - $d$  plots from massive pingo ice of core #9, from intrasedimental ice of core #10 and from precipitation (2016-2018). Data are shown in Fig. 3. Additional data from 2018 include spring water of Grøndalen and river and tributary water of the Grøn River (Skakun et al., ~~in review~~2020).

Water source	Depth	Number of sub-samples	$\delta^{18}\text{O}$ min	$\delta^{18}\text{O}$ mean	$\delta^{18}\text{O}$ max	$\delta^{18}\text{O}$ std	$\delta\text{D}$ min	$\delta\text{D}$ mean	$\delta\text{D}$ max	$\delta\text{D}$ std	$d$ min	$d$ mean	$d$ max	$d$ std	Slope	Intercept	$r^2$	Slope	Intercept	$r^2$
	[m bs]	[n]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	[‰]	$\delta^{18}\text{O}$ - $\delta\text{D}$	$\delta^{18}\text{O}$ - $\delta\text{D}$	$\delta^{18}\text{O}$ - $\delta\text{D}$	$\delta\text{D}$ - $d$	$\delta\text{D}$ - $d$	$\delta\text{D}$ - $d$
Precipitation	surface	88	-18.42	-8.95	-0.80	4.23	-144.5	-64.2	-17.3	30.2	-25.0	7.5	45.1	10.8	6.78	-3.39	0.9	--	--	--
Grøn River and tributaries	surface	7	-11.71	-11.24	-10.89	0.27	-83.2	-78.1	-75.2	2.6	10.5	11.9	13.3	1.3	8.18	13.92	0.75	--	--	--
Spring 2018	surface	1	--	-13.01	--	--	--	-93.5	--	--	--	10.6	--	--	--	--	--	--	--	--
core #9 unit I	1.5-9.8	16	-16.81	-12.56	-9.56	2.26	-116.9	-88.9	-68.4	15.1	8	11.5	17.6	3.1	6.66	-5.28	1	-0.20	-6.26	0.97
core #9 unit II	9.8-16.1	10	-16.65	-13.06	-11.07	2.34	-115.9	-92.0	-78.8	15.4	9.7	12.4	17.4	3.3	6.6	-5.88	1	-0.21	-7.10	0.99
core #9 unit III	16.1-20.8	7	-15.18	-13.17	-10.80	1.58	-106.3	-93.1	-77.2	10.5	9.2	12.3	15.1	2.2	6.58	-6.46	1	-0.21	-7.72	0.96
core #9 unit IV	20.8-22.2	3	-12.80	-11.42	-10.60	1.2	-90.7	-81.7	-6.1	7.9	8.5	9.7	11.7	1.8	6.52	-7.26	1	-0.23	-8.78	0.97
core #9 units I-IV	1.4-22.2	38	-16.81	-12.56	-9.52	2.14	-116.9	-89.0	-68.4	14.2	7.6	11.5	17.6	2.9	6.63	-5.67	1	-0.21	-6.77	0.98
core #10	6.65-8.4	4	-18.93	-14.09	-11.98	3.25	-131.3	-98.8	-84.4	21.9	11.5	13.9	20.1	4.1	6.74	-3.81	1	--	--	--

**Table 2: Hydrochemical composition of the massive pingo ice of core #9 given as, mean ( $\pm$  standard deviation), minimum and maximum values per unit. Data are shown in Fig. 2. Additional data include spring water of Grøndalen from 1926 (Orvin, 1944) and 2018 (this study), snow from 2016-2018 and river and tributary water of the Grøn River (Skakun et al., [in review 2020](#)).**

Water source	Depth	Number of sub-samples	pH mean (min-max)	EC mean (min-max)	ion content mean (min-max)	Na <sup>+</sup> mean (min-max)	K <sup>+</sup> mean (min-max)	Ca <sup>2+</sup> mean (min-max)	Mg <sup>2+</sup> mean (min-max)	Cl <sup>-</sup> mean (min-max)	SO <sub>4</sub> <sup>2-</sup> mean (min-max)	HCO <sub>3</sub> <sup>2-</sup> mean (min-max)	NO <sub>3</sub> <sup>-</sup> mean (min-max)	Alkalinity
	[m bs]	[n]		[ $\mu$ S cm <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mM]
<b>Grøn River 2018</b>	surface	1	7.4 (--)	-- (--)	118.4 (--)	7.6 (--)	0.9 (--)	13 (--)	9.1 (--)	5.3 (--)	63.3 (--)	19.2 (--)	-- (--)	-- (--)
<b>Snow 2018</b>	surface	1	7.7 (--)	-- (--)	16.4 (--)	5.3 (--)	< 0.25 (--)	0.3 (--)	0.3 (--)	8 (--)	0.6 (--)	2.0 (--)	-- (--)	-- (--)
<b>Spring 1926</b>	surface	1	-- (--)	-- (--)	879.2 (--)	333.3 (--)	16.5 (--)	4.9 (--)	6.1 (--)	113.5 (--)	3.3 (--)	372.3 (--)	-- (--)	-- (--)
<b>Spring 2018</b>	surface	1	8.8 (--)	1834 (--)	1192 (--)	-- (--)	-- (--)	-- (--)	-- (--)	15.3 (--)	3.8 (--)	-- (--)	-- (--)	2.19
<b>core#9 unit I</b>	1.5-9.8	16	7.2 $\pm$ 0.4 (6.6-7.9)	44 $\pm$ 30 (5-106)	22.3 $\pm$ 14.9 (2.6-54.2)	8.2 $\pm$ 6.8 (0.0-23.8)	2.5 $\pm$ 0.7 (1.7-4.1)	0 (0-0.5)	-- (--)	6.4 $\pm$ 4.1 (1.1-14.4)	0.9 $\pm$ 0.3 (0.6-1.8)	13.5 $\pm$ 11.5 (1.0-39.9)	0.7 $\pm$ 0.1 (0.7-1.1)	-- (--)
<b>core#9 unit II</b>	9.8-16.1	7	7.8 $\pm$ 0.7 (7.0-8.8)	141 $\pm$ 118 (27-269)	72.2 $\pm$ 60.5 (13.8-137.9)	30.8 $\pm$ 25.2 (5.4-70.3)	1.1 $\pm$ 0.7 (0.3-2.1)	0 (0-0.2)	-- (--)	12.2 $\pm$ 7.8 (4.3-25.1)	1.8 $\pm$ 1.3 (0.7-4.4)	51.6 $\pm$ 41.8 (6.9-110.1)	0.6 $\pm$ 0.1 (0.5-0.7)	-- (--)
<b>core#9 unit III</b>	16.1-20.8	8	8.4 $\pm$ 0.4 (7.8-8.9)	394 $\pm$ 265 (133-834)	202.0 $\pm$ 136.0 (68.1-427.7)	107.3 $\pm$ 68.1 (39.8-216.9)	1.1 $\pm$ 1.0 (0.2-2.8)	-- (--)	0.4 (0.0-1.9)	51.1 $\pm$ 40.3 (14.3-120.7)	2.1 $\pm$ 0.6 (1.4-3.1)	163.3 $\pm$ 106.8 (56.4-336.3)	0.8 $\pm$ 0.5 (0.5-2.1)	-- (--)
<b>core#9 unit IV</b>	20.8-22.2	3	7.8 $\pm$ 0.1 (7.8-8.9)	104 $\pm$ 5 (100-108)	53.3 $\pm$ 2.3 (51.0-55.6)	27.2 $\pm$ 1.5 (25.6-28.4)	0.3 $\pm$ 0.1 (0.2-0.3)	-- (--)	-- (--)	11.0 $\pm$ 1.9 (8.8-12.4)	1.5 $\pm$ 0.3 (1.3-1.8)	40.5 $\pm$ 1.7 (39.5-42.5)	0.7 $\pm$ 0.1 (0.6-0.7)	-- (--)
<b>core#9 units I-IV</b>	1.5-22.2	34	7.7 $\pm$ 0.7 (7.8-8.9)	152 $\pm$ 197 (5-834)	77.8 $\pm$ 100.9 (2.6-427.7)	37.8 $\pm$ 52.3 (0.0-216.9)	1.7 $\pm$ 1.1 (0.2-4.1)	0 (0-0.5)	0.4 (0.0-1.9)	18.5 $\pm$ 26.6 (1.1-120.7)	1.4 $\pm$ 0.9 (0.6-4.4)	59.2 $\pm$ 81.4 (1.0-336.3)	0.7 $\pm$ 0.3 (0.5-2.1)	-- (--)

5

**Table 3: Hydrochemical composition of water extracts of the sedimentary cores #9, #10 and #11 given as, mean ( $\pm$  standard deviation), minimum and maximum values per core. Data are shown in Fig. 4.**

Water source	Depth	Number of sub-samples	pH mean (min-max)	EC mean (min-max)	ion content mean (min-max)	Na <sup>+</sup> mean (min-max)	K <sup>+</sup> mean (min-max)	Ca <sup>2+</sup> mean (min-max)	Mg <sup>2+</sup> mean (min-max)	Cl <sup>-</sup> mean (min-max)	SO <sub>4</sub> <sup>2-</sup> mean (min-max)	HCO <sub>3</sub> <sup>2-</sup> mean (min-max)	NO <sub>3</sub> <sup>-</sup> mean (min-max)
	[m bs]	[n]		[ $\mu$ S cm <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]	[mg l <sup>-1</sup> ]
<b>core#9</b>	22.55-24.9	5	9.6 $\pm$ 0.2 (9.2-9.9)	1796 $\pm$ 818 (1011-2670)	897.8 $\pm$ 408.8 (505.0-1335.0)	625.9 $\pm$ 204.4 (429.2-861.6)	18.5 $\pm$ 3.7 (14.4-22.6)	-- (--)	-- (--)	216.0 $\pm$ 144.7 (107.0-397.2)	74.7 $\pm$ 14.9 (52.6-93.8)	522.9 $\pm$ 227.5 (289.0-836.8)	0.7 $\pm$ 0.1 (0.6-0.9)
<b>core#10</b>	0-11.9	10	7.3 $\pm$ 0.5 (6.7-7.9)	199 $\pm$ 120 (22-436)	99.6 $\pm$ 60.0 (10.8-218.0)	46.4 $\pm$ 28.1 (3.9-81.1)	8.0 $\pm$ 4.2 (1.3-15.4)	22.2 $\pm$ 17.0 (0.6-49.0)	2.0 $\pm$ 1.3 (0.5-4.1)	15.6 $\pm$ 10.4 (0-31.6)	47.4 $\pm$ 38.9 (1.4-138.0)	22.2 $\pm$ 17.0 (4.2-49.0)	0.2 $\pm$ 0.1 (0.1-0.4)
<b>core#11</b>	0-5.0	4	7.2 $\pm$ 0.3 (6.9-7.6)	75 $\pm$ 71 (75 $\pm$ 71)	37.5 $\pm$ 35.6 (6.9-88.1)	8.0 $\pm$ 3.7 (2.5-10.3)	2.6 $\pm$ 2.3 (0.6-5.1)	6.2 $\pm$ 8.2 (1.0-15.7)	2.6 $\pm$ 3.3 (0.3-6.4)	1.6 $\pm$ 0.7 (0.8-2.4)	18.3 $\pm$ 22.4 (1.4-50.1)	15.7 $\pm$ 16.6 (4.2-40.3)	0.2 $\pm$ 0.1 (0.1-0.3)

Figures





Figure 1: Study region of Nordenskiöld Land on West Spitsbergen (inset), showing (a) the position of Grøndalen, (b) the position of seven pingos in Grøndalen (redrawn after <https://toposvalbard.npolar.no>), spring location (blue circle) and estimated faults locations (dotted lines) and (c) the drilling profile across Fili pingo (shown as orange star in b) with locations of cores #9, #10, #11. Please note that the actual lateral extent of the massive pingo ice body is unknown.



**Figure 2: Isotopic and hydrochemical composition of the massive ice of Fili pingo obtained from core#9 as well as thermometric data from the borehole on 12 September 2018. Light grey symbols in the first plot refer to the upper x-axis ( $\delta D$ ). Data are given in Table 1 and Table 2.**






Figure 3: Co-isotopic plots of (a)  $\delta^{18}\text{O}$  and  $\delta\text{D}$  in modern precipitation (08/2016-09/2018) and water of the Grøn River and its tributaries (Skakun et al., [in review 2020](#)), (b)  $\delta^{18}\text{O}$  and  $\delta\text{D}$  in massive ice of core #9 from pingo and from spring water sampled, and (c)  $\delta\text{D}$  and deuterium excess ( $d$ ) data in massive ice of core #9 from pingo and from spring water. Data are given in Table 1. Note different axis scales in (a) and (b).





**Figure 4: Hydrochemical composition of water extracts from the sedimentary cores #9, #10 and #11. Data are given in Table 3. Note different axis scale for ion content in (a) reaching up to 1335 mg l<sup>-1</sup>.**



**Figure 5: Isotopic composition of unit I (a, b) and unit III (c, d) of the massive pingo ice of core #9 in comparison to freezing model data under closed-system conditions (Ekaykin et al., 2016).**




Figure 6: Schematic sketch of Grøndalen evolution and pingo formation differentiating into (a) marine stage, (b) initial pingo growth after sea retreat and establishment of the valley's hydrological system, (c) continuing pingo growth along the topographic gradient and (d) current pingo degradation and occurrence of springs.