

## **Author response to Reviewer's and Editor's comments regarding resubmission of TC-2020-07**

Thanks for another round of constructive reviews. The comments and suggestions were highly appropriate and we have changed the manuscript accordingly. Details of changes are provided in the point-to-point reply and in the marked-up versions of the manuscript and the supplement, all three found on the following pages and in that order. In short, we did the following:

- Changed the last part of the abstract to emphasize that our study shows that permafrost aggradation deserves more attention as driver for the transport of deep groundwater and methane to the surface.
- Replaced pie charts with bar charts in figures 8 and 10
- Added two new statistical fits to the measured K-values of Carolinefjellet and Helvetiafjellet Fms (in the supplement).
- Rephrased text and added/removed sentences and words as suggested by the referees.

With great thanks,

Mikkel Toft Hornum on behalf of all authors

# Point-to-point reply to referee comments

Referee comments are written in red. Author replies in black.

## Referee #1 (Melissa Bunn)

The following minor revisions are offered for the consideration of the authors:

- Line 53-54: Heat transport and groundwater flow
  - corrected
- Table 1 – Does the Asterisk in Site/\*Event have a purpose, is there a note missing?
  - The asterisk was leftover from a previous manuscript version. Now deleted.
- Line 258: In discussing the RMS error for the heat flow model validation, opposed to reasonable accuracy, could it be stated that it is an acceptable level of accuracy for the given purpose.
  - *Old version, line 258:* “[...] to represent reasonable accuracy.”
  - *New version:* “[...] to represent an acceptable level of accuracy for the given purpose.”
- Line 333: The properties were that of THE Janusfjellet Group.
  - corrected
- Line 353: would tidal flat be more appropriate relative to Fjord, given the extent of the model boundary?
  - We think ‘fjord’ is more appropriate, because the general head boundary conditions was assigned to cells located where the fjord begins (and the model domain ends). We have added a sentence to clarify:
  - *Old version:* “The fjord was simulated with a general head of 0 m a.s.l. assigned to the relevant cells and the conductance was determined according to hydraulic conductivity (Table 3).”
  - *New version:* “The fjord was simulated with a general head of 0 m a.s.l. and the conductance was determined according to the hydraulic conductivity (Table 3). The area assigned with this boundary conditions comprised 24 cells located within the uppermost layer at the north-western end of the model domain.”
- Line 360: were assigned no-flow conditions
  - corrected
- Line 447 to 448: Partial sentence left over?
  - Yes. Partial sentence deleted.
- Line 449: Two exceptions to this result were the minimum...
  - corrected
- Line 468: and the lack of discharge at the up-valley....
  - corrected
- Line 479: all of this outflow discharge to the fjord.
  - corrected
- Line 479: Instead of referring to the water flux that is redistributed to subpermafrost liquid water as “outflow to permafrost thaw” perhaps it would be clearer to explain this as a phase change and redistribution to storage opposed to an outflow, as it does not leave the model domain.
  - We agree with the referee and have rephrased here and in the caption for Figure 8:

- *Old version, Lines 478-480:* “For intermediate and maximum  $Q_{REQ}$  scenarios (ScXb–c, Fig. 8), all of this discharged to the fjord, while, for the minimum  $Q_{REQ}$  scenarios (ScXa, Fig. 8), a minor proportion of the outflow represents phase change associated with permafrost thaw, which causes a storage redistribution within the model domain.”
- *New version:* “For intermediate and maximum  $Q_{REQ}$  scenarios (ScXb–c, Fig. 8), all of this discharged to the fjord, while, for the minimum  $Q_{REQ}$  scenarios (ScXa, Fig. 8), a minor proportion of the outflow represents phase change associated with permafrost thaw, which causes a storage redistribution within the model domain.”
- *Old version, Lines 489-490:* “\*For minimum  $Q_{REQ}$  scenarios (1a, 2a and 3a) part of the outflow is caused by basal permafrost thaw (Figs. 7b–c).”
- *New version:* “\*For minimum  $Q_{REQ}$  scenarios (1a, 2a and 3a) part of the outflow represents phase change associated with permafrost thaw (Figs. 7b–c), which causes a storage redistribution within the model domain.”
- **Line 480: Larger proportions of outflow to the fjord were simulated.....**
  - corrected
- **Line 520: low-permeability**
  - corrected
- **Line 590: Negelecting this effect represents an uncertainty in the simulation results,....**
  - corrected
- **Line 600: These conditions should be taken into account....**
  - corrected
- **Supplement S2 – Figure S5: The higher measured hydraulic conductivity values do not seem to fit the Weibull distribution presented. Were other distributions presented, with this distribution yielding the best fit? If so, it may be useful to include a statement indicating such. Was a log-normal distribution (using the negative log of hydraulic conductivity) attempted?**
  - *Supplement, old version, Lines 81-82:* “The ranges of hydraulic conductivity of these units were defined by the 25 %, 50 % and 75 % percentiles of a Weibull probability fit to the measured values (Fig. S5).”
  - *New version:* “To tighten the  $K_h$ -range used in the groundwater model, we defined the realistic minimum, mean, and maximum values as the first, second and third quartiles of a statistical fit to the measured values. As illustrated on Fig. S4, three types of statistical distribution were tested; log-normal, Weibull and log-logistic (panels a), b) and c), respectively). While the log-logistic fit showed the best correlation, all three fits predicted the same hydraulic conductivities at the quartiles.”
  - *Supplement, old version, caption for Figure S4:* “Figure S5 Weibull fit to measured hydraulic conductivities of Carolinefjellet and Helvetiafjellet formations. Original data from the Longyearbyen CO<sub>2</sub> Laboratory Project (Olaussen et al., 2020, and references therein).”
  - *New version:* “**Figure S4** Log-normal (a), Weibull (b) and log-logistic (c) fits to the measured hydraulic conductivities of Carolinefjellet and Helvetiafjellet formations. Original data from the Longyearbyen CO<sub>2</sub> Laboratory Project (Olaussen et al., 2020, and references therein). The log-logistic fit shows the best correlation with the measured values and the values used in the groundwater model were thus defined by the quartiles predicted by this fit. Note that the two other fits both predict the same quartiles.”

## Referee #2

The authors have made many edits to address my points in the previous review. I have the following suggestions for the revised manuscript.

- L25-27: I suggest rewriting/replacing the last two sentences and try and make it more impactful. I think the interesting implication is how methane emissions are affected by the processes investigated in this paper, or I suppose what can be inferred about methane from the processes. The introduction also set up this implication. Also, give that this is an unusual hydraulic system, where would you expect to find other sites like it?
  - *Old version, Lines 20-28:* “Simulations also suggest that the generally low-permeability hydrogeological units cause groundwater residence times to exceed the duration of the Holocene. The likelihood of such pre-Holocene groundwater ages is also supported by the geochemistry of the pingo springs, which demonstrates an unexpected sea-ward freshening of groundwater, potentially caused by a paleo-subglacial melt water “wedge” from the Weichselian. This sub-permafrost wedge progressively thins inland, as permafrost thickness (and age) increases and so, less unfrozen freshwater is available for mixing. Although this unusual hydraulic system is most likely governed by permafrost aggradation, the potential for additional pressurisation is also explored. We find that methane production and methane clathrate formation/dissolution deserve particular attention on account of their likely effects upon the hydraulic pressure at the study site and others like it.”
  - *New version:* “We also explore the potential for additional pressurisation, and find that methane production and methane clathrate formation/dissolution deserve particular attention on account of their likely effects upon the hydraulic pressure. Our model simulations also suggest that the generally low-permeability hydrogeological units cause groundwater residence times to exceed the duration of the Holocene. The likelihood of such pre-Holocene groundwater ages is supported by the geochemistry of the pingo springs, which demonstrates an unexpected sea-ward freshening of groundwater, potentially caused by a paleo-subglacial melt water “wedge” from the Weichselian. This sub-permafrost wedge progressively thins inland, as permafrost thickness (and age) increases and so, less unfrozen freshwater is available for mixing. Although this is an unusual hydraulic system our observations confirm that, also in other uplifted Arctic valleys, millennial-scale permafrost aggradation deserves attention as a possible driver of sustained flow of sub-permafrost groundwater and methane to the surface.”
- L210: Maybe clarify “by the eye” a bit. Was any quantitative measurement involved, or is this just a guess? Perhaps add an uncertainty range to indicate a potential range, since this probably is an unprecise method of estimation.
  - This is indeed a guess based on personal experience, and we agree that this is an imprecise method. We have further emphasized the uncertainty by rephrasing:
  - *Old version:* “Based on our own “by the eye” observations, the discharge rate at Førstehytte Pingo was in orders of  $0.1 \text{ L s}^{-1}$  when visited in fall of 2015, 2016 and 2017, and less than  $0.01 \text{ L s}^{-1}$  when rediscovered in October 2019.”
  - *New version:* “Based on our own “by the eye” estimates involving no quantitative measurements, the discharge rate at Førstehytte Pingo was in orders of  $0.1 \text{ L s}^{-1}$  when visited in fall of 2015, 2016 and 2017, and less than  $0.01 \text{ L s}^{-1}$  when rediscovered in October 2019.”

- L431: When using terms such as “surprising” it should also be clarified why the results are “surprising”.
  - *Old version, Lines 431-433:* “At first surprising, the model simulations generally did not suggest that the highest aggradation rate occurred where permafrost is youngest (zone 0-1), but instead at zone 1-2. This was due to the different properties of the sediments and bedrock undergoing freezing.”
  - *New version:* “For a homogeneous medium with one-sided freezing, the freezing front progression rate will decrease with time (as exemplified by Figure S2). At first, it therefore seems surprising that the model simulations generally did not suggest that the highest aggradation rate occurred where permafrost is youngest (zone 0-1), but instead at zone 1-2. This was due to the heterogeneity in the model domain as expressed by the different properties of the sediments and bedrock undergoing freezing.”
- L418: explain what labels were used to identify the pingo springs in panel 1c.
  - Change to figure 7: We have emphasized the symbols and labelling used to show the freezing front and permafrost depth observations. The references of these observations have been added to the figure caption.
- L473: I would rephrase: It is the model that shows that outflow only take place if hydraulic pressure is artesian, the colour fill and figure 8 is only visualizing the model result. So the figure text says that red is artesian flow, and blue is not. But several figures have both (1a, 2a, 3a). Clarify that the pressure needs to be artesian at the pingos. I guess this is the case. I think converting the pie charts into bar charts where the data is grouped based on simulation and the artesian conditions may be more effective, but perhaps this is an issue of taste so I leave it for the authors to consider.
  - Sentence rephrased to clarify:
  - *Old version, Lines 473-474:* “The colour fill and the pie charts on Fig. 8 together show that outflow at a pingo site only takes place if the hydraulic pressure is artesian.”
  - *New version:* “The colour fill and the bar charts on Fig. 8 together show that the hydraulic pressure below a pingo site needs to be artesian in order for outflow to take place at that pingo.”
  - Pie charts replaced with bar charts in Figures 8 and 10 text changed accordingly.
- L487: Clarify what distribution in the term “outflow distribution” refer to
  - *Old version, Lines 488-489:* “The outflow distribution and discharge rates are illustrated by pie charts with the location of the discharge points (pingos and fjord) indicated on (1c).”
  - *New version:* “The groundwater outflow rates and distribution are illustrated by bar charts with the location of the discharge points (pingos and fjord) indicated on (1c).”
- Figure 8: I still think there is too much information in one figure, but I guess the authors disagree. Pie charts are typically not recommended for scientific data, since it is difficult to discern magnitudes. Bar charts are typically more effective than pie charts. Of course, the authors have provided the actual data in the pie charts, but that adds clutter and information overload.
  - Pie charts replaced with bar charts in Figures 8 and 10 text changed accordingly.
- Figure 10. Add a line that the figure is using the same structure, legend etc. as Figure 8.
  - done

# Numerical modelling of permafrost spring discharge and open-system pingo formation induced by basal permafrost aggradation

Mikkel T. Hornum<sup>1,2</sup>, Andrew J. Hodson<sup>1,3</sup>, Søren Jessen<sup>2</sup>, Victor Bense<sup>4</sup>, Kim Senger<sup>1</sup>

<sup>1</sup>Department of Arctic Geology, The University Centre in Svalbard (UNIS), N-9171 Longyearbyen, Norway.

5 <sup>2</sup>Department of Geosciences and Natural Resource Management, University of Copenhagen, 1350 Copenhagen K, Denmark.

<sup>3</sup>Department of Environmental Science, Western Norway University of Applied Sciences, N-6856 Sogndal, Norway

<sup>4</sup>Department of Environmental Sciences, Wageningen University, 6708PB Wageningen, Netherlands.

*Correspondence to:* Mikkel T. Hornum (mth@ign.ku.dk)

## Abstract

10 In the high Arctic valley of Adventdalen, Svalbard, sub-permafrost groundwater feeds several pingo springs distributed along the valley axis. The driving mechanism for groundwater discharge and associated pingo formation is enigmatic because wet-based glaciers are not present in the adjacent highlands and the presence of continuous permafrost seem to preclude recharge of the sub-permafrost groundwater system by either a sub-glacial source or a precipitation surplus. Since the pingo springs enable methane that has accumulated underneath the permafrost to escape directly to the atmosphere, our limited understanding  
15 of the groundwater system brings significant uncertainty to predictions of how methane emissions will respond to changing climate. We address this problem with a new conceptual model for open-system pingo formation wherein pingo growth is sustained by sub-permafrost pressure effects, as related to the expansion of water upon freezing, during millennial scale basal permafrost aggradation. We test the viability of this mechanism for generating groundwater flow with decoupled heat (1D-transient) and groundwater (3D-steady-state) transport modelling experiments. Our results suggest that the conceptual model  
20 represents a feasible mechanism for the formation of open-system pingos in lower Adventdalen and elsewhere. We also explore the potential for additional pressurisation, and find that methane production and methane clathrate formation/dissolution deserve particular attention on account of their likely effects upon the hydraulic pressure. Our model sSimulations also suggest that the generally low-permeability hydrogeological units cause groundwater residence times to exceed the duration of the Holocene. The likelihood of such pre-Holocene groundwater ages is ~~also~~ supported by the geochemistry of the pingo springs,  
25 which demonstrates an unexpected sea-ward freshening of groundwater, potentially caused by a paleo-subglacial melt water “wedge” from the Weichselian. This sub-permafrost wedge progressively thins inland, as permafrost thickness (and age) increases and so, less unfrozen freshwater is available for mixing. Although this is an unusual hydraulic system ~~is most likely governed by permafrost aggradation, the potential for additional pressurisation is also explored. We find that methane production and methane clathrate formation/dissolution deserve particular attention on account of their likely effects upon the~~  
30 hydraulic pressure at the study site and others like it. our observations confirm that, also in other uplifted Arctic valleys, millennial-scale permafrost aggradation deserves attention as a possible driver of sustained flow of sub-permafrost

## 1 Introduction

Sub-permafrost groundwater systems are highly inaccessible and so their investigation usually relies on sparse data (van der Ploeg et al., 2012). However, cold regions increasingly become hydrogeologically active after surface warming and associated permafrost degradation. This implies, for example, an increased outflow of deeper groundwater to rivers and lakes (Bense et al., 2012), increased rates of biogeochemical processes (Grosse et al., 2016), and potentially increased fluxes of methane or other compounds into the surface environment and atmosphere (Schuster et al., 2018). The surface discharge of sub-permafrost groundwater is currently exemplified by springs in the high Arctic (Andersen et al., 2002; Grasby et al., 2012; Haldorsen et al., 1996; Williams, 1970). If conditions are favourable, spring outflow may instead freeze below the active layer and initiate the growth of an ice-cored hill or pingo. By definition, this would classify as an open-system pingo because of the open connection to the sub-permafrost groundwater (Liestøl, 1996). Considerable methane stocks may exist below continuous permafrost and where no such springs exist, the only rapid escape route goes to the ocean, where methane oxidation prevents much of it from reaching the atmosphere (Mau et al., 2017; Myhre et al., 2016). Where springs do exist, however, sub-permafrost methane may escape directly to the atmosphere, contributing significantly to the total landscape methane emissions (Betlem et al., 2019; Hodson et al., 2019).

The hydrogeological mechanisms causing the sustained flow of sub-permafrost groundwater to surface springs remain elusive (Scheidegger et al., 2012). Earlier it was proposed that subglacial meltwater from underneath warm-based ice sheets or glaciers would sufficiently recharge a sub-permafrost aquifer (Demidov et al., 2019; Liestøl, 1977; Scheidegger et al., 2012; Scheidegger and Bense, 2014). However, in regions of continuous permafrost lacking warm-based glaciers or other groundwater recharge pathways, such models do not seem applicable (Ballantyne, 2018; Grasby et al., 2014; Woo, 2012). An alternative model to explain the existence of perennial springs in such environments is that hydraulic head gradients in the sub-permafrost hydrogeological system are maintained by artesian pressure generated by past or current aggradation of basal permafrost (Fig. 1). This would remove the need to invoke groundwater recharge from the surface as spring outflow derives from relict groundwater. Furthermore, it might explain the formation of emergence-related open system pingos in coastal lowlands (Burr et al., 2009; Yoshikawa and Harada, 1995).

In this paper, we use field data from Adventdalen, Svalbard, in combination with numerical modelling of heat and groundwater ~~transport flow~~ to evaluate the hypothesis that perennial spring flow through continuous permafrost can be driven by sub-permafrost artesian pressure produced by basal permafrost aggradation. Alternative causes of anomalous pressures are also discussed, including overpressure remaining from past perturbations (e.g., glacial loading) or contemporary processes such as equilibration of groundwater density contrasts and gas production. The investigation of the above hypothesis is based on decoupled heat and groundwater modelling, but in the discussion, this is combined with inverse analyses of spring geochemistry from a series of open-system pingos within the valley. A 1D heat transfer model forced by reconstructed paleo-

temperatures serves to simulate Holocene ground temperatures and permafrost development in the valley floor of Adventdalen.

65 By considering the expansion of water upon freezing, the simulated rates of present permafrost aggradation must cause a loss in aquifer volume equivalent to a recharge rate. This apparent recharge defines the only inflow term to a steady-state 3D groundwater model that simulates the present state of the sub-permafrost groundwater system. The modelling results are then discussed in relation to the hydrochemical observations of the pingo spring waters.

## 2 Conceptual model of permafrost aggradation-driven pingo formation


70 When permafrost aggrades into the ground, water in the pore space freezes, and hence expands. At shallower depths this is evident from ice lenses and other types of visible ground ice, resulting in ground heave, but from a certain depth downwards (e.g. ~ 5 m in Adventdalen: Gilbert et al., 2018), these cryostructures are no longer observed (French, 2017). Instead, the lithostatic pressure prevents ground heave and the ice expansion induces an overpressure (with regard to the hydrostatic pressure) on the sub-permafrost groundwater, especially where pressures cannot dissipate in an efficient manner. The process  
75 is well known from closed-system pingos, where groundwater is enclosed by aggrading permafrost and expelled to the surface from a closed talik (i.e. a perennially unfrozen part of the permafrost) (Mackay, 1998).

In contrast to closed-system pingos, an open-system pingo is sourced from a body of groundwater that is not enclosed by frozen ground. Liestøl (1977) suggests that an open-system pingo-spring can be driven by recharge from subglacial melting of warm-based glaciers. Scheidegger et al. (2012) developed a coupled model of transient permafrost formation and showed  
80 how hydraulic heads can maintain spring outflow for millennia even when permafrost is aggrading (disregarding ice expansion). In our study, we test the hypothesis that permafrost aggradation itself can generate such excess head.

Figure 1 illustrates our conceptual model for open-system pingo formation by basal permafrost aggradation and presents the additional conditions that also have to be met. The assumed starting point is a coastal landscape with no permafrost and a subsurface consisting of a hydrogeological unit in which hydraulic pressures dissipate poorly (Fig. 1a). Figures 1b and  
85 1c illustrate that a negative shift in the surface energy balance results in permafrost aggradation. Freezing pressure is induced at the freezing front resulting in hydraulic head gradients. The shift in the surface energy balance may occur due to a drop in the mean annual air temperature (MAAT) (Figs. 1b–c), a regressing shoreline (Fig. 1c), rapid erosion (not illustrated), or a combination of any of these. Close to the sea, groundwater flows towards the shoreface, but at some distance inland, higher advective heat transfer, associated with higher groundwater velocities, prevents frozen ground formation. As a consequence,  
90 groundwater may flow through a talik that perforates the permafrost (i.e. a through-talik) towards the surface along the most hydraulically conductive path, resulting in a spring (or pingo) (as modelled by Scheidegger et al., 2012). Freeze-up of the through-talik is further restricted if permafrost aggradation lowers the melting point by increasing pressure and/or salinity. Figure 1d illustrates that when ground temperatures are eventually in equilibrium with the MAAT, permafrost aggradation has stagnated, and so groundwater flow to the pingos has ceased. Due to the lack of advective heat transfer, the through-talik might




95 therefore close and, if so, irreversibly de-activate pingo spring discharge. However, (although salinity may keep the through-  
talik open, in spite of no-flow).



100 **Figure 1** Conceptual model of pingo formation driven by permafrost aggradation in a low-permeable system. **(a)** No permafrost is present.  
**(b)** and **(c)** A negative shift in the surface energy balance results in permafrost aggradation. Freezing pressure is induced at the freezing front  
and this result~~ing~~ing in hydraulic head gradients. At some distance inland, higher advective heat transfer, associated with higher groundwater  
and where a ~~spring (or pingo) forms at the spring.~~ spring **(d)**  
 The ground is in thermal equilibrium with the MAAT, permafrost aggradation has stagnated, and groundwater flow to the pingos has ceased.

### 3 Study site

105 Adventdalen is a ~ 30 km long glacially cut valley in central Spitsbergen, Svalbard (Fig. 2a). Its high Arctic climate is  
 characterised as polar tundra (Kottek et al., 2006) and the ground is dominated by continuous permafrost (Humlum et al.,  
 2003). Because of the dry climate with a mean annual precipitation of ~ 200 mm (Hanssen-Bauer et al., 2018) only a few,  
 small glaciers exist today, the largest being Drønbreen, 9 km long and up to 200 m thick.



110 **Figure 2** (a) Map of Lower Adventdalen with the location of data resources, pingos and the Holocene marine limit. LP = Lagoon Pingo, LYRP = Longyear Pingo, FHP = Førstehytte Pingo, IHP = Innerhytte Pingo, RP = River Pingo. Core logs from boreholes S1–3 and D1–D7 (respectively, Gilbert et al., 2018, and Olaussen et al., 2020, and references therein), seismic lines (Bælum et al., 2012, and unpublished commercial lines from Norsk Hydro) and a geological map (Norwegian Polar Institute, 2019) were used to build the geological model (Fig. 5a) (see details in Hornum, 2018). Permafrost depth measurements at the Sarkofagen, DH4 and Breinosa sites are from Liestøl (1977), Braathen et al. (2012), and Christiansen et al. (2005), respectively. The freezing front depth at LP is from Yoshikawa and Harada (1995). Data used to develop the map including topography, glacial extent, and fluvial network by courtesy of Norwegian Polar Institute (2019). (b) Geological cross sections constructed based on the resources mentioned above. The Quaternary unit overly well-consolidated sedimentary

strata of pre-Cenozoic age (i.e., Cretaceous or older). See Sect. 3.1 for a (hydro)geological description of the layers shown in the cross sections A, B and C.

### 120 3.1 Geology and hydrogeology in Adventdalen

In Adventdalen, fine-grained Quaternary sediments (< 70 m thick Gilbert et al., 2018) overly pre-Cenozoic, well-consolidated sedimentary strata (Fig. 2b), which are likely the best described in Svalbard largely thanks to the Longyearbyen CO2 Laboratory Project (Olaussen et al., 2020, and references therein). Together, all these units form a low-permeability groundwater system.

125 The sedimentary strata gently dip in a west-south-westerly direction (Fig. 2b) and the youngest strata are thus found closest to Longyearbyen and the present-day coastline. The uppermost unit, the Early Cretaceous Carolinefjellet Fm (~ 300 m thick, Fig. 2b), consists of sandstone intercalated with shale beds and overlies the fluvial sandstones of the Helvetiafjellet Fm (59–72 m thick, Grundvåg et al., 2019). The Festningen Member of the Helvetiafjellet Fm (11–18 m thick), comprises fractured sandstones and is relatively hydraulically conductive, as proven by cross-well water injection tests (Bælum et al., 2012).  
130 Directly below is the ~ 450 m thick Janusfjellet Subgroup (Fig. 2b) that comprises two shale-dominated units, the Rurikfjellet (201–232 m thick, Grundvåg et al., 2019) Agardhfjellet Formations (253–264 m thick, Koevoets et al., 2018). A regional detachment zone with extensive fracturing and swelling clays propagates near the boundary of these two formations (Braathen et al., 2012) and is considered a major barrier to fluid migration (Olaussen et al., 2020). The tectonic disturbances, as reflected in Festningen Sandstone and the detachment zone, make it possible that minor secondary permeability development is present  
135 elsewhere in the stratigraphy. This would have implications for groundwater movement in the system, which is otherwise predominantly through rocks with low hydraulic conductivity (Table 3).

The glacier advances during the last glacial maximum (LGM) on Svalbard (~ 20 ka (ka = 10<sup>3</sup> yr before present)) are thought to have completely eroded any pre-existing glacial deposits in the inner fjords of Svalbard (Elverhøi et al., 1995) and the Quaternary succession in Adventdalen thus postdates this event. Optically stimulated luminescence (OSL) datings in three  
140 cores from Adventdalen (S1, S2, and S3, Fig. 2a) support this (Gilbert et al., 2018). The Quaternary succession overlies fractures in the underlying sedimentary strata, possibly explained by glacier load/unload and freeze-thaw processes (Benn and Evans, 2010; Gilbert et al., 2018), as well as the significant tectonic uplift in the area. The presumed high hydraulic conductivity of this fracture zone is in contrast to the generally low-permeability of the Quaternary succession. The lowermost Quaternary unit is a < 5 m thick, subglacial lodgement till deposited during the last Weichselian glacial advance. Overlying the till, a  
145 shallowing-upwards trend is observed in the gradually changing succession of marine muds (< 20 m), pro-deltaic to deltaic muds and very fine-grained sands (< 35 m), tidally influenced (saline) fluvial fine-grained sands (< 35 m), and aeolian loess deposits (< 5 m). This reflects Holocene progradation of the present delta-system (Cable et al., 2018; Gilbert et al., 2018).

The sub-permafrost groundwater often has hydraulic heads above hydrostatic, which results in artesian conditions. This is evident from the occurrence of several pingo springs and from artesian outflow from deep boreholes (> 100 m below  
150 ground level (b.g.l.)) at the confluence of Bolterdalen and Adventdalen (Malte Jochmann, pers. comm.; SNSK, Unpublished


Reports SN1981\_008 and SN1983\_004). Based on artesian outflow during a drilling experiment nearby, Braathen et al. (2012) deduce a hydraulic pressure of 18 to 23 bars at a depth of ~ 175 m b.g.l. in well DH4 (Festningen Member, Fig. 2), which corresponds to a hydraulic head of 9 to 60 m above hydrostatic when the potential pressure effects of the dissolved gasses are excluded. Significant under-pressure ~ 50 bar below hydrostatic is recognised in deeper stratigraphical layers (~ 800 m b.g.l.) and is believed to relate to glacial unloading, extensive fracturing and matrix expansion (Birchall et al., 2020; Braathen et al., 2012; Wangen et al., 2016). The low pressure indicates hydrogeological separation from upper groundwaters immediately beneath the permafrost, in line with Sr-isotope analyses from the drill cores (Huq et al., 2017; Ohm et al., 2019).

### 3.2 Late Weichselian and Holocene climate history

Air temperatures on Svalbard have been continuously recorded at Longyearbyen Airport since 1911 (Nordli et al., 2014). Until the 1990s, the 30-yr running mean of MAATs was -6.0 °C, while it has increased to -4.2 °C in the period 1988 to 2017 (Hanssen-Bauer et al., 2018). For the entire temperature record, the mean summer air temperature (MSAT) has consistently been 10 °C warmer than the MAAT (on the 30-yr scale, Førlund et al., 1997). Further back in time, Holocene mean summer sea temperatures (MSST) in and around Svalbard are relatively well constrained by fossil-based temperature reconstructions (Fig. 3a, van der Bilt et al., 2018; Hald et al., 2007; Mangerud and Svendsen, 2017). Mangerud and Svendsen (2017) point out that the MSST is essentially identical to the MSAT.

**Table 1** Absolute ages from Adventdalen constraining delta propagation. Depending on the dated material and the host sediment, the dating indicates minimum, approximate or maximum valley floor ages. See Fig. 2 for site locations. HML = Holocene marine limit. Compiled from <sup>i</sup>Åhman (1973), <sup>ii</sup>Svensson (1970), <sup>iii</sup>Gilbert et al. (2018), <sup>iv</sup>Yoshikawa and Nakamura (1996) and <sup>v</sup>Lønne and Nemeč (2004).

Site/Event	Distance to modern delta front [m]	Dating method	Dating material	Age of valley floor [yr BP]
LP	~340	C-14	Peat	>240 (±50) <sup>i</sup>
LYRP	~3650	C-14	Driftwood	<2650 (±55) <sup>ii</sup>
S3	~4300	Quartz OSL	Quartz	~3000 (±200) <sup>iii</sup>
FHP	~6400	C-14	Shell	<6980 (±70) <sup>iv</sup>
S2	~7500	C-14	Plant matter	<9178 (±153) <sup>iii</sup>
HML	~16000	C-14	Shell	<10025 (±160) <sup>v</sup>



**Figure 3** Holocene temperature reconstructions in and around Svalbard. Dashed grey area indicate time of minimal driftwood arrival (Farnsworth et al., 2020). The unit of the time axis is ka =  $10^3$  years before present. **(a)** MSST curves (= MSAT, see text). Red line from Mangerud and Svendsen (2017). Orange line from Hald et al. (2007). Blue line from van der Bilt et al. (2018). **(b)** MAAT used in this work.

175 Based on Mangerud and Svendsen (2017) and Førland et al. (1997) (see Sect. 4.3.3).

At the last glacial maximum (LGM) occurring at  $\sim 20$  ka, glaciers covered all fjords in Spitsbergen (Ingólfsson and Landvik, 2013). By  $\sim 11.5$  ka the central parts of Isfjorden were glacier-free and its inner tributaries followed at  $\sim 11.2$  ka (Forwick and Vorren, 2011; Gilbert et al., 2018). If any glacier ice remained in Adventdalen after then, it was certainly gone  
 180 by  $\sim 10$  ka when non-glacial sediments were deposited in the valley head (Lønne and Nemeč, 2004). The eustatic sea-level rise caused by northern hemispheric deglaciation during Late Quaternary and Early Holocene was surpassed on Svalbard by the rate of its postglacial rebound. The Holocene marine limit (HML) ranges from  $\sim 20$  m above sea level (a.s.l.) in the northwestern part of Spitsbergen to  $\sim 90$  m a.s.l. in the central part (Forman, 1990). In Adventdalen, raised marine sediments suggest a HML of  $\sim 62$  m a.s.l. and  $\sim 70$  m a.s.l. in the inner and outer part of the valley, respectively (Lønne and Nemeč,  
 185 2004). Although not well constrained, the relative sea level is estimated to have fallen pseudo-exponentially until reaching close to present levels  $\sim 5$  ka (Lønne and Nemeč, 2004). Despite the uncertainty of sea-level fall, the fjord retreat and the associated exposure of new valley floor are relatively well constrained by absolute dating presented in previous work (Table 1).

190 **Table 1** Absolute ages from Adventdalen constraining delta propagation. Depending on the dated material and the host sediment, the dating indicates minimum, approximate or maximum valley floor ages. See Fig. 2 for site locations. HML = Holocene marine limit. Compiled from <sup>I</sup>Åhman (1973), <sup>II</sup>Svensson (1970), <sup>III</sup>Gilbert et al. (2018), <sup>IV</sup>Yoshikawa and Nakamura (1996) and <sup>V</sup>Lønne and Nemeč (2004).

<u>Site/Event</u>	<u>Distance to modern delta front [m]</u>	<u>Dating method</u>	<u>Dating material</u>	<u>Age of valley floor [yr BP]</u>
<u>LP</u>	~340	C-14	Peat	> 240 ( $\pm 50$ ) <sup>I</sup>
<u>LYRP</u>	~3650	C-14	Driftwood	< 2650 ( $\pm 55$ ) <sup>II</sup>
<u>S3</u>	~4300	Quartz OSL	Quartz	~ 3000 ( $\pm 200$ ) <sup>III</sup>
<u>FHP</u>	~6400	C-14	Shell	< 6980 ( $\pm 70$ ) <sup>IV</sup>
<u>S2</u>	~7500	C-14	Plant matter	< 9178 ( $\pm 153$ ) <sup>III</sup>
<u>HML</u>	~16000	C-14	Shell	< 10025 ( $\pm 160$ ) <sup>V</sup>

### 3.3 Permafrost, pingos and the apparent lack of groundwater recharge

195 In the valley floor of Adventdalen, the permafrost thickness ranges from ~ 0 m at the coast to ~ 200 m inland. In the adjacent mountains it increases to > 450 m (Christiansen et al., 2005; Humlum et al., 2003; Liestøl, 1977). One observation of the freezing front depth at Lagoon Pingo (Harada and Yoshikawa, 1996) and permafrost depth observations at well DH4 (Braathen et al., 2012), Endalen, Sarkofagen (both Liestøl, 1977), and Breinosa (Christiansen et al., 2005) support this regional characterisation (Fig. 2a). Mountain permafrost is presumably of Weichselian age, while permafrost in valleys postdates the  
 200 Late Holocene (Humlum, 2005). The continuous permafrost and a lack of warm-based glaciers in the adjacent highlands most likely hinder subglacial recharge to the sub-permafrost aquifer due to the impervious frozen ground (Burt and Williams, 1976; Haldorsen et al., 2010; McCauley et al., 2002; Walvoord and Kurylyk, 2016; Woo, 2012).

Sub-zero temperatures are a prerequisite for permafrost formation and its thickness essentially reflects equilibration to the geothermal heat flow (French, 2017). In the Adventdalen area, measurements of the geothermal gradient range from  
 205 0.02 °C m<sup>-1</sup> in the highlands to 0.03 °C m<sup>-1</sup> in the valley bottoms (Betlem et al., 2019; Liestøl, 1977).


Open-system pingos are a common feature in Svalbard and Adventdalen (Humlum et al., 2003), where five of them are distributed parallel to the valley axis (Fig. 2a). The three outermost; Lagoon, Longyear and Førstehytte Pingos, are all located on the northeastern side of the valley. All three have formed in Quaternary marine muds (Yoshikawa and Harada, 1995) and close to the sedimentary bedrock boundary (Fig. 2b). In the valley head, two additional pingos are located close to  
 210 the boundary of HML; Innerhytte and River Pingos. They have formed in shales above a major fault and are situated in the valley floor in the path of the river Adventelva (Yoshikawa and Harada, 1995). With the exception of the seemingly inactive Longyear Pingo, groundwater has discharged perennially from springs located at the pingos, at least since the earliest recordings in the 1920s (Orvin, 1944). However, visible spring outflow (or winter icing) at Førstehytte Pingo was not observed from summer 2018 until October 2019. Presumably, during that time, groundwater flow through the permafrost continued, but  
 215 instead of discharging to the surface, groundwater froze within the pingo and added to its growth. From Lagoon Pingo, Yoshikawa and Harada (1995) reported a spring discharge of 0.013 to 0.016 L s<sup>-1</sup>, Hodson et al. (2019) estimated ca. 0.3 L s<sup>-1</sup> during the 2017 summer, and we measured 0.26 L s<sup>-1</sup> in August 2019. At Innerhytte Pingo, Yoshikawa and Harada (1995) measured a discharge rate of 0.11 L s<sup>-1</sup>, which is somewhat smaller than Liestøl's (1977) estimate in 1976 of ~ 1 L s<sup>-1</sup>. Based



on our own “by the eye” ~~observations~~ estimates involving no quantitative measurements, the discharge rate at Førstehytte Pingo was in orders of  $0.1 \text{ L s}^{-1}$  when visited in fall of 2015, 2016 and 2017, and less than  $0.01 \text{ L s}^{-1}$  when rediscovered in October 2019.

#### 4 Method - Numerical modelling

Several numerical model codes are capable of simulating coupled heat and groundwater transport in permafrost environments (Grenier et al., 2018). However, the benchmark models do not consider the overpressure produced by ice expansion. To include this process, we decoupled the modelling of heat flow from sub-permafrost groundwater flow and made use of a source term to mimic the pressure effects of permafrost aggradation (Fig. 4). Ground temperatures and permafrost dynamics were simulated in the vertical dimension using a custom made finite-difference 1D transient heat transfer model (hereafter just 1DHT) coded in MATLAB R2019b (MathWorks®, 2019). The 1DHT model script is publicly available at DOI:10.5281/zenodo.3578839. Groundwater flow was modelled 3D steady-state with MODFLOW in the groundwater modelling software GMS 10.4 (AQUAVEO™, 2019). The connection between the two models was the permafrost aggradation rates simulated by the 1DHT, which determined the only water source for the groundwater model. The decoupled approach does not simulate advective nor lateral heat transport. The potential limitations will be assessed in the Discussion (Sect. 6.2.1).



235 **Figure 4** Schematic overview of the inner workings of the decoupled heat and groundwater model. Model setup, calculations and algorithms are indicated with sharp corners and bold text. Validation and comparison of simulations and observations are indicated with round corners and italics. Input and output data are indicated with rounded corners, grey background and normal text.

#### 4.1 Heat flow

240 Heat flow was modelled one-dimensionally in the vertical dimension, which is a common approach for permafrost models (Riseborough et al., 2008). Following from Fourier's law and conservation of energy, the 1D conductive heat flow equation states that:

$$\frac{\delta T}{\delta t} = \frac{k_e}{\rho_e \cdot c_e} \cdot \frac{\delta^2 T}{\delta z^2} \quad (1)$$

where  $T$  is temperature [K],  $t$  is time [s],  $z$  is distance [m], and  $k_e$ ,  $\rho_e$ , and  $c_e$  are the effective values of the thermal conductivity [W (m K)<sup>-1</sup>], density [kg m<sup>-3</sup>], and specific heat capacity [J (kg K)<sup>-1</sup>], respectively. The term  $\frac{k_e}{\rho_e \cdot c_e}$  equates to  $\alpha_e$ , the effective



thermal diffusivity [ $\text{m}^2 \text{s}^{-1}$ ]. As heat transfer was modelled one-dimensionally, simulating advective heat transfer was not possible. The ratio of advection to conduction heat transfer rates may be quantified by a Peclet number (Bergman et al., 2011):

$$P_{eL} = \frac{vL}{\alpha_e} \quad (2)$$

where  $v$  is the pore water velocity and  $L$  is the characteristic length.

In the case of a saturated medium, heat will be conducted through a matrix of solids (i.e., sediment or rock) and liquid water, ice or a mixture. The effective thermal parameters were assumed independent of temperature, but the fractions of water and ice changed between the solidus and liquidus temperatures,  $T_S$  and  $T_L$  respectively. The fraction of liquid water within the pore space,  $f_w$ , was determined using a smoothed step function (same approach as Mottaghy and Rath, 2006):

$$f_w = \begin{cases} \exp\left(-\left(\frac{T-T_L}{w}\right)^2\right) & \text{if } T < T_L \\ 1 & \text{if } T > T_L \end{cases} \quad (3)$$

where  $w$  [K] determines the shape of the freezing curve. For this work  $w \approx 0.96$ , implying that  $T_S = -2 \text{ }^\circ\text{C}$  and  $T_L = 0 \text{ }^\circ\text{C}$ . Bonacina and Comini (1973) and Mottaghy and Rath (2006) note that the exact shape of the freezing curve is of little importance for the calculated temperatures, but that a smoother function generally improves the performance of a numerical model due to a more efficient convergence of the numerical approximation. The total fractions of soil or rock ( $F_s$ ), water ( $F_w$ ), and ice ( $F_{ice}$ ) are described respectively as;  $F_s = 1 - n$ ,  $F_w = f_w \cdot n$ , and  $F_{ice} = n - F_w$  with  $n$  being the total porosity. The effective thermal conductivity was calculated as root-square-mean, as done by Mottaghy and Rath (2006) and Govaerts et al. (2016). When temperature change occurs between  $T_S$  and  $T_L$ , freezing or thawing results in the release or absorption of latent heat,  $L = 333.6 \text{ kJ kg}^{-1}$  (Mottaghy and Rath, 2006). The latent heat of fusion was included in the expression of the equivalent volumetric heat capacity [ $\text{J (m}^3 \text{ K}^{-1})$ ],  $C_{eq}$  (same approach as Govaerts et al., 2016):

$$C_{eq} = c_e \cdot \rho_e = F_s \cdot \rho_s \cdot c_s + F_w \cdot \rho_w \cdot \left(c_w + \frac{\delta f_w}{\delta T} \cdot L\right) + F_{ice} \cdot \rho_{ice} \cdot \left(c_{ice} + \frac{\delta f_w}{\delta T} \cdot L\right) \quad (4)$$

where subscripts  $s$ ,  $w$ , and  $ice$  indicate parameters of soil or rock, water, and ice, respectively.

To validate the model code we compared simulations with two analytical solutions; Neumann's solution as presented by Carslaw and Jaeger (1959) and Mottaghy and Rath (2006); and an analytical solution of a step change in temperature neglecting latent heat effects as presented by Carslaw and Jaeger (1959) and Eppelbaum et al. (2014). The model code was able to reproduce the analytical results with root-mean-square errors of respectively  $1.1 \cdot 10^{-2}$  and  $1.3 \cdot 10^{-5}$  and these numbers were regarded to represent reasonable-an acceptable level of accuracy for the given purpose. The model code validation is described in detail in the supplementary info.

## 4.2 Groundwater flow

Following from Darcy's law and the conservation of mass, the 3D groundwater flow equation fundamental for groundwater modelling can be described as (Fitts, 2002):

$$K_x \frac{\delta^2 h}{\delta x^2} + K_y \frac{\delta^2 h}{\delta y^2} + K_z \frac{\delta^2 h}{\delta z^2} + Q_N = S_s \frac{\delta h}{\delta t} \quad (5)$$

where  $x$ ,  $y$  and  $z$  are distances [m] in the three dimensions,  $K$ 's are hydraulic conductivities [ $\text{m s}^{-1}$ ] in those dimensions,  $h$  is the hydraulic head [m],  $Q_N$  is a term representing any potential sink or source [ $\text{m}^3 \text{s}^{-1}$ ] (i.e., recharge, seepage, etc.),  $S_s$  is the specific storage, and  $t$  is time [s]. In this work, groundwater flow was modelled as a steady-state implying that the right-hand side of Eq. (5) equals 0. However, in the discussion of the model simulation results, hydrodynamic storage effects resulting from the glacial loading and unloading are considered.

Groundwater flow was simulated with MODFLOW, which solves the 3D groundwater flow equation with the finite-difference method (McDonald and Harbaugh, 1988). We approximated the pressure build-up from the simulated rate of permafrost aggradation,  $R_{PF}$ , by considering that it must correspond to some equivalent recharge rate (or source term,  $Q_N$  in Eq. 5),  $REq$ . Assuming no expansion or compression of the matrix,  $REq$  is specifically proportional to  $R_{PF}$ , the total porosity,  $n$ , and the expansion of water upon freezing,  $X_w$ :


$$\begin{aligned} REq &= R_{PF} \cdot n \cdot X_w && [\text{m s}^{-1}] && (6) \\ Q_{REq} &= REq \cdot A && [\text{m}^3 \text{s}^{-1}] \end{aligned}$$

where  $Q_{REq}$  is equivalent to the source term  $Q_N$  in Eq. (5), and  $A$  is an area [ $\text{m}^2$ ].

### 4.3 Setup and boundary conditions

#### 4.3.1 Geological model

In order to define proper geothermal and hydrogeological properties, a geological model of the subsurface in Adventdalen was built. Towards northwest, the model covers the tidal flat (Fig. 2a), but no other sea-covered areas were included. Elsewhere, the horizontal model boundary was a simplified outline of the HML. The lower boundary is at 300 m b.g.l. (Fig. 5a). We used data from boreholes, seismic lines (see locations and references on Fig. 2a), and a geological map with DEM provided by the Norwegian Polar Institute (2019). The general workflow was to map relevant geological boundaries in 3D with the petroleum industry software Petrel v2016 (Schlumberger©, 2019), then use them to build geological layers with the TIN and SOLIDS editor functions GMS 10.4 (AQUAVEO™, 2019). For the 1DHT model, the geology was simplified into one-dimensional columns for a total of 12 zones of the model area. The zones were defined as follows: The age of the valley floor (Table 1) was used to infer isochrones of valley floor exposure with intervals of 1000 yrs (Fig. 5a). The isochrones defined boundaries between the zones and ~~the their~~-names of the zones (i.e., the zone located between the 5 ka and 6 ka isochrones was named zone 5-6, Fig. 5b). The area between isochrones 9 ka and 10 ka was divided into two zones (9-10a and 9-10b) to incorporate geological variation.



**Figure 5** (a) 3D geological model of the subsurface below the valley floor in Adventdalen and vertical 1D simplifications (inset in upper right corner) below zones of the model area. The former determines the hydrogeological properties in the groundwater model (Table 3), whereas the latter determines the geothermal properties in the 1DHT model (Table 2). The domain of the 1DHT model extends to 1000 m b.g.l. (not shown). Deeper than 300 m b.g.l., geothermal properties were defined as for Janusfjellet Subgroup. The sea retreat reconstruction was inferred from absolute datings (Table 1) and is illustrated by valley floor exposure isochrones (red dashed lines). Pingos are indicated with blue arrows. (b) Vertical view of the model area showing the zonation. The aforementioned isochrones defined the zone names so that the valley floor exposure age of a zone is apparent from its name (i.e., zone 0-1 became sub-aerially exposed between 1 and 0 ka, zone 1-2 between 2 and 1 ka, etc.).

### 310 4.3.2 Geothermal and hydrogeological properties

Due to the sparse data available from the field area, geothermal and hydrogeological properties of the lithologies in the model domain (Tables 2 and 3) were largely based on the available literature. The considerable contrast between the thermal properties of water and ice implied that porosity was the most important parameter for permafrost growth, and realistic minimum, intermediate, and maximum values were therefore defined for the 1DHT model (Table 2). The permafrost base is presently located within the upper two thirds of the Janusfjellet Subgroup (Figs. 2b and 5a). Estimated burial depths and thicknesses of overlying units (Grundvåg et al., 2019; Marshall et al., 2015) indicate that this strata has been buried to maximum depths between 2150 to 2600 m b.g.l. corresponding to effective vertical stresses between 34 to 41 MPa (assuming a rock density of  $2.6 \text{ kg m}^{-3}$  and hydrostatic equilibrium). Different studies on the compressibility of lithologically and age equivalent rocks in the North Sea thus suggest porosities between 0.08 to 0.3 (Burland, 1990; Okiongbo, 2011; Skempton, 1969; Yang and Aplin, 2004). and we therefore used this range in our modelling experiments. An exception to the purely

literature-based values is the sandstone units of which the matrix porosity and vertical permeability,  $\kappa_v$ , were measured as part of the Longyearbyen CO<sub>2</sub> Laboratory Project (Olaussen et al., 2020, and references therein). The small-scale horizontal permeability,  $\kappa_h$ , for sandstones is typically a factor two higher than  $\kappa_v$  (Domenico and Schwartz, 1998). The horizontal hydraulic conductivity,  $K_h$ , was therefore calculated using the measurements of  $\kappa_v$  by Braathen et al. (2012) as

$$K_h = C_{Kh/Kv} \cdot \frac{\kappa_v \cdot \rho_w \cdot g}{\mu} \quad (7)$$

where  $C_{Kh/Kv}$  is the conversion factor (i.e., 2 for this work),  $\kappa_v$  is permeability [m<sup>2</sup>],  $\rho_w$  is the density of water [kg m<sup>-3</sup>],  $g$  is the gravitational acceleration [m s<sup>-2</sup>], and  $\mu$  is the dynamic viscosity of water [kg (m s)<sup>-1</sup>]. The range of the hydraulic conductivity values of the Carlinefjellet and Helvetiafjellet formations (Festningen Sandstone not included) was defined by the 25 %, 50 % and 75 % percentiles of a [Weibull-log-logistic](#) probability fit of the measured values ([details provided in Supplement](#)). Ranges of hydraulic conductivity for the fluvio-deltaic succession were based on literature values from (Fitts, 2002). For the remaining bedrock units we also regarded the influence of fractures (Singhal and Gupta, 2010). All within these ranges, three sets of hydraulic conductivity defined the different model scenarios Sc1–3x (Table 3). For steady-state simulations, the porosity does not affect the net groundwater fluxes (i.e., discharge and Darcy fluxes, Eq. 5). To evaluate the pore water velocities, however, the effective porosity is of importance. We used the same values of effective porosity for all groundwater model simulations (Table 3).

**Table 2** Geothermal material properties used in the heat transfer model. Density and thermal properties compiled from <sup>I</sup>Williams and Smith (1989), <sup>II</sup>Robertson (1988), and <sup>III</sup>Manger (1963). Porosities from <sup>IV</sup>Fitts (2002), <sup>V</sup>Braathen et al. (2012), and based on works by <sup>VI</sup>Burland (1990), Grundvåg et al. (2019), Marshall et al. (2015), Okiongbo (2011), and Yang and Aplin (2004) (see text).

Material	Thermal conductivity [J (yr m K) <sup>-1</sup> ]	Specific heat capacity [J (kg K) <sup>-1</sup> ]	Density [kg m <sup>-3</sup> ]	Thermal diffusivity [m <sup>2</sup> s <sup>-1</sup> ]	Total porosity [m <sup>3</sup> m <sup>-3</sup> ]		
					Min	Intermediate	Max
Water	<sup>I</sup> 1.77·10 <sup>7</sup>	<sup>I</sup> 4180	<sup>I</sup> 1000	1.34·10 <sup>-7</sup>	-	-	-
Ice	<sup>I</sup> 7.06·10 <sup>7</sup>	<sup>I</sup> 2100	<sup>I</sup> 917	1.16·10 <sup>-6</sup>	-	-	-
Silty sand (Qt)	<sup>II</sup> 1.58·10 <sup>7</sup>	<sup>I</sup> 850	<sup>III</sup> 2400	2.46·10 <sup>-7</sup>	<sup>IV</sup> 0.3	<sup>IV</sup> 0.4	<sup>IV</sup> 0.5
Sandstone	<sup>II</sup> 7.88·10 <sup>7</sup>	<sup>II</sup> 900	<sup>III</sup> 2600	1.01·10 <sup>-6</sup>	<sup>V</sup> 0.06	<sup>V</sup> 0.1	<sup>V</sup> 0.15
Shale	<sup>II</sup> 4.73·10 <sup>7</sup>	<sup>II</sup> 800	<sup>III</sup> 2600	7.21·10 <sup>-7</sup>	<sup>VI</sup> 0.08	<sup>VI</sup> 0.19	<sup>VI</sup> 0.3

**Table 3** Properties of the hydrogeological units used in the groundwater model. Values based on <sup>I</sup>Fitts (2002) and <sup>II</sup>Singhal and Gupta (2010) or evaluated from <sup>III</sup>Braathen et al. (2012) ([see details provided in Supplement](#)).

Hydrogeological unit	Lithology	Hydraulic conductivity [m day <sup>-1</sup> ]			Effective porosity All
		Sc1x	Sc2x	Sc3x	
<sup>I</sup> Qt1	Clay, silt and sand	10 <sup>-4</sup>	10 <sup>-3</sup>	10 <sup>-2</sup>	0.4
<sup>I</sup> Qt2	Heavily fractured bedrock	10 <sup>-2</sup>	0.1	1	0.4
<sup>III</sup> Carolinefjellet Fm	Sandstone	2·10 <sup>-4</sup>	5·10 <sup>-4</sup>	10 <sup>-3</sup>	0.1
<sup>III</sup> u. Helvetiafjellet Fm	Sandstone	2·10 <sup>-4</sup>	5·10 <sup>-4</sup>	10 <sup>-3</sup>	0.1
<sup>I, II</sup> Festingen Sandstone	Fractured sandstone	5·10 <sup>-2</sup>	7.5·10 <sup>-2</sup>	0.1	0.1
<sup>I, II</sup> Janusfjellet Subgroup	Shale	5·10 <sup>-4</sup>	7.5·10 <sup>-4</sup>	10 <sup>-3</sup>	0.1
<sup>I, II</sup> Detachment zone	Fractured shale	5·10 <sup>-3</sup>	7.5·10 <sup>-3</sup>	10 <sup>-2</sup>	0.1

### 4.3.3 1D transient heat transfer model (1DHT)

The model domain contained 12 columns, each 1000 m long and consisting of 500 cells with a height of 2 m. One column was associated to each of the model area zones and the geothermal properties were defined according to the associated geological 1D simplifications (see insert on Fig. 5~~ab~~). Deeper than 300 m b.g.l., the properties were that of the Janusfjellet Subgroup. The simulation run time was defined by the valley floor age inferred for that zone (Fig. 5), so that, for zone 0-1 the simulation period was 0.5 to 0 ka, for zone 1-2 it was 1.5 to 0 ka, etc. For zone 10, the simulation period was 10 to 0 ka. The initial ground temperature distribution followed the geothermal gradient reported by Liestøl (1977) ( $0.025\text{ }^{\circ}\text{C m}^{-1}$ ) from a surface temperature of  $0\text{ }^{\circ}\text{C}$ . At any subsequent time, the lower boundary condition was defined from the same geothermal gradient resulting in a basal temperature change of less than  $0.65\text{ }^{\circ}\text{C}$ . The upper boundary condition was defined by the Holocene MAAT curve presented in Fig. 3b. Assuming that the present  $10\text{ }^{\circ}\text{C}$  difference between MAAT and MSAT (Førland et al., 1997) was alike for the entire Holocene, we constructed this curve (Fig. 3b) by subtracting  $10\text{ }^{\circ}\text{C}$  from the MSST curve by Mangerud and Svendsen (2017) (Fig. 3a). As illustrated on Fig. 3a, their MSST curve is largely in agreement with MSST temperature reconstructions from west and southwest of Svalbard (van der Bilt et al., 2018; Hald et al., 2007). We chose to rely on Mangerud and Svendsen (2017) because; a) their curve is more local to our field area than the alternatives and; b) the suggested timing of the Holocene thermal minimum at  $\sim 3$  to  $2$  ka is in agreement with the maximum of perennial or semi-permanent land fast sea ice at  $\sim 2.5$  to  $2$  ka inferred from the minimal occurrence of dated driftwood (Dyke et al., 1997; Farnsworth et al., 2020; Funder et al., 2011). Furthermore, their curve is better supported by geomorphological evidence of glacier dynamics (Farnsworth et al., 2020).

### 4.3.4 Groundwater model

For the groundwater model, each grid cell measured  $100$  by  $100$  by  $5$  m ( $x\ y\ z$ ) and their hydrogeological properties were defined from the geology (Fig. 5a, Table 3). The model domain was defined from the geological model therefore covering an elongated ground surface area of  $59\text{ km}^2$  that is  $< 4$  km broad and  $\sim 18$  km long (Fig. 5b). Frozen ground was considered impervious and cells shallower than the simulated freezing front depth were thus de-activated. The lower boundary was at  $300$  m b.g.l. The fjord was simulated with a general head of  $0$  m a.s.l. ~~and assigned to the relevant cells and~~ the conductance was determined according to the hydraulic conductivity (Table 3). The area assigned with this boundary conditions comprised 24 cells located within the uppermost layer at the northwestern end of the model domain. The MODFLOW drain package was used to simulate pingo springs. Because the cells located at the springs were inactivated, the drains were assigned to the uppermost active cells located closest to springs, but within the conductive Festningen Sandstone if present in the underlying stratigraphy (i.e., Lagoon and Førstehytte Pingos, Fig. 5a). Drain levels were set according to spring elevations (i.e.,  $1$ ,  $20$ ,  $65$ , and  $77$  m a.s.l. for Lagoon, Førstehytte, Innerhytte, and River Pingos, respectively). The simulated springs were able drain more water than the cells they were situated in could transmit. That is, the conductance was set ~~more than~~ high enough not to restrict any discharge. Except for the fjord and the springs, all outer model boundaries were assigned no-flow conditions~~ed~~.

375 The only source of water in the groundwater model was defined from the basal permafrost aggradation rate simulated  
by the 1DHT model and assigned as recharge to the uppermost active cells in the model domain. To compensate for the lack  
of dynamic storage effects in the steady-state model, we applied a moving time-average to the simulated basal permafrost  
growth (or decay) before calculating the recharge equivalent (Eq. 6). The time window of the moving average was based on  
the possible range of the adjustment time,  $t_a$ , which is the time needed for fluids to redistribute to a pressure perturbation (e.g.,  
380 Neuzil, 2012; Šuklje, 1969):

$$t_a = l^2 S_s K^{-1} \quad (8)$$

where  $l$  is half of the shortest dimension of the system (the characteristic length),  $S_s$  is the specific storage, and  $K$  is the  
hydraulic conductivity. We found  $t_a$  to be shortest in the vertical dimension, but assumed that hydraulic pressures could only  
dissipate in the horizontal dimension after the formation of continuous permafrost no earlier than 6 ka (Humlum, 2005; this  
385 research). Specifically, we estimated the horizontal  $t_a$  to be between 20 and 19000 yrs. To quantify this, we used a  
characteristic length of 1 km. For  $S_s$ , we used a matrix compressibility of  $7 \cdot 10^{-10}$  to  $7 \cdot 10^{-8} \text{ Pa}^{-1}$  (based on common estimates for  
fractured rocks, e.g., Domenico and Mifflin, 1965; Domenico and Schwartz, 1998; Fitts, 2002) yielding a  $S_s$  of  $7 \cdot 10^{-6}$  to  $7 \cdot 10^{-4}$   
 $\text{m}^{-1}$  (in line with literature values, c.f. Singhal and Gupta, 2010). For  $K$ , we used the values estimated for the dominating  
geological unit (Janusfjellet Subgroup, Table 3). The time window used to compensate for dynamic storage effects were  
390 defined from the above, but no longer than the age of permafrost (i.e., 6000 yrs or less).

To represent the uncertainty of how permafrost aggradation affects sub-permafrost groundwater flow, we simulated  
nine different scenarios that were defined by having three sets of values for the two fundamental parameters in any  
combination; hydraulic conductivity (Scenarios Sc1–3x, Table 3) and equivalent recharge (Scenarios ScXa–b, values  
calculated as described above and by Eq. 6). The nine scenarios are all labelled ScXx where X and x indicates the minimum,  
395 intermediate or maximum value sets of hydraulic conductivity and equivalent recharge, respectively. We further simulated a  
tenth scenario that takes additional pressure sources into account.

## 5 Results


### 5.1 1DHT model results

The direct output from running the 1DHT model code was matrices containing the temperatures throughout the model domain  
400 for each time step in the simulation period. For each time step, the permafrost and freezing front depths were calculated by  
interpolating the depth at which the associated temperatures occurred. The greatest phase change rate in the 1DHT model  
occurs at a temperature of  $-0.7 \text{ }^\circ\text{C}$  (following from Eq. 3) and it was therefore the progression rate of this isotherm that was  
used for the calculation of the equivalent recharge (by net pore space loss, Eq. 6). Hereafter, ‘permafrost aggradation’ therefore  
means the downwards progression rate of this isotherm ( $-0.7 \text{ }^\circ\text{C}$ ), although this is not entirely congruent with the thermal  
405 definition of permafrost (ground perennially below  $0 \text{ }^\circ\text{C}$ , French, 2017). Since phase change occurs over a temperature range,

the porosity used to calculate the equivalent recharge was taken as a weighted mean of the porosities in the corresponding cell range, where the weight was proportional to the phase change rate.

### 5.1.1 Permafrost and freezing front depth

In Fig. 6, the simulated Holocene ground temperature development in Adventdalen is exemplified by the growth of frozen ground and permafrost in zones 2-3, 7-8 and 9-10b when using the intermediate porosity values (Table 2). For the oldest part of the model area (most inland), an early occurrence of frozen ground was simulated during the Early Holocene cooling of 9 to 8 ka (Figs. 3 and 5). However, due to the subsequent warming at 8 to 6.5 ka, frozen ground was thawed and not re-established until ~ 6.5 ka. Since this time, deep ground temperatures were simulated to be cooling until present. The pattern was identical for simulations with lower and higher porosities (not shown) although the depths were different (as illustrated on Figs. 7a).




**Figure 6** Development of simulated freezing front and permafrost front depths from zones 2-3, 7-8 and 9-10b of the model area (see Fig. 5). These simulation results derive when using the intermediate porosity values (Table 2). Note that completely frozen ground does not establish permanently until ~ 6.5 ka.

Depending on the scenario, the 1DHT model simulated present day permafrost and freezing front depths of respectively 165 to 184 and 110 to 124 m b.g.l. at distances further than 6 km from the delta front (Fig. 7). Closer to the delta front both isotherms are located at shallower depths and decrease to 58 to 65 m b.g.l. and 31 to 34 m b.g.l. The porosity plays an important role for the temperature development due to latent heat of the water (ice) filling the pore space and because water and ice account for the minimum and maximum thermal diffusivities in the model domain, respectively. In panel (a) of Fig. 7, an uncertainty field is drawn (shading) as derived from the applied porosity range (Table 2). The upper and lower edge of the

425 shaded area corresponds to the maximum and minimum porosity. The line corresponds to the intermediate porosity (Table 2).  
In panel (b), the simulated present permafrost aggradation rate is plotted by point symbols. The shaded area was drawn by  
applying the moving time-average correction defined using the estimated adjustment times (see Sect. 4.3.4, Eq. 8) and indicates  
the values used to calculate the equivalent recharge rates in panel (c). Here, the line indicates intermediate values of recharge  
added to the groundwater model, while the edges of the shaded area represent the lower and upper estimates. The scarcity of  
430 ground temperature observations does not allow for model calibration, but observations both at Lagoon Pingo (freezing front)  
and well DH4 (permafrost) agree relatively well with simulations.





435 **Figure 7** (previous page) Present-day permafrost conditions as simulated by the 1DHT model. (a) Freezing front and permafrost depths. The upper and lower edge of the shaded area corresponds to the maximum and minimum limits of the porosity range, while the curve and the points corresponds to the intermediate (Table 2). Permafrost depth and freezing front depth observations are from (Braathen et al., (2012) and Harada and Yoshikawa, (1996), respectively. (b) Rate of permafrost aggradation. The point symbols represent the present permafrost aggradation, while the shaded area is drawn by applying a time-moving average as described in Sect. 4.3.4. and represents the values used to calculate the equivalent recharge rates. \*It is the  $-0.7\text{ }^{\circ}\text{C}$  isotherm, which has been used to calculate this as the greatest phase change rate takes place at that temperature. (c) Equivalent recharge rate (net rate of loss in pore space). The points on the curve and the outer edges of the shaded area represent the recharge rates, which were assigned to the corresponding zones in the groundwater model.

### 5.1.2 Permafrost aggradation and recharge equivalent

445 Simulated rates of present permafrost aggradation ranged from  $-0.02 - 5\text{ cm yr}^{-1}$  and generally decreased up-valley with older exposure ages and for scenarios with lower porosity (Fig. 7b). The correction for dynamic storage effects generally increased the “effective” permafrost aggradation rate that was used to calculate the recharge equivalent. The reason for this was that basal permafrost growth was generally faster in the past (Fig. 6). For a homogeneous medium with one-sided freezing, the freezing front progression rate will decrease with time (as exemplified by Figure S2). At first, it therefore seems At first surprising that, the model simulations generally did not suggest that the highest aggradation rate occurred where permafrost is youngest (zone 0-1), but instead at zone 1-2. This was due to the heterogeneity in the model domain as expressed by the 450 different properties of the sediments and bedrock undergoing freezing. In zone 0-1, closest to the shore, phase change took place at  $< 60\text{ m b.g.l.}$  corresponding to the most porous and least thermally diffusive unit (Qt1, insert on Fig. 5a and Table 2). Thus, a relatively high amount of latent heat had to be released for the freezing front to aggrade. By contrast, the opposite was the case in zone 1-2, where the freezing front just entered the sandstone unit that possessed the lowest porosity (Carolinefjellet Fm, insert on Fig. 5a and Table 2). For the same reason, Fig. 7c shows that the pattern of the equivalent recharge decreases 455 from  $1.1 - 1.9\text{ mm yr}^{-1}$  closest to delta front (zone 0-1), to  $-0.02 - 0.16\text{ mm yr}^{-1}$  in zone 10 furthest up-valley.

### 5.2 Simulated groundwater flow paths and flow velocity distributions

The above simulated recharge equivalent rates were assigned to cells within the corresponding zones of the model area (Fig. 5b). The resulting outputs of the groundwater model for all scenarios are shown in Fig. 8. The equivalent recharge rates,  $REQ$ , calculated from the 1DHT model simulations resulted in a total inflow of water,  $Q_{REQ}$  to the groundwater system of 20, 40.5 and  $63.4\text{ m}^3\text{ day}^{-1}$  for the minimum, intermediate and maximum effective permafrost aggradation rate scenarios, respectively. 460 For the minimum recharge equivalent scenarios (Fig. 8a), the slightly negative recharge equivalent rates (i.e., permafrost thaw) simulated at distances further than 6 km from the delta front result in a total hydraulic pressure loss that corresponds to a discharge rate of  $2.4\text{ m}^3\text{ day}^{-1}$ .

465 ~~For the minimum  $Q_{REQ}$  and intermediate to maximum  $K$  scenarios, simulated heads were lower two scenarios (simulated heads—~~ Simulated hydraulic heads ranged from sea level to maxima between 119 m a.s.l. (maximum  $Q_{REQ}$  and

minimum  $K$  scenario, Fig. 8-1c) and 10 m a.s.l. (minimum  $Q_{REQ}$  and maximum  $K$  scenario, Fig. 8-3a). The only two exceptions ~~except for were~~ the minimum  $Q_{REQ}$  and intermediate to maximum  $K$  scenarios (Figs. 8-2a and 8-3a) for which hydraulic heads went down to -6 and -10 m a.s.l., respectively, in the up-valley part of the system. The simulated hydraulic head in well DH4 was generally within the range deduced from well outflow (Braathen et al., 2012), but significantly above for the maximum  $Q_{REQ}$  and minimum  $K$  scenario (Fig. 8-1c). For two other scenarios, the simulated head fell slightly outside the deduced range (above and below, respectively for the intermediate  $Q_{REQ}$  and minimum  $K$  scenario and the minimum  $Q_{REQ}$  and maximum  $K$  scenario, Figs. 8-1b and 8-3a). For the remaining six scenarios, the groundwater model simulated heads within the uncertainty range of the observation. As illustrated by the colour fill on Fig. 8, entirely or almost entirely artesian conditions were simulated for all but four scenarios (all small  $Q_{REQ}$  scenarios and the intermediate  $Q_{REQ}$  and maximum  $K$  scenario, Figs. 8-1a, 8-2a and 475 8-3a–b), where the up-valley part of the system has hydraulic pressures below ground level.


With the porosities listed in Table 3, groundwater flow paths and pore water velocities were evaluated from all simulations using particle tracking (Pollock, 2016). In order to visualise groundwater movement towards the outlet points, we used the particle tracking to draw 3 kyr catchment zones (the term ‘catchment’ is somewhat misleading in this context as no actual recharge takes place). The 3 kyr duration was chosen because it is on that order of time that the modelled permafrost and groundwater conditions likely existed. For most scenarios, water particle path lines (blue lines, Fig. 8) depicted a multidirectional flow pattern with local catchment zones for each outlet point. A more uniform down-valley-directed flow pattern was simulated for the intermediate  $Q_{REQ}$  and maximum  $K$  scenario (Figs. 8-3b). For the minimum  $Q_{REQ}$  scenarios (ScXa, Figs. 8-1a, 8-2a and 8-3a), the negative equivalent recharge rates in the up-valley part of the system (Fig. 7c) resulted in a bidirectional flow pattern with groundwater flowing away from a groundwater divide located ~ 2 km from the delta front. 480 The uniform and bidirectional flow patterns coincide with the partly non-artesian conditions and the lack of discharge at the up-valley pingo springs. As also illustrated by the size of the 3 kyr catchment zones, the simulated mean pore water velocities ranged from 0.05 to 0.14 m yr<sup>-1</sup> (Figs. 8-1a and 8-3c, respectively) and suggest a relatively stagnant groundwater system. This is in accordance with mean residence times that ranged from 60 to 950 kyr (respectively, maximum  $K$  and  $Q_{REQ}$  and minimum  $K$  and  $Q_{REQ}$  scenarios, Figs. 8-3c and 8-3a) and by far exceed the duration of the Holocene.

The colour fill and the ~~bar pie~~ charts on Fig. 8 together show that ~~the hydraulic pressure outflow below at~~ a pingo site ~~needs to be artesian in order for outflow to take place at the pingo~~ ~~only takes place if the hydraulic pressure is artesian~~. Outflow from all pingo sites were simulated for four scenarios including all three with maximum  $Q_{REQ}$  and the one with intermediate  $Q_{REQ}$  and minimum  $K$  (Figs. 8-1b–c, 8-2c and 8-3c). The simulated spring discharge rates (~~pie charts~~bar charts, Fig. 8) increased with increasing  $Q_{REQ}$  and decreasing  $K$ , and had a maximum value of 0.31 L s<sup>-1</sup> at FHP for the scenario with maximum  $Q_{REQ}$  and minimum  $K$  (Fig. 8-1c). The simulated proportion of the total outflow not discharging at the springs varied from 30 % to 89 % (the extremes respectively illustrated by Figs. 8-1c and 8-3a). For intermediate and maximum  $Q_{REQ}$  scenarios (ScXb–c, Fig. 8), ~~and~~ all of this discharged to the fjord, while, ~~for the minimum~~  $Q_{REQ}$  scenarios (ScXa, Fig. 8), a minor proportion of the outflow ~~represents phase change associated with~~ ~~is caused by~~ permafrost thaw, ~~which causes a storage~~

500 ~~redistribution within the model domain. for the minimum  $Q_{REQ}$  scenarios.~~ Larger proportions of outflow to the fjord were simulated in the case of maximum  $K$  and a small total inflow  $Q_{REQ}$ , with the former being the most important parameter.

505 **Figure 8** (next page) Groundwater model simulations from all 9 scenarios. The individual diagrams are sorted so that the hydraulic conductivity increase along the right-hand axis (scenarios **Sc1–3x**) and the equivalent recharge produced by permafrost aggradation increase along the left-hand axis (scenarios **ScXa–c**). On each diagram, the following simulation results are illustrated: Heads from the uppermost grid layer are shown in m a.s.l. by isopotential contours (note that the colour scales are different) and in m a.g.l. by the colour fill (see scale at the bottom of the figure). The groundwater outflow rates and distribution ~~and discharge rates~~ are illustrated by bar charts ~~pie charts~~ with the location of the discharge points (pingos and fjord) indicated on **(1c)**. \*For minimum ~~m~~  $Q_{REQ}$  scenarios (**1a**, **2a** and **3a**) part of the outflow represents phase change associated with permafrost thaw (Figs. 7b–c), which causes a storage redistribution within the model domain ~~is caused by basal permafrost thaw (Figs. 7b–c)~~. Flow patterns are illustrated by thin blue lines, which each depict pathways of particles released in the uppermost grid layer. The mean pore water velocities, shown in the upper left-hand corners, were calculated from the aforementioned particles and using the same porosities for all scenarios (Table 3). The areas outlined with thick dashed lines show where each outlet point were simulated to receive water from during 3 kyr. In the lower right-hand corner, the simulated head in well DH4 is illustrated on a range plot with the range defined as deduced ~~by~~ from 510 Braathen et al. (2012). The colour of the bar indicates if the simulated head falls within (green) or outside the deduced range with less (yellow) or more (red) than 10 % of the total range. The location of DH4 and the pingo springs is marked on **(1c)**.

Hydraulic conductivity



Equivalent recharge

## 6 Discussion

### 520 6.1 Alternative processes producing sub-permafrost overpressures

In this work, we contemplate the implication of deep (sub-permafrost) groundwater systems being restricted from recharge by impervious continuous permafrost. It seems enigmatic that anomalous overpressures and springs still persist in such landscapes, where the lack of warm-based ice at the bottom of glaciers or ice-sheets, or other features capable of maintaining through-taliks as pathways for groundwater flow, seem to rule out recharge from precipitation. Directly supporting the main  
525 research hypothesis, the outcomes of our investigation suggest that basal permafrost aggradation due to equilibration of ground temperatures may produce sufficient artesian pressures to sustain such a system. However, other mechanisms producing anomalous pressures relative to hydrostatic conditions cannot be excluded and are therefore considered below.

Anomalous pressures may occur in groundwater systems that are either hydrodynamically equilibrated or disequilibrated (Neuzil, 1995). ~~To clarify the meaning of equilibrated/disequilibrated in this context, -equilibrated systems~~  
530 ~~ans being~~ are in a steady-state condition with the geological and hydrological setting, while disequilibrated systems are not. For the former, anomalous pressures are typically produced by topography-driven head gradients, but as the permafrost conditions in Adventdalen seem to rule out this process, we focus on the disequilibrium-type of anomalous pressures. These result from geological or glacial processes and can be further classified into systems where anomalous pressures equilibrate to past or ongoing perturbations. Anomalous pressure produced by permafrost aggradation is an example of the latter and we will  
535 discuss this in Sect. 6.3 using the model simulation results. First we consider the alternative processes.

#### 6.1.1 Equilibration to past perturbations – glacial loading

A possible interpretation of anomalous overpressure is that a previous perturbation was long-lived enough to redistribute groundwater (and other fluids) and recent enough for groundwater not to have adjusted to the present conditions (Bahr et al., 1994). The notion of adjustment time (i.e.,  $t_a$ , see Sect. 4.3.4 and Eq. 8) becomes convenient when assessing whether an ice-  
540 load removed  $> 10^4$  yr ago could be responsible for present anomalous pressures. For shallow, low-permeability and well-consolidated bedrock systems like the one investigated in this work, we found the vertical  $t_a$  to be between 80 and 7500. To calculate this, we used the lowest  $K$ -estimate of the dominant hydrogeological unit (Janusfjellet Subgroup, Table 3) and a characteristic length of 200 (approximating half of the thickness of the aforementioned unit). The specific storage was defined like when calculating the horizontal adjustment time (Sect. 4.3.4). Conclusively, we argue that overpressures in systems like  
545 the investigated case cannot be explained by equilibration ~~from to~~ past glacial loading.

#### 6.1.2 Equilibration to ongoing perturbations – density contrasts and gases

Past geological or climatic events may be indirectly responsible for ongoing pressure perturbations in systems that adjust to active hydrodynamic processes (Neuzil, 1995). Here, we consider the potential pressure contribution derived from groundwater density contrasts and the occurrence and possible production of gases and gas hydrates.



550 For a coastal setting like our field site, it is relevant to consider how a potential disequilibrium of the freshwater-  
saltwater interface could drive groundwater flow. During glaciation, the equilibrium depth of this interface must have been  
considerably deeper than today if subglacial melting could replenish the groundwater system. Following glacial unloading, the  
fresh groundwater body is in disequilibrium with the decreased surficial pressure and the density contrast directs hydraulic  
555 interface, assuming hydrostatic conditions and densities of 1025 and 1000 kg m<sup>-3</sup> respectively (following the Ghyben-Herzberg  
relation, Verruijt, 1968). In other terms, to explain artesian pressures resulting in outflow from springs situated at elevations  
of up to 77 m a.s.l., the seawater-freshwater interface has to be situated at depths down to 3 km b.g.l. unless extensive brine is  
present. The actual seawater-freshwater interface is most certainly located above this depth, and the observed low-pressures at  
~ 800 m b.g.l. (Braathen et al., 2012) definitively exclude density contrasts as a main cause for the overpressures in the  
560 shallower system. We conclude that density contrasts may theoretically contribute to the artesian pressures, but only  
insignificantly.

The presence of gases, either free in solution or bound in gas hydrate complexes (i.e. clathrates), may affect hydraulic  
pressures (Neuzil, 2003). Pingo spring waters and sub-permafrost groundwater in Adventdalen indeed contain both CH<sub>4</sub> and  
CO<sub>2</sub> (Hodson et al., 2020). The methane is dominated by a biogenic fingerprint (Hodson et al., 2019) and contemporary  
565 methanogenesis is probable (Huq et al., 2017). In order to explain pressure build-up, the essential question is whether any  
ongoing process produces or releases gas to the groundwater, thereby increasing pressure. Such processes may be exemplified  
by methanogenesis or clathrate dissolution, which cause the partial gas pressure to exceed the hydrostatic pressure, so that free  
gas forms and replaces groundwater in the pore space. We speculate that, over time, groundwater flow driven by this process  
is limited, as it represents neither a groundwater source nor a net loss in pore space. In Adventdalen, the pressure and  
570 temperature conditions at the base of permafrost are at the threshold for gas hydrate stability, and controlled mainly by the gas  
composition (Betlem et al., 2019). Whether partly responsible for groundwater flow or not, this proximity to the boundary of  
hydrate stability means gas clathrates may currently represent a pressure buffer. This is because should clathrates be present,  
any decrease in pressure to conditions below thermodynamic stability initiates clathrate dissolution, thereby releasing gases  
and increasing the pressure. It is as yet unclear which form the methane predominantly takes below the permafrost in  
575 Adventdalen. However, the near-stability conditions, the documented sub-permafrost gas accumulation, and the recent history  
of climate warming do make the buffering effects of clathrate dissolution more likely.

## 6.2 Model limitations, extent and uncertainties

For sub-permafrost groundwater systems, an extraordinary amount of relevant data and research exists for Adventdalen (van  
der Ploeg et al., 2012) and this arguably makes Adventdalen an optimal case for investigation. There were, nevertheless, too  
580 few observations for calibrating the numerical models in a statistical way, and so in the following, we consider the model  
limitations carefully before drawing conclusions from the simulation results.

### 6.2.1 Limitations related to model approach

Using an approach where transient one-dimensional heat flow modelling was decoupled from steady-state three-dimensional groundwater modelling required an array of assumptions that deserve attention. Modelling heat transfer one-dimensionally in the vertical dimension implies that no lateral conduction was considered. The inherent assumption was thus that the isotherms are horizontally parallel. This assumption holds inland, but for a coastal setting the slope of an isotherm is expected to increase seawards and in some cases cause a thermal “bulge” under the sea floor (c.f. Gregersen and Eidsmoen, 1988; Taniguchi, 2000). The 1DHT model simulations indicated that even the largest isotherm slope gradients in Adventdalen are quite small (Fig. 7a). Between the two most seawards points, the gradients for the  $-2\text{ }^{\circ}\text{C}$  and  $0\text{ }^{\circ}\text{C}$  isotherms are  $-25$  and  $-35\text{ m km}^{-1}$  ( $\Delta z\ \Delta x^{-1}$ ), respectively, in landwards direction. Effectively, if heat transfer in this work had been modelled in 2D, the simulated permafrost aggradation rate would have been slightly slower close to the coast due to lateral heat transfer. Nevertheless, considering how small the isotherm slope gradients are, the lateral heat flow component was considered negligible and we found the one-dimensional modelling approach appropriate.

The inability to model advective heat transfer represents an uncertainty proportional to the importance of this process over the time scale in question. From the hydrogeological properties and the spring water chemistry discussed later on, we realised that the groundwater system must be relatively stagnant. We therefore assumed that the only uncertainty related to the omission of advective heat transfer arose from neglecting the energy leaving the system with the groundwater. By definition, the greatest discrepancy between simulations and actual conditions must occur locally at the outflow points to which the advective heat transfer rate is greatest. On the regional scale, however, we infer that advective heat transfer played an insignificant role. Disregarding shallow formation of visible ground ice, the total pore water expulsion by freezing approximates to 9 % of the volume of ice in the pore space. The average pore water velocity of this water when it got expelled from the system can be approximated by half of the frozen ground depth (assuming this represents the mean travelled distance) divided by the porosity and the time it took for frozen ground to establish. For the investigated system this yields a Peclet number of  $P_{eL} < 0.02$ , implying that advective heat transfer played an insignificant role on the regional scale (taking 100 m as an average frozen ground thickness and characteristic length, and the thermal diffusivity of frozen ground).

The steady-state approach of groundwater modelling implied that dynamic storage effects could not be simulated ( $S_s$ , Eq. 5). To account for the present pressure contributions from previous permafrost dynamics, we instead applied the time-moving average to the development of the permafrost base before calculating the recharge equivalent (Fig. 4). Another drawback from the steady-state approach, which was not accounted for in the model setup, is the possible overestimation of the pressure contribution that arrives from not considering the effects of the Holocene sea level fall. ~~This-Neglecting this effect~~ represents an uncertainty ~~of-in~~ the simulation results, but because sea levels already reached levels close to the present day by 5 ka, we regard it as insignificant.



## 6.2.2 Model extent uncertainty

The boundary conditions of the groundwater model define a bathtub-like system with the pingo springs and the fjord as the only discharge points, and with the expansion of water upon freezing within the model regime as the only source of hydraulic pressure. In reality, the hydrological system in Adventdalen may not entirely conform to this description as groundwater flow across the model boundaries cannot be rejected. Additional recharge could, for example, occur through microcracks below the valley floor induced during glaciation (Leith et al., 2014). Likewise, hydraulic pressures may, to a greater extent than simulated, dissipate directly to the fjord through unknown pathways. In this respect, our model serves to isolate the pressure effect of freezing expansion in Adventdalen and systems like it. ~~This~~ These conditions should be taken into account before drawing site-specific conclusions from the modelling results.

Due to Early Holocene warming (Fig. 3), the 1DHT simulation results showed that continuous frozen ground in Adventdalen is likely younger than 6.5 ka even where the valley floor is older (Fig. 6). This is supported by geomorphological and geochronological evidence (Humlum, 2005). As such, there seems to be no reason why permafrost dynamics in the valley bottom outside the HML should be markedly different from that in the up-valley part of the model area. Based on the above, it is possible that basal permafrost aggradation goes on beyond the model area (HML) and model simulations may have underestimated the freezing-induced pressures affecting spring discharge.

The dominantly low-permeability groundwater system challenged a physically determined lower boundary for the model domain. From the significant low-pressures observed in deeper stratigraphic layers (~ 800 m b.g.l. at DH4, Braathen et al., 2012), we inferred isolation of the investigated groundwater system from that below and simply assigned the base to a depth of 300 m b.g.l. By simulating scenarios with a lower base of 250 and 400 m b.g.l., we found that simulation results did not change significantly (< 1 % deviation of simulated heads and discharge rates).


## 6.3 Do model simulations represent the processes in the groundwater system in Adventdalen?

The amount of hydrogeological data from Adventdalen was insufficient for automatic calibration of model parameters and the model simulations should therefore at best be taken as possible scenarios for the conditions in Adventdalen. However, some scenarios yielded simulations that must be considered at odds with the available observations. For the minimum  $K$  and maximum  $Q_{REQ}$  scenario (Figs. 8-1c), the simulated hydraulic heads were almost certainly too high. The only head observation supports this view and we therefore suggest that the ~~real~~ hydraulic conductivities in reality must be higher if the recharge rate (real and/or equivalent) is as employed here (or higher). Further, discharge from the up-valley pingo springs was not simulated for scenarios with minimum  $Q_{REQ}$  and maximum  $K$  (ScXa and Sc3b, Figs. 8-1a, 8-2a, 8-3a–b). This could indicate that the real  $Q_{REQ}$ -values are in effect higher than those employed for these scenarios. However, since alternative processes contributing to hydraulic pressures were not incorporated in the model, such conclusion is speculative. If permafrost aggradation is the main driver of pingo spring outflow in Adventdalen, the most plausible representation of the system is likely to be found within the scenarios shown in Figs. 8-1b, 8-2b–c and 8-3c).


645 For the flow pattern, a more certain conclusion could be drawn. The flow was simulated to be multidirectional, with local sub-catchments appearing whenever the groundwater model was able to simulate artesian spring discharges from the pingos. This indicates that regional groundwater flow across the model area is very limited.

On Fig. 9, simulated spring outflows from all model simulations are plotted together with the few available observations. Validation of any particular model scenario was not possible due to the variability and paucity of observations. 650 Nevertheless, assuming that only a small fraction of the discharge (if any) freezes within the pingo and becomes part of its core, the comparable observed and simulated discharges suggest that permafrost aggradation alone may explain the presence of the pingos and their springs in low-permeability systems comparable to the one modelled. To investigate the effect of additional pressure sources, we ran the groundwater model with maximum  $K_{\text{z}}$ -values (Table 3) and different, uniformly distributed recharge rates, all resulting in a greater total inflow of groundwater than from permafrost aggradation alone (Fig. 655 8). We used the maximum  $K$ -values to allow for the highest amount of recharge to enter the system. Figure 10 illustrates such a scenario with a recharge rate of  $1 \text{ mm yr}^{-1}$ . We found that, if the pressure production exceeds that equivalent to a recharge rate of  $1 \text{ mm yr}^{-1}$ , hydraulic heads rise unrealistically (i.e.,  $> 200 \text{ m a.g.l.}$ ). Within the model limitations (Sect. 6.2), Fig. 10 may thus be regarded as an approximation of the upper limit of possible total inflow (or pore space loss) rates ( $161.4 \text{ m}^3 \text{ day}^{-1}$ ). The corresponding spring water discharge rates range from  $0.12 \text{ to } 0.56 \text{ L s}^{-1}$  (Fig. 9) and the mean residence time is 24 kyr.

660



**Figure 9** Simulated, observed (measured) and estimated (“by the eye”) spring discharge rates. Blue dots are discharge rates simulated for groundwater model scenarios where the source term is defined by the rate of basal permafrost aggradation (Figs. 7 and 8). The orange dots are discharge rates simulated for a groundwater model scenario with an additional unknown pressure source (Fig. 10).



665

**Figure 10** Groundwater model simulation representing additional pressure sources. Recharge is distributed uniformly with a rate of 1 mm yr<sup>-1</sup>. The figure is using the same structure and legend as Figure 8.

#### 6.4 Comparison with hydrological processes inferred from pingo spring water chemistry

The lack of hydrological data for model calibration make comparison with other information on the groundwater system ever so important. In this context, hydrochemical data from 25 pingo spring water samples from 2014 to 2017 (Hodson et al., 2020): see DOI:10.5285/3d82fd3f-884b-47b6-b11c-6c96d66b950d) give additional insights into the groundwater system. Accordingly, water samples from LP, FHP, IHP and RP reveal that all these pingo springs share the same sodium-bicarbonate (NaHCO<sub>3</sub>) water type (illustrated in the Supplement), which is commonly associated with freshening of a saline groundwater system (e.g., Giménez-Forcada, 2010). The only exceptions are four samples taken near River Pingo in 2017 of a magnesium-sulfate water type. These four samples were excluded from the following discussion because they might not be associated with a pingo according to Hodson et al. (in review 2020).

Among the 21 NaHCO<sub>3</sub>-dominated samples a few distinct trends were observed in the hydrochemistry. Specifically, the concentration of Cl<sup>-</sup> and heavy stable water isotopes both increase in the up-valley direction. To illustrate this, the concentration of Cl<sup>-</sup> is plotted against δ<sup>18</sup>O<sub>H<sub>2</sub>O</sub> in Fig. 11. The former has a relatively constant concentration at each site compared to the latter. We inferred that the variation of the Cl<sup>-</sup> concentrations between the different springs reflects an up-valley variation in the sub-permafrost groundwater system, and not processes acting locally along the flow paths towards the individual pingos. If the latter had been the case, we would expect to see greater intra-site variation.


680

In order to explain the increasing  $\text{Cl}^-$  concentration and  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$  we considered solute rejection and isotope fractionation associated with freezing as well as mixing between seawater and freshwater. For the former, we found that the positive relationship between the two parameters was incongruent with this being a major control in the investigated system: when ice forms, water molecules containing the heavier isotope  $^{18}\text{O}$  (and D) are preferentially included in the ice, while the residual water becomes isotopically lighter. For freezing in a well-mixed and closed reservoir, the isotopic ratio in the residual water,  $\delta_w$ , may be expressed by a Rayleigh-type fractionation according to the following equation (Lacelle, 2011):

$$\delta_w = \delta_0 + \ln(\alpha_{i-w}) \cdot 1000 \cdot \ln(f) \quad (8)$$

where  $\delta_0$  is the initial isotopic ratio in the water,  $\alpha_{i-w}$  is the fractionation coefficient between ice and water, and  $f$  is the fraction of residual water.  $\alpha_{i-w} = 1.003$  (Lehmann and Siegenthaler, 1991) at equilibrium and approaches 1 for faster freezing rates (non-equilibrium). The decrease of  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$  in the residual water resulting from freezing is exemplified in Fig. 11 by taking a typical LP water sample (i.e., with the lowest salinity) and assuming that  $\text{Cl}^-$  is completely excluded from the ice. The shading indicates the possible range of  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$  that can be derived from this process. Although two samples from FHP fall within the shaded area, it was hard to explain the composition of these with freezing from a LP-type water, as the remaining samples did not comply with this interpretation (Fig. 11).


Another model line on Fig. 11 is drawn by assuming that the LP samples result from mixing of seawater and a freshwater end-member with zero  $\text{Cl}^-$  concentration. Generally, the remaining samples agree with this model line and hence we argue that mixing is the more feasible explanation. This was also in line with the interpretation that the  $\text{NaHCO}_3$ -dominated hydrochemistry reflects freshening.



**Figure 11**  $\text{Cl}^-$  concentration and  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$  of pingo spring water samples. The thick black model line is drawn by assuming that the LP samples result from mixing of seawater and a freshwater endmember with a zero  $\text{Cl}^-$  concentration. The range of possible  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$ -values following freeze-out (Eq. 8) from water with an initial composition alike LP is illustrated with the shaded area. Here,  $\text{Cl}^-$  is assumed to be

completely excluded from the ice. The lower and upper edges of the shading represent equilibrium fractionation and no fractionation, respectively, while the intermediate model lines illustrate fractionation at 20 %, 40 %, 60 % and 80 % (top–down) of equilibrium conditions.

710 For the above mixing scenario, field surveys suggested a somewhat unusual trend with greater fractions of freshwater towards the sea, where  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$  and  $\text{Cl}^-$  concentrations approach those of the inferred freshwater end-member in Fig. 11. In the case of present-day recharge from the adjacent mountains (as demonstrated at a pingo 35 km South West of Adventdalen by Demidov et al., 2019), we would not expect to observe such a systematic trend along the valley axis, as this would be unlikely in a system dependent upon localised areas for infiltration. We therefore suggest that the unexpected landwards increase in  $\text{Cl}^-$  is difficult to explain without the sequence of events illustrated in Fig. 12. During glaciation, the groundwater system was  
715 recharged by subglacial melting (Fig. 12a). Despite being covered by the sea during the Early Holocene, seawater could not infiltrate substantially into the groundwater system to replace the fresh groundwater (Fig. 12b). On Fig. 12c, the body of freshwater forms a wedge that thins inland below the freezing front due to the density difference with seawater. Moving away from the sea, the springs expel more saline groundwater because the wedge thins in this direction and the permafrost thickness increases (Fig. 12c). Therefore both the sources of water and the hydraulic conditions of the groundwater system seem  
720 intricately linked to landscape evolution throughout the Holocene.



**Figure 12** Possible interpretation of hydrochemical trends observed in pingo spring waters. **(a)** Subglacial melting from the Weichselian ice sheet recharged the groundwater system with freshwater. **(b)** Although covered by the sea during Early Holocene, low-permeability rocks limited infiltration of sea water and the fresh groundwater body persisted. **(c)** Due to the shallower permafrost depth towards the sea, spring water sampled in this direction holds a lower concentration of sea water (salt).

725

## 7 Conclusions

730

Results from the decoupled heat and groundwater model show that millennial-scale basal permafrost aggradation may alone produce hydraulic pressures sufficient for the formation of pingos and their spring water outflows when the right conditions are met. In addition to the climate cooling necessary for permafrost aggradation, a relatively low-permeability groundwater system with limited dissipation of hydraulic pressures are also required for pingo formation. Pingos formed in this way do not conform to the traditional differentiation between open-system and closed-system types, but constitute a borderline case: by definition, they classify as open-system pingos, because the groundwater body from which spring water is expelled is not enclosed in permafrost. Generically though, they relate more to closed-system pingos, because the causal mechanism of hydraulic pressures is essentially similar, although operating over much longer time-scales. We emphasise that this conceptual

735

model for pingo formation represents an end-member of open-system pingo-forming processes, which is not exclusive, but may act in combination with others, such as those reported nearby by Demidov et al. (2019).

740 The simulation results from the 1DHT model suggested that basal permafrost aggradation in Adventdalen presently induces head gradients corresponding to the effect of a recharge rate of  $\sim 0.1 \text{ mm yr}^{-1}$  furthest up-valley, and increasing to  $\sim 1 \text{ mm yr}^{-1}$  towards the sea. By applying these rates to the groundwater model, we simulated spring outflow rates of the order of  $10^{-1} \text{ L s}^{-1}$ . Due to the probable occurrence of basal permafrost aggradation outside the model area, these may be underestimations. Nevertheless, the simulated and observed spring outflow rates at Adventdalen pingos were of the same order of magnitude, suggesting that they likely form at least partly in accordance with our conceptual model. This further suggests that overpressures induced by water expansion during freezing in other sub-permafrost groundwater systems can result from  
745 permafrost aggradation.

The simulated aquifer flow paths and flow velocity distributions suggested that sub-permafrost groundwater flow in Adventdalen is characterised by slow mean pore water velocities ( $<0.25 \text{ m yr}^{-1}$ ) and long residence times ( $> 2.5 \cdot 10^4 \text{ yr}$ ) that exceed the duration of the Holocene. The groundwater system most likely has a multidirectional flow pattern with individual catchments around each pingo.

750 The presence of a positive relationship between  $\text{Cl}^-$  and  $\delta^{18}\text{O}_{\text{H}_2\text{O}}$  in the pingo spring water samples suggests that mixing between seawater and freshwater is the major control of hydrogeochemistry in the sub-permafrost groundwater system prior to aggradation. As a result, a somewhat unexpected but clear trend of increasing salinity in an up-valley direction was found. Therefore, given the relatively stagnant groundwater system, Weichselian subglacial meltwater could endure the Early Holocene inundation and result in the present-day situation where a freshwater body forms a wedge that thins in the inland  
755 direction below the permafrost. This possible interpretation readily explains the inland increase of the spring salinity because the inland springs expel groundwater from greater and hence more saline depths.

Alternative and non-recharge-related processes that may also affect sub-permafrost pressures were considered. The role of gases may be particularly important in this context because it is likely that methane hydrates have influenced the groundwater system under investigation. However, methane hydrate dissolution may in fact act as a pressure buffer and prolong  
760 artesian pressures after permafrost ceases aggrading (or starts thawing). This represents an uncertainty in forecasting how groundwater and methane fluxes will react to climate change. Unresolved questions regarding the occurrence and formation of gases in sub-permafrost groundwater systems therefore constitute an ongoing challenge for Arctic science.

## 8 Code availability

The 1DHT model code is publicly available at DOI:10.5281/zenodo.3578839.

765 **Author contributions**

MTH developed the 1DHT model code and designed the modelling experiments with contributions from VB. AJH, SJ and MTH analysed the hydrochemical data. MTH prepared the manuscript with contributions from all the co-authors.

**Competing financial interest**

The authors declare no competing financial interests.

770 **Acknowledgements**

This paper largely emanated from work initiated with MTH's MSc thesis (Hornum, 2018) and the authors acknowledge Prof. Peter Engesgaard for supervising the thesis work. The authors also acknowledge The Research Council of Norway grant 294764. [The authors are thankful to Melissa Bunn and an anonymous reviewer whose constructive reviews were very helpful for improving this manuscript.](#)

775 **References**

- Åhman, R.: Studier av pingoer i Adventdalen och Reindalen på Spetsbergen, Lunds Univ. Naturgeografiska Institution. Rapp. och Not., 15, 27–44, 1973.
- Andersen, D. T., Pollard, W. H., McKay, C. P. and Heldmann, J.: Cold springs in permafrost on Earth and Mars, *J. Geophys. Res. E Planets*, 107(3), doi:10.1029/2000je001436, 2002.
- 780 AQUAVEO™: Groundwater Modeling System 10.4.4, [online] Available from: <https://www.aquaveo.com/software/gms-groundwater-modeling-system-introduction>, 2019.
- Bælum, K., Johansen, T. A., Johnsen, H., Rød, K., Ruud, B. O. and Braathen, A.: Subsurface structures of the longyearbyen CO<sub>2</sub> lab study area in central spitsbergen (arctic Norway), as mapped by reflection seismic data, *Nor. Geol. Tidsskr.*, 92(4), 377–389, 2012.
- 785 Bahr, J. M., Moline, G. R. and Nadon, G. C.: Anomalous Pressures in the Deep Michigan Basin, in *AAPG Memoir 61: Basin Compartments and Seals*, pp. 153–165., 1994.
- Ballantyne, C. K.: *Periglacial geomorphology*, 1st ed., Wiley-Blackwell., 2018.
- Benn, D. I. and Evans, D. J. A.: *Glaciers & Glaciation*, 2nd ed., Hodder Education., 2010.
- Bense, V. F., Kooi, H., Ferguson, G. and Read, T.: Permafrost degradation as a control on hydrogeological regime shifts in a  
790 warming climate, *J. Geophys. Res. Earth Surf.*, 117(3), 1–18, doi:10.1029/2011JF002143, 2012.



- Bergman, T. L., Lavine, A. S., Incropera, F. P. and Dewitt, D. P.: *Fundamentals of Heat and Mass Transfer*, 7th ed., John Wiley & Sons., 2011.
- Betlem, P., Senger, K. and Hodson, A.: 3D thermobaric modelling of the gas hydrate stability zone onshore central Spitsbergen, Arctic Norway, *Mar. Pet. Geol.*, 100(August 2018), 246–262, doi:10.1016/j.marpetgeo.2018.10.050, 2019.
- 795 van der Bilt, W. G. M., D’Andrea, W. J., Bakke, J., Balascio, N. L., Werner, J. P., Gjerde, M. and Bradley, R. S.: Alkenone-based reconstructions reveal four-phase Holocene temperature evolution for High Arctic Svalbard, *Quat. Sci. Rev.*, 183, 204–213, doi:10.1016/j.quascirev.2016.10.006, 2018.
- Birchall, T., Senger, K., Hornum, M. T., Olaussen, S. and Braathen, A.: Underpressure of the Northern Barents Shelf: distribution, causes and implications on the petroleum, Pre-proof, *Am. Assoc. Pet. Geol. Bull.*, doi:10.1306/02272019146, 800 2020.
- Bonacina, C. and Comini, G.: On the solution of the nonlinear heat conduction equations by numerical methods, *Int. J. Heat Mass Transf.*, 16(3), 581–589, doi:10.1016/0017-9310(73)90225-1, 1973.
- Braathen, A., Bælum, K., Christiansen, H. H., Dahl, T., Eiken, O., Elvebakk, H., Hansen, F., Hanssen, T. H., Jochmann, M., Johansen, T. A., Johnsen, H., Larsen, L., Lie, T., Mertes, J., Mørk, A., Mørk, M. B., Nemec, W., Olaussen, S., Oye, V., Rød, 805 K., Titlestad, G. O., Tveranger, J. and Vagle, K.: The Longyearbyen CO<sub>2</sub> Lab of Svalbard, Norway - Initial Assessment of the Geological Conditions for CO<sub>2</sub> Sequestration, *Nor. Geol. Tidsskr.*, 92(4), 353–376, 2012.
- Burland, J. B.: *On the compressibility and shear strength of natural clays.*, 1990.
- Burr, D. M., Tanaka, K. L. and Yoshikawa, K.: Pingos on Earth and Mars, *Planet. Space Sci.*, 57(5–6), 541–555, doi:10.1016/j.pss.2008.11.003, 2009.
- 810 Burt, T. P. and Williams, P. J.: Hydraulic conductivity in frozen soils, *Earth Surf. Process.*, 1(4), 349–360, doi:10.1002/esp.3290010404, 1976.
- Cable, S., Elberling, B. and Kroon, A.: Holocene permafrost history and cryostratigraphy in the High-Arctic Adventdalen Valley, central Svalbard, *Boreas*, 47(2), 423–442, doi:10.1111/bor.12286, 2018.
- Carslaw, H. S. and Jaeger, J. C.: *Conduction of heat in solids*, 2nd ed., Clarendon Press., 1959.
- 815 Christiansen, H. H., French, H. M. and Humlum, O.: Permafrost in the Gruve-7 mine, Adventdalen, Svalbard, *Nor. Geogr. Tidsskr.*, 59(2), 109–115, doi:10.1080/00291950510020592, 2005.
- Demidov, N., Wetterich, S., Verkulich, S., Ekaykin, A., Meyer, H., Anisimov, M., Schirrmeister, L., Demidov, V. and Hodson, A. J.: Geochemical signatures of pingo ice and its origin in Grøndalen, west Spitsbergen, *Cryosph.*, 13(11), 3155–3169, doi:10.5194/tc-13-3155-2019, 2019.

- 820 Domenico, P. A. and Mifflin, M. D.: Water from low-permeability sediments and land subsidence, *Water Resour. Res.*, 1(4), 563–576, doi:10.1029/WR001i004p00563, 1965.
- Domenico, P. A. and Schwartz, F. W.: *Physical and chemical hydrogeology*, Wiley & Sons., 1998.
- Dyke, A. S., England, J., Reimnitz, E. and Jette, H.: Changes in driftwood delivery to the Canadian Arctic Archipelago, *Arctic*, 50(1), 1–16, 1997.
- 825 Elverhøi, A., Svendsen, J. I., Solheim, A., Andersen, E. S., Milliman, J., Mangerud, J. and Hooke, R. L.: Late Quaternary Sediment Yield from the High Arctic Svalbard Area, *J. Geol.*, 103(1), 1–17, doi:10.1086/629718, 1995.
- Eppelbaum, L., Kutasov, I. and Pilchin, A.: *Applied Geothermics*, *Lect. Notes Earth Syst. Sci.*, 757, doi:10.1007/978-3-642-34023-9, 2014.
- Farnsworth, W. R., Ingólfsson, Ó., Alexanderson, H., Allaart, L., Forwick, M., Noormets, R., Retelle, M. and Schomacker, A.: Holocene glacial history of Svalbard: Status, perspectives and challenges, *Earth-Science Rev.*, 208, doi:10.1016/j.earscirev.2020.103249, 2020.
- 830 Fitts, C. R.: *Groundwater Science*, 1st ed., Academic Press., 2002.
- Førland, E. J., Hanssen-Bauer, I. and Nordli, Ø.: Climate statistics and longterm series of temperature and precipitation at Svalbard and Jan Mayen, Norwegian Meteorological Institute, DNMI Nor. Meteorol. Inst. Rep., 21, 1997.
- 835 Forman, S. L.: Post-glacial relative sea-level history of northwestern Spitsbergen, Svalbard, *Geol. Soc. Am. Bull.*, 102(11), 1580–1590, doi:10.1130/0016-7606(1990)102<1580:PGRSLH>2.3.CO;2, 1990.
- Forwick, M. and Vorren, T. O.: Stratigraphy and deglaciation of the Isfjorden area, Spitsbergen, *Nor. Geol. Tidsskr.*, 90(4), 163–179, 2011.
- French, H. M.: *The Periglacial Environment*, 4th ed., John Wiley & Sons Ltd., 2017.
- 840 Funder, S., Goosse, H., Jepsen, H., Kaas, E., Kjær, K. H., Korsgaard, N. J., Larsen, N. K., Linderson, H., Lyså, A., Möller, P., Olsen, J. and Willerslev, E.: A 10,000-year record of Arctic Ocean Sea-ice variability - View from the beach, *Science* (80-. ), 333(6043), 747–750, doi:10.1126/science.1202760, 2011.
- Gilbert, G. L., O’Neill, H. B., Nemeč, W., Thiel, C., Christiansen, H. H. and Buylaert, J. P.: Late Quaternary sedimentation and permafrost development in a Svalbard fjord-valley, Norwegian high Arctic, *Sedimentology*, 65(7), 2531–2558, doi:10.1111/sed.12476, 2018.
- 845 Giménez-Forcada, E.: Dynamic of sea water interface using hydrochemical facies evolution diagram, *Ground Water*, 48(2), 212–216, doi:10.1111/j.1745-6584.2009.00649.x, 2010.
- Govaerts, J., Beerten, K. and Ten Veen, J.: Weichselian permafrost depth in the Netherlands: A comprehensive uncertainty

and sensitivity analysis, *Cryosphere*, 10(6), 2907–2922, doi:10.5194/tc-10-2907-2016, 2016.

850 Grasby, S. E., Beauchamp, B. and Bense, V.: Sulfuric acid speleogenesis associated with a glacially driven groundwater system-paleo-spring “pipes” at Borup Fiord Pass, Nunavut, *Astrobiology*, 12(1), 19–28, doi:10.1089/ast.2011.0700, 2012.

Grasby, S. E., Proemse, B. C. and Beauchamp, B.: Deep groundwater circulation through the High Arctic cryosphere forms Mars-like gullies, *Geology*, 42(8), 651–654, doi:10.1130/G35599.1, 2014.

855 Gregersen, O. and Eidsmoen, T.: Permafrost conditions in the shore area at Svalbard, in *Permafrost, proceedings of the Fifth International Conference on Permafrost, August 2-5, 1988, Trondheim, Norway*, vol. 2, edited by K. Senneset, pp. 933–936, Tapir Publishers., 1988.

860 Grenier, C., Anbergen, H., Bense, V., Chanzy, Q., Coon, E., Collier, N., Costard, F., Ferry, M., Frampton, A., Frederick, J., Gonçalves, J., Holmén, J., Jost, A., Kokh, S., Kurylyk, B., McKenzie, J., Molson, J., Mouche, E., Orgogozo, L., Pannetier, R., Rivière, A., Roux, N., Rühaak, W., Scheidegger, J., Selroos, J. O., Therrien, R., Vidstrand, P. and Voss, C.: Groundwater flow and heat transport for systems undergoing freeze-thaw: Intercomparison of numerical simulators for 2D test cases, *Adv. Water Resour.*, 114(February), 196–218, doi:10.1016/j.advwatres.2018.02.001, 2018.

Grosse, G., Goetz, S., McGuire, A. D., Romanovsky, V. E. and Schuur, E. A. G.: Changing permafrost in a warming world and feedbacks to the Earth system, *Environ. Res. Lett.*, 11, 040201, doi:10.1088/1748-9326/11/4/040201, 2016.

865 Grundvåg, S.-A., Jelby, M. E., Sliwinska, K. K., Nøhr-Hansen, H., Aadland, T., Sandvik, S. E., Tennvassås, I., Engen, T. and Olaussen, S.: Sedimentology and palynology of the Lower Cretaceous succession of central Spitsbergen: integration of subsurface and outcrop data, *Nor. J. Geol.*, 99(2), doi:10.17850/njg006, 2019.

Hald, M., Andersson, C., Ebbesen, H., Jansen, E., Klitgaard-Kristensen, D., Risebrobakken, B., Salomonsen, G. R., Sarnthein, M., Sejrup, H. P. and Telford, R. J.: Variations in temperature and extent of Atlantic Water in the northern North Atlantic during the Holocene, *Quat. Sci. Rev.*, 26, 3423–3440, doi:10.1016/j.quascirev.2007.10.005, 2007.

870 Haldorsen, S., Heim, M. and Lauritzen, S. E.: Subpermafrost Groundwater, Western Svalbard, *Nord. Hydrol.*, 27(1–2), 57–68, doi:10.2166/nh.1996.0019, 1996.

Haldorsen, S., Heim, M., Dale, B., Landvik, J. Y., van der Ploeg, M., Leijnse, A., Salvigsen, O., Hagen, J. O. and Banks, D.: Sensitivity to long-term climate change of subpermafrost groundwater systems in Svalbard, *Quat. Res.*, 73(2), 393–402, doi:10.1016/j.yqres.2009.11.002, 2010.

875 Hanssen-Bauer, I., Førland, E. J., Hisdal, H., Mayer, S., Sandø, A. B., Sorteberg, A., Adakudlu, M., Andresen, J., Bakke, J., Beldring, S., Benestad, R., Bilt, W., Bogen, J., Borstad, C., Breili, K., Breivik, Ø., Børsheim, K. Y., Christiansen, H. H., Dobler, A., Engeset, R., Frauenfelder, R., Gerland, S., Gjeltén, H. M., Gundersen, J., Isaksen, K., Jaedicke, C., Kierulf, H., Kohler, J., Li, H., Lutz, J., Melvold, K., Mezghani, A., Nilsen, F., Nilsen, I. B., Nilsen, J. E. Ø., Pavlova, O., Ravndal, O.,

- Risebrobakken, B., Saloranta, T., Sandven, S., Schuler, T. V., Simpson, M. J. R., Skogen, M., Smedsrud, L. H., Sund, M.,  
880 Vikhamar-Schuler, D., Westermann, S. and Wong, W. K.: Climate in Svalbard 2100. [online] Available from:  
<http://www.miljodirektoratet.no/M1242> (Accessed 12 September 2019), 2018.
- Harada, K. and Yoshikawa, K.: Permafrost age and thickness near Adventfjorden, Spitsbergen, *Polar Geogr.*, 20(4), 267–281,  
doi:10.1080/10889379609377607, 1996.
- Hodson, A., Nowak, A., Redeker, K. R., Holmlund, E. S., Christiansen, H. H. and Turchyn, A. V.: Seasonal dynamics of  
885 methane and carbon dioxide evasion from an open system pingo: Lagoon pingo, svalbard, *Front. Earth Sci.*, 7, 30,  
doi:10.3389/feart.2019.00030, 2019.
- Hodson, A., Nowak, A., Hornum, M. T., Senger, K., Redeker, K. R., Christiansen, H. H., Jessen, S., Betlem, P., Thornton, S.,  
Turchyn, A. V., Olaussen, S. and Marca, A.: Sub-permafrost methane seepage from open system pingos in Svalbard, Pre-  
proof, *Cryosph.*, doi:10.5194/tc-2020-11, 2020.
- 890 Hornum, M. T.: Postglacial Rebound, Permafrost Growth, and its Impact on Groundwater Flow and Pingo Formation,  
University of Copenhagen. [online] Available from: [https://www.researchgate.net/profile/Mikkel\\_Hornum2](https://www.researchgate.net/profile/Mikkel_Hornum2), 2018.
- Humlum, O.: Holocene permafrost aggradation in Svalbard, *Geol. Soc. Spec. Publ.*, 242, 119–130,  
doi:10.1144/GSL.SP.2005.242.01.11, 2005.
- Humlum, O., Instanes, A. and Sollid, J. L.: Permafrost in Svalbard: A review of research history, climatic background and  
895 engineering challenges, *Polar Res.*, 22(2), 191–215, doi:10.3402/polar.v22i2.6455, 2003.
- Huq, F., Smalley, P. C., Mørkved, P. T., Johansen, I., Yarushina, V. and Johansen, H.: The Longyearbyen CO<sub>2</sub> Lab: Fluid  
communication in reservoir and caprock, *Int. J. Greenh. Gas Control*, doi:10.1016/j.ijggc.2017.05.005, 2017.
- Ingólfsson, Ó. and Landvik, J. Y.: The Svalbard-Barents Sea ice-sheet-Historical, current and future perspectives, *Quat. Sci.  
Rev.*, 64, 33–60, doi:10.1016/j.quascirev.2012.11.034, 2013.
- 900 Koevoets, M. J., Hammer, Ø., Olaussen, S., Senger, K. and Smelror, M.: Integrating subsurface and outcrop data of the Middle  
Jurassic to Lower Cretaceous Agardhfjellet Formation in central Spitsbergen, *Nor. J. Geol.*, 98(4), doi:10.17850/njg98-4-01,  
2018.
- Kottek, M., Grieser, J., Beck, C., Rudolf, B. and Rubel, F.: World Map of the Köppen-Geiger climate classification updated, ,  
15(3), 259–263, doi:10.1127/0941-2948/2006/0130, 2006.
- 905 Lacelle, D.: On the  $\delta^{18}\text{O}$ ,  $\delta\text{D}$  and D-excess relations in meteoric precipitation and during equilibrium freezing: Theoretical  
approach and field examples, *Permafr. Periglac. Process.*, 22(1), 13–25, doi:10.1002/ppp.712, 2011.
- Lehmann, M. and Siegenthaler, U.: Equilibrium oxygen- and hydrogen-isotope fractionation between ice and water, *J. Glaciol.*,  
37(125), 23–26, doi:10.3189/s0022143000042751, 1991.

- Leith, K., Moore, J. R., Amann, F. and Loew, S.: Subglacial extensional fracture development and implications for Alpine  
910 Valley evolution, *J. Geophys. Res. Earth Surf.*, 119(1), 62–81, doi:10.1002/2012JF002691, 2014.
- Liestøl, O.: Pingos, springs, and permafrost in Spitsbergen, Nor. Polarinstitut Årb. 1975, 7–29, 1977.
- Liestøl, O.: Open-system pingos in Spitsbergen, Nor. *Geogr. Tidsskr.*, doi:10.1080/00291959608552355, 1996.
- Lønne, I. and Nemeč, W.: High-arctic fan delta recording deglaciation and environment disequilibrium, *Sedimentology*, 51(3),  
553–589, doi:10.1111/j.1365-3091.2004.00636.x, 2004.
- 915 Mackay, J. R.: Pingo growth and collapse, Tuktoyaktuk Peninsula area, western arctic coast, Canada: A long-term field study,  
*Geogr. Phys. Quat.*, 52(3), 271–323, doi:10.7202/004847ar, 1998.
- Manger, G. E.: Porosity and Bulk Density of Sedimentary Rocks, *Geol. Surv. Bull.*, 1144-E, doi:10.1111/nan.12452, 1963.
- Mangerud, J. and Svendsen, J. I.: The Holocene Thermal Maximum around Svalbard, Arctic North Atlantic; molluscs show  
early and exceptional warmth, *The Holocene*, 28(1), 65–83, doi:10.1177/0959683617715701, 2017.
- 920 Marshall, C., Ugunu, J., Large, D. J., Meredith, W., Jochmann, M., Friis, B., Vane, C., Spiro, B. F., Snape, C. E. and Orheim,  
A.: Geochemistry and petrology of palaeocene coals from Spitzbergen - Part 2: Maturity variations and implications for local  
and regional burial models, *Int. J. Coal Geol.*, 143, 1–10, doi:10.1016/j.coal.2015.03.013, 2015.
- MathWorks®: MATLAB R2019b, [online] Available from: <https://se.mathworks.com/products/matlab.html>, 2019.
- Mau, S., Römer, M., Torres, M. E., Bussmann, I., Pape, T., Damm, E., Geprägs, P., Wintersteller, P., Hsu, C. W., Loher, M.  
925 and Bohrmann, G.: Widespread methane seepage along the continental margin off Svalbard-from Bjørnøya to Kongsfjorden,  
*Sci. Rep.*, 7, doi:10.1038/srep42997, 2017.
- McCauley, C. A., White, D. M., Lilly, M. R. and Nyman, D. M.: A comparison of hydraulic conductivities, permeabilities and  
infiltration rates in frozen and unfrozen soils, *Cold Reg. Sci. Technol.*, 34(2), 117–125, doi:10.1016/S0165-232X(01)00064-  
7, 2002.
- 930 McDonald, M. G. and Harbaugh, A. W.: A modular three-dimensional finite-difference ground-water flow model - Techniques  
of Water-Resources Investigations 06-A1., 1988.
- Mottaghy, D. and Rath, V.: Latent heat effects in subsurface heat transport modelling and their impact on palaeotemperature  
reconstructions, *Geophys. J. Int.*, 164(1), 236–245, doi:10.1111/j.1365-246X.2005.02843.x, 2006.
- Myhre, C. L., Ferré, B., Platt, S. M., Silyakova, A., Hermansen, O., Allen, G., Pisso, I., Schmidbauer, N., Stohl, A., Pitt, J.,  
935 Jansson, P., Greinert, J., Percival, C., Fjaeraa, A. M., O’Shea, S. J., Gallagher, M., Le Breton, M., Bower, K. N., Bauguitte, S.  
J. B., Dalsøren, S., Vadakkepuliambatta, S., Fisher, R. E., Nisbet, E. G., Lowry, D., Myhre, G., Pyle, J. A., Cain, M. and  
Mienert, J.: Extensive release of methane from Arctic seabed west of Svalbard during summer 2014 does not influence the

- atmosphere, *Geophys. Res. Lett.*, 43(9), 4624–4631, doi:10.1002/2016GL068999, 2016.
- Neuzil, C. E.: Abnormal pressures as hydrodynamic phenomena, *Am. J. Sci.*, 295(6), 742–786, doi:10.2475/ajs.295.6.742,  
940 1995.
- Neuzil, C. E.: Hydromechanical coupling in geologic processes, *Hydrogeol. J.*, 11(1), 41–83, doi:10.1007/s10040-002-0230-8, 2003.
- Neuzil, C. E.: Hydromechanical effects of continental glaciation on groundwater systems, *Geofluids*, 12(1), 22–37, doi:10.1111/j.1468-8123.2011.00347.x, 2012.
- 945 Nordli, Ø., Przybylak, R., Ogilvie, A. E. J. and Isaksen, K.: Long-term temperature trends and variability on spitsbergen: The extended svalbard airport temperature series, 1898-2012, *Polar Res.*, 33(1), 21349, doi:10.3402/polar.v33.21349, 2014.
- Norwegian Polar Institute: Map data, [online] Available from: <https://geodata.npolar.no/> (Accessed 13 May 2020), 2019.
- Ohm, S. E., Larsen, L., Olaussen, S., Senger, K., Birchall, T., Demchuk, T., Hodson, A., Johansen, I., Titlestad, G. O., Karlsen, D. A. and Braathen, A.: Discovery of shale gas in organic-rich Jurassic successions, Adventdalen, Central Spitsbergen,  
950 Norway, *Nor. J. Geol.*, 99(2), 1–28, doi:10.17850/njg007, 2019.
- Okiongbo, K. S.: Effective Stress-Porosity Relationship above and Within the Oil Window in the North Sea Basin, *Res. J. Appl. Sci. Eng. Technol.*, 3(1), 32–38, 2011.
- Olaussen, S., Senger, K., Braathen, A., Grundvåg, S.-A. and Mørk, A.: You learn as long as you drill; research synthesis from the Longyearbyen CO2 Laboratory, Svalbard, Norway, *Nor. J. Geol.*, 99(2), 157–187, doi:10.17850/njg008, 2020.
- 955 Orvin, A. K.: Litt om kilder på Svalbard, *Nor. Geol. Tidsskr. Norges Svalbard- og Ishavsundersøgelser*, 10(57), 15–38, 1944.
- van der Ploeg, M. J., Haldorsen, S., Leijnse, A. and Heim, M.: Subpermafrost groundwater systems: Dealing with virtual reality while having virtually no data, *J. Hydrol.*, 475, 42–52, doi:10.1016/j.jhydrol.2012.08.046, 2012.
- Pollock, D. W.: User Guide for MODPATH Version 7-A Particle-Tracking Model for MODFLOW, U.S. Geol. Surv. Open File Rep., 1086, 41, doi:10.3133/ofr20161086, 2016.
- 960 Riseborough, D., Shiklomanov, N., Etzelmüller, B., Gruber, S. and Marchenko, S.: Recent advances in permafrost modelling, *Permafr. Periglac. Process.*, 19(2), 137–156, doi:10.1002/ppp.615, 2008.
- Robertson, E. C.: Thermal properties of rocks. Report 88-441, US Dep. Inter. Geol. Surv., 106, 1988.
- Scheidegger, J. M. and Bense, V. F.: Impacts of glacially recharged groundwater flow systems on talik evolution, *J. Geophys. Res. Earth Surf.*, 119(4), 758–778, doi:10.1002/2013JF002894, 2014.
- 965 Scheidegger, J. M., Bense, V. F. and Grasby, S. E.: Transient nature of Arctic spring systems driven by subglacial meltwater, *Geophys. Res. Lett.*, 39(12), 1–6, doi:10.1029/2012GL051445, 2012.

- Schlumberger©: Petrel E&P, [online] Available from: <https://www.software.slb.com/products/petrel>, 2019.
- Schuster, P. F., Schaefer, K. M., Aiken, G. R., Antweiler, R. C., Dewild, J. F., Gryzniec, J. D., Gusmeroli, A., Hugelius, G., Jafarov, E., Krabbenhoft, D. P., Liu, L., Herman-Mercer, N., Mu, C., Roth, D. A., Schaefer, T., Striegl, R. G., Wickland, K.  
970 P. and Zhang, T.: Permafrost Stores a Globally Significant Amount of Mercury, *Geophys. Res. Lett.*, 45(3), 1463–1471, doi:10.1002/2017GL075571, 2018.
- Singhal, B. B. S. and Gupta, R. P.: *Applied Hydrogeology of Fractured Rocks*, 2nd ed., Springer Netherlands., 2010.
- Skempton, A. W.: The consolidation of clays by gravitational compaction, *Q. J. Geol. Soc. London*, 125(1–4), 373–408, doi:10.1144/gsjgs.125.1.0373, 1969.
- 975 Šuklje, L.: *Rheologic Aspects of Soil Mechanics*, 1st ed., Wiley-Interscience., 1969.
- Svensson, H.: Pingo i yttre delen av Adventdalen, *Nor. Polarinstitut Årb.* 1969, 168–174, 1970.
- Taniguchi, M.: Evaluations of the saltwater-groundwater interface from borehole temperature in a coastal region, *Geophys. Res. Lett.*, 27(5), 713–716, doi:10.1029/1999GL002366, 2000.
- Verruijt, A.: A note on the ghyben-herzberg formula, *Int. Assoc. Sci. Hydrol. Bull.*, 13, 43–46,  
980 doi:10.1080/02626666809493624, 1968.
- Walvoord, M. A. and Kurylyk, B. L.: Hydrologic impacts of thawing permafrost—a review, *Vadose Zo. J.*, 15(6), doi:10.2136/vzj2016.01.0010, 2016.
- Wangen, M., Souche, A. and Johansen, H.: A model for underpressure development in a glacial valley, an example from Adventdalen, Svalbard, *Basin Res.*, 28(6), 752–769, doi:10.1111/bre.12130, 2016.
- 985 Williams, J. R.: *Ground Water in the Permafrost Regions of Alaska*, US Geol. Surv. Prof. Pap., 1970.
- Williams, P. J. and Smith, M. W.: The ground thermal regime, in *The Frozen Earth*, pp. 83–121, Cambridge University Press., 1989.
- Woo, M. K.: *Permafrost Hydrology*, Springer-Verlag Berlin Heidelberg., 2012.
- Yang, Y. and Aplin, A. C.: Definition and practical application of mudstone porosity-effective stress relationships, *Pet. Geosci.*, 10(2), 153–162, doi:<https://doi.org/10.1144/1354-079302-567>, 2004.  
990
- Yoshikawa, K. and Harada, K.: Observations on nearshore pingo growth, Adventdalen, Spitsbergen, *Permafr. Periglac. Process.*, 6(4), 361–372, doi:10.1002/ppp.3430060407, 1995.
- Yoshikawa, K. and Nakamura, T.: Pingo growth ages in the delta area, Adventdalen, Spitsbergen, *Polar Rec. (Gr. Brit.)*, doi:10.1017/S0032247400067565, 1996.





## Supplement of:

# Numerical modelling of permafrost spring discharge and open-system pingo formation induced by basal permafrost aggradation

Mikkel T. Hornum<sup>1,2</sup>, Andrew J. Hodson<sup>1,3</sup>, Søren Jessen<sup>2</sup>, Victor Bense<sup>4</sup>, Kim Senger<sup>1</sup>

5 <sup>1</sup>Department of Arctic Geology, The University Centre in Svalbard (UNIS), N-9171 Longyearbyen, Norway.

<sup>2</sup>Department of Geosciences and Natural Resource Management, University of Copenhagen, 1350 Copenhagen K, Denmark.

<sup>3</sup>Department of Environmental Science, Western Norway University of Applied Sciences, N-6856 Sogndal, Norway

<sup>4</sup>Department of Environmental Sciences, Wageningen University, 6708PB Wageningen, Netherlands.

*Correspondence to:* Mikkel T. Hornum (mth@ign.ku.dk)

## 10 S1 Validation of the 1DHT model

The 1D heat transfer model (1DHT) consists of a MATLAB script (MathWorks®, 2019) tailored to simulate dynamics of ground temperatures and permafrost conditions. The model code is publicly available at DOI:10.5281/zenodo.3578839.

Before the 1DHT model was applied in our investigation, it was validated through comparison with two analytical solutions.

In the following, we first describe the basis of the 1DHT model. Second, we present two different analytical solutions and

15 show how they compare with numerical results as simulated by the 1DHT model.


### S1.1 Model code

In the core of the 1DHT model is an explicit forward-difference time approximation of the one-dimensional conductive heat transfer (Eq. 1). For the interior cell,  $i$ , which is situated in a 1D grid in all of which the initial temperature,  $T^p$ , is known (Fig. S1), this approximation states that at a new time,  $(p + 1)$ ,

$$\begin{aligned} 20 \quad \frac{T_i^{p+1} - T_i^p}{\Delta t} &= \alpha \frac{T_{i+1}^p - T_i^p + T_{i-1}^p}{\Delta x^2} \\ \Leftrightarrow \quad T_i^{p+1} &= \frac{\alpha \Delta t}{\Delta x^2} (T_{i+1}^p + T_{i-1}^p) + \left(1 - 2 \frac{\alpha \Delta t}{\Delta x^2}\right) T_i^p \end{aligned} \quad (\text{S1})$$

where  $T_i^{p+1}$  is the temperature in cell  $i$  at the time  $(p + 1)$ ,  $\Delta t$  is the time step, and  $\Delta x$  is the distance to the center of the neighboring cells. The thermal diffusivity,  $\alpha$ , is calculated as defined by Eqs. (1), (3), and (4) in Sect. 4.1. Equation S1 is only a stable numerical solution if the stability criterion is true (Bergman et al., 2011):

$$25 \quad \frac{\alpha \Delta t}{\Delta x^2} \leq \frac{1}{2} \quad \Leftrightarrow \quad \Delta t \leq \frac{\Delta x^2}{\alpha} \frac{1}{2} \quad (\text{S2})$$



**Figure S1** Conceptual representation of a 1D grid for which the 1DHT model simulates temperature changes (Eq. S1).

## S1.2 Neumann's solution

In the case of phase change, conductive heat transfer becomes non-linear and the mathematical (Stefan) problems that arise may be of considerable difficulty (Carslaw and Jaeger, 1959). One of the exact solutions that deal with such a problem is the Neumann solution, which here is presented largely based on Mottaghy and Rath (2006). The presented version of the Neumann solution solves the 1D heat equation (Eq. 1), for a semi-infinite body, which consists of a single component and initially has the liquidus temperature. At the surface, the body is exposed to a negative temperature step change and the medium starts to change phase from liquid to solid. The position of the phase front,  $Z$ , is expressed as a function of time,  $t$ :

$$Z(t) = 2 \cdot \gamma \cdot \sqrt{\alpha_{so} \cdot t} \quad (\text{S3})$$

where  $\gamma$  is a parameter determined by

$$\frac{\left( \exp\left( (\alpha_{so} - \alpha_{li}) \frac{\gamma^2}{\alpha_{li}} \right) \cdot \operatorname{erfc}\left( \gamma \cdot \sqrt{\frac{\alpha_{so}}{\alpha_{li}}} \right) \right)}{\operatorname{erf}(\gamma)} - \frac{(T_L - T_S) \cdot k_{li} \cdot \sqrt{\alpha_{so}}}{(T_S - T_0) \cdot k_{so} \cdot \sqrt{\alpha_{li}}} = 0 \quad (\text{S4})$$


In both above equations,  $\alpha$ 's are thermal diffusivities,  $k$ 's are thermal conductivities, and subscripts  $so$  and  $li$  refer to the solid or liquid state.  $T_L$  and  $T_S$  are the liquidus and solidus temperatures and  $T_0$  is the surface temperature at  $t > 0$ . The latent heat of fusion is incorporated in the expression of the thermal diffusivity of the liquid:

$$\alpha_{li} = \frac{k_{li}}{\rho_{li} \cdot c_{li} + L \frac{-1}{T_L - T_S}} \quad (\text{S5})$$

where  $\rho_{li}$  and  $c_{li}$  is the liquid's density and specific heat capacity, respectively.

To compare the 1DHT model with the exact Neumann's solution (Eq. S3), a situation which can be handled by both methods, was defined: A body of pure water, initially at the liquidus temperature  $T_L = 0$  °C is exposed to a surface temperature of  $T_0 = -4$  °C for a period of 3000 yr. The thermal properties of ice and water are as listed Table 1 and the solidus temperature is  $T_S = -2$  °C. In the following, these conditions will be referred to as Neumann conditions.

Solving Eq. S4 with the Neumann conditions, we found that  $\gamma = 0.0679$ . Numerically, the 1DHT model simulated the temperature development in a 1D-grid containing 100 cells each with a length of 2 m. From the model simulation results, the propagation of the freezing front was evaluated by interpolating  $T = -2$  °C. The propagation of the freezing front, as calculated by Neumann's solution and evaluated from the 1DHT model simulation, is plotted on Fig. S2. The RMSE of the simulation results is 0.011 and show a relatively good model performance.



55 **Figure S2** Freezing front depth with time in a body of water under Neumann conditions (see text) as calculated by the numerical 1DHT model and the analytical Neumann's solution.


### S1.3 Step change in surface temperature (no latent heat effects)

This analytical solution also assumes a negative temperature step change at the surface of a semi-infinite body: At the time  $t=0$ , the surface temperature is  $T_{0i}$ , and at any later times ( $t > 0$ ), it is  $T_0$ . As opposed to Neumann's solution, latent heat effects are neglected, but the initial medium (e.g., ground) temperature can follow any (uniform) geothermal gradient and the medium may consist of several components. Following the step change in surface temperature ( $\Delta T_0 = T_0 - T_{0i}$ ), the temperature change,  $\Delta T$ , is described as a function of time,  $t$ , and depth,  $z$ , by (Carslaw and Jaeger, 1959; Eppelbaum et al., 60 2014):

$$\Delta T(z, t) = \Delta T_0 \cdot \operatorname{erfc}\left(\frac{z}{2 \cdot \sqrt{\alpha_{eff} \cdot t}}\right) \quad (\text{S6})$$

where  $\alpha_{eff}$  is the effective thermal diffusivity. As with Neumann's solution, it was necessary to describe conditions, which this analytical solution can handle. The initial surface temperature was defined as  $T_{0i} = 5 \text{ }^\circ\text{C}$  and the ground temperature distribution followed a geothermal gradient of  $0.025 \text{ }^\circ\text{C m}^{-1}$ . At times  $t > 0$ , the surface temperature was defined as  $T_0 = 0 \text{ }^\circ\text{C}$  implying that  $\Delta T_0 = -5 \text{ }^\circ\text{C}$ . The medium had the geothermal properties of silty sand (Table 2) and a total porosity  $n=0.4$ , which was fully saturated with water. This yields  $\alpha_{eff} = 5.7 \text{ m}^2 \text{ yr}^{-1}$ .

The numerical grid was set up as for the simulation of the Neumann conditions except for the temperature distribution, which followed the geothermal gradient as described above. The calculated ground temperature distribution from both the 1DHT model and the analytical solution at  $t = 1000 \text{ yr}$  is presented on Fig. S3. An excellent performance by the 1DHT model is indicated by a RMSE of  $1.3 \cdot 10^{-5}$ .





75 **Figure S3** Comparison of the ground temperature distribution at  $t = 1000$  yr calculated analytically (Eq. S6) and as simulated by the 1DHT model.

## S2 Hydraulic conductivity of Carolinefjellet and Helvetiafjellet Formations

80 The vertical permeability,  $\kappa_v$ , of the sandstone-dominated Carolinefjellet and Helvetiafjellet formations were measured as part of the Longyearbyen CO<sub>2</sub> Laboratory Project (Olaussen et al., 2020, and references therein). The small-scale horizontal permeability,  $\kappa_h$ , for sandstones is typically a factor two higher than  $\kappa_v$  (Domenico and Schwartz, 1998) and we converted the horizontal hydraulic conductivity,  $K_h$ , accordingly (Eq. 7). To tighten the  $K_h$ -range used in the groundwater model, we defined the realistic minimum, mean, and maximum values as the first, second and third quartiles of a statistical fit to the measured values. As illustrated on Fig. S4, three types of statistical distribution were tested; log-normal, Weibull and log-logistic (panels a), b) and c), respectively). While the log-logistic fit showed the best correlation, all three fits predicted the same hydraulic conductivities at the quartiles. The ranges of hydraulic conductivity of these units were defined by the 25 %, 50 % and 75 % percentiles of a Weibull probability fit to the measured values (Fig. S5).

85

### Carolinefjellet and Helvetiafjellet formations




**Figure S5-S4** Weibull-Log-normal (a), Weibull (b) and log-logistic (c) fits fit to the measured hydraulic conductivities of Carolinefjellet and Helvetiafjellet formations. Original data from the Longyearbyen CO<sub>2</sub> Laboratory Project (Olausson et al., 2020, and references therein). The log-logistic fit shows the best correlation with the measured values and the values used in the groundwater model were thus defined by the quartiles predicted by this fit. Note that the two other fits both predict the same quartiles.

90

### S3 Major ions in Adventdalen pingo spring waters

Hydrochemical data from 25 spring water samples from 2014 to 2017 presented by Hodson et al. ([in review 2020](#)) and publicly available from DOI:10.5285/3d82fd3f-884b-47b6-b11c-6c96d66b950d give insights into the groundwater system in Adventdalen. As illustrated in Fig. S6a, water samples from Lagoon (LP), Førstehytte (FHP), Innerhytte (IHP) and River Pingos (RP) reveal that all these springs share the same sodium-bicarbonate ( $\text{NaHCO}_3$ ) water type. The only exception is four samples taken near River Pingo in 2017 of a magnesium-sulfate water type (Fig. S6b). These four samples were excluded from the discussion because they might not be associated with a pingo according to Hodson et al. ([In Review 2020](#)).



**Figure S5** Stiff plots of major ion concentrations from pingo spring water samples in Adventdalen (data first presented in Hodson et al., [In Review 2020](#)). The corners of the Stiff polygons represent mean concentrations.

### References

- 105 Bergman, T. L., Lavine, A. S., Incropera, F. P. and Dewitt, D. P.: Fundamentals of Heat and Mass Transfer, 7th ed., John Wiley & Sons., 2011.
- Carslaw, H. S. and Jaeger, J. C.: Conduction of heat in solids, 2nd ed., Clarendon Press., 1959.
- Domenico, P. A. and Schwartz, F. W.: Physical and chemical hydrogeology, Wiley & Sons., 1998.
- 110 Eppelbaum, L., Kutasov, I. and Pilchin, A.: Applied Geothermics, Lect. Notes Earth Syst. Sci., 757, doi:10.1007/978-3-642-34023-9, 2014.

Hodson, A., Nowak, A., Hornum, M. T., Senger, K., Redeker, K. R., Christiansen, H. H., Jessen, S., Betlem, P., Thornton, S., Turchyn, A. V., Olausen, S. and Marca, A.: Sub-permafrost methane seepage from open system pingos in Svalbard, Cryosph., doi:10.5194/tc-2020-11, 2020.

MathWorks®: MATLAB R2019b, [online] Available from: <https://se.mathworks.com/products/matlab.html>, 2019.

- 115 Mottaghy, D. and Rath, V.: Latent heat effects in subsurface heat transport modelling and their impact on palaeotemperature reconstructions, *Geophys. J. Int.*, 164(1), 236–245, doi:10.1111/j.1365-246X.2005.02843.x, 2006.

Olausen, S., Senger, K., Braathen, A., Grundvåg, S.-A. and Mørk, A.: You learn as long as you drill; research synthesis from the Longyearbyen CO2 Laboratory, Svalbard, Norway, *Nor. J. Geol.*, 99(2), 157–187, doi:10.17850/njg008, 2020.