

Millennial-scale fluctuations of palaeo-ice margin at the southern fringe of the last Fennoscandian Ice Sheet

Karol Tylmann¹, Wojciech Wysota², Vincent Rinterknecht³, Piotr Moska⁴, Aleksandra Bielicka-Giełdoń⁵, ASTER Team*

5 ¹Department of Geomorphology and Quaternary Geology, University of Gdańsk, Gdańsk, 80-308, Poland

²Department of Geology and Hydrogeology, Nicolaus Copernicus University, Toruń, 87-100, Poland

³Aix Marseille Univ, CNRS, IRD, INRAE, CEREGE, Aix-en-Provence, 13545, France

⁴Institute of Physics – Centre for Science and Education, Gliwice, 44-100, Poland

⁵Department of General and Inorganic Chemistry, University of Gdańsk, Gdańsk, 80-308, Poland

10 *A list of the team members appears at the end of the paper

Correspondence to: Karol Tylmann (k.tylmann@ug.edu.pl)

Abstract. ~~The paper presents the first terrestrial record of millennial-scale palaeo-ice margin oscillations at the southern fringe of the last Fennoscandian Ice Sheet (FIS) during the last glacial cycle. The study area is located in northern Poland close to the last FIS maximum limit.~~ The paper presents a study of reconstructing chronology and dynamics of palaeo-ice margin oscillations at the southern fringe of the last Fennoscandian Ice Sheet (FIS are) based on combined luminescence and ¹⁰Be surface exposure dating. ~~The study area is located in northern Poland close to the last FIS maximum limit.~~ Optically stimulated luminescence (OSL) Luminescence method was used to date sandy deposits (fluvioglacial sediments and aeolian deposits filling fossil periglacial wedges) intercalating basal till layers, ~~and~~ the most likely age of the tills was constrained by Bayesian modelling of the sequence of OSL ages and lithostratigraphy. ¹⁰Be surface exposure dating was used ~~method was used~~ on erratic boulders left during the final retreat of the last FIS and resting on ~~at~~ the surface of glacial landforms. Our results, which are mainly based on OSL chronology and Bayesian modelling, indicate millennial-scale oscillations of the last FIS in northern Poland between ~19 and ~17 ka. The last FIS retreated and re-advanced over a relatively short period of time (2–3 ka), leaving ~~a~~ lithostratigraphic records (basal tills) of three ice re-advances ~~in~~ over a millennial-scale cycle: 19.2 ± 1.1 ka, 17.8 ± 0.5 ka and 16.9 ± 0.5 ka. Despite ¹⁰Be surface exposure ages obtained for 14 erratic boulders are poorly-clustered, the main mode of ages distribution occur at ~18 ka and indicates a possible signal of the ice sheet retreat after one of the re-advances. ~~The paper presents the first terrestrial record of millennial-scale palaeo-ice margin oscillations at the southern fringe of the FIS during the last glacial cycle.~~ We explore the dynamics of these oscillations and ~~confront~~ compare the proposed cycles of the southern FIS advances and retreats with existing patterns of the last deglaciation and millennial-scale fluctuations of the last FIS inferred from marine records.

1 Introduction

Ice sheets and glaciers are key components of a cryosphere coupled to climate, global sea level ~~or~~ and ocean circulation (e.g., Clarke et al., 1999; Greve and Blatter, 2009; Fyke et al., 2018). Ice sheets fluctuations are good indicators of climate changes, ~~as~~ because they tend to stay in equilibrium with regional climate, and they reacting on any long-term variations of temperature and precipitation by their mass balance adjustment. However, interactions between ice sheets and climate are complex. Cooling and warming affect expansion and shrinkage of glaciated areas, but on the other hand, the size-extent of areas with permanent ice cover have a significant impact on the climatic system, e.g. by controlling the magnitude of albedo, by delivering large amounts of ~~cold~~ freshwater into oceans or by diverting the jet stream circulation. Thus, ice sheets and glaciers are strongly linked to climate, ~~being in fact~~ and they are as such a key element ~~in-of~~ the ~~ice~~ cryosphere-climate ~~ie~~ system (e.g., Hahn et al., 2018; Noble et al., 2020). In the era of global warming, a lot of attention is given to understand their past and current trends and to feed models simulating their future behaviour. ~~The last two ice sheets, Antarctica and Greenland have been also monitored, and their shrinkage has been analysed in relation to changing climate (Thomas, 2001; Rignot et al., 2019).~~ Our knowledge about interactions of the Pleistocene palaeo-ice sheets with past climate changes is however, much more limited, as glacial geological records ~~is~~ are fragmentary and in many cases difficult to date (e.g., Fuchs and Owen, 2008; King et al., 2014; Davis, 2022). ~~Therefore,~~ In order to explore interactions between palaeo-ice sheets, such as the Fennoscandian or the Laurentide ice sheets, with Pleistocene climate fluctuations it is ~~essentially important~~ key to link available geological records s with timing of palaeo-ice sheets advances and retreats. ~~It~~ Chronologies ~~enables to~~ correlate ~~these~~ spatial fluctuations with palaeoclimatic records available from ice cores, marine sediments, loess sequences or other lacustrine archives for examples s (Levy et al., 2018; Rea et al., 2018; Nawrocki et al., 2019). Dating terrestrial glacial records s is however challenging, mainly due to the very dynamic nature of the glacial environment, resulting in great lateral and vertical variations of sediments, presence of erosional gaps and deformations as well as post-depositional reworking (Brodzikowski and van Loon, 1987; Kurjański et al., 2020).


Here we present a study reconstructing the chronology and dynamics of palaeo-ice margin oscillations based on combined optically stimulated luminescence (OSL) ~~luminescence~~ and ^{10}Be surface exposure dating. The study was conducted in northern Poland, at the southern fringe of the last Fennoscandian Ice Sheet (FIS). ~~Luminescence-OSL~~ method was used to date sandy deposits intercalating basal till layers and the most likely age of the tills was constrained by Bayesian modelling incorporating the sequence of OSL ages and lithostratigraphy ~~the most likely age of the tills was constrained by Bayesian modeling~~. ^{10}Be surface exposure dating ~~method~~ was used to date erratic boulders left by the last FIS and resting on a surface of conspicuous glacial landforms. The paper presents the first terrestrial record of millennial-scale palaeo-ice margin oscillations at the southern fringe of the FIS during the last glacial cycle. We explore the dynamics of these oscillations, and we ~~confront~~ compare the proposed cycles of the southern FIS advances and retreats with existing pattern of the last deglaciation and millennial-scale fluctuations of the last FIS inferred from marine records.

2 Study area and dating sites

2.1 Location

65 The study area is located in northern Poland in the region covered by the last FIS, in the very close vicinity of its maximum limit (Fig. 1a). It covers the region of a fresh glacial landscape shaped in the Late Pleistocene during the last ice sheet advance and retreat, which in this part of the northern Polish Lowland occurred around 22–18 ka BP (Tylmann et al., 2019; Hughes et al., 2022; Marks et al., 2022). The area is located within the Lubawa Upland, an elevated morainic upland ~~(the Lubawa Upland)~~, where the highest elevations exceed 300 m a.s.l., and are located up to 200 m higher than the surrounding

70 lowlands and valleys (Fig. 1b). The topography of this region is highly diversified with conspicuous moraine hillocks and deeply incised valleys creating local ~~denivelations-relief~~ up to 50–70 m. Variability of such fresh glacial relief is a result of glaciotectionic deformations that repeatedly ~~occurring-occurred during-over~~ several Pleistocene glaciations in this region (Marks, 1979; Gałazka et al., 2009) and of intensive meltwater erosion of the ice bed and ice sheet ~~s~~ foreland during the last deglaciation (Tylmann, 2014).



75

80

Figure 1: (a) Study area against the maximum extent of the last FIS in Europe. The Channel River route during the Last Glacial Maximum (LGM) is marked with black dashed line (Toucanne et al., 2015). (b) Digital elevation model (SRTM) of northern Poland with location of sediments site (Rożental), large erratic boulders (LES-3 – 13, LGM-11 – 12, LUB-01 – 05 and POM-1 – 2) and coring site where radiocarbon dating has been done (Niewiarowski, 2003). Black dots with sample symbols indicate location of boulders in the study area, while black dots with sample symbols and re-calculated ages indicate location of boulders in the surroundings. Main limits of the last FIS (LGM and PM) according to Geological Map of Poland 1 : 500 000 (Marks et al., 2006).

The Sediments-sediments outcrop where luminescence dating was conducted is located on the north-western slope of the Lubawa Upland, within one of the moraine hillocks which occur in this area (Figs. 1b and 2b). The site is a gravel pit in Rożental, where the sequence of up to 10 m thick Pleistocene glacial deposits is exposed (Fig. 3). The origin of this sedimentary sequence was described in details elsewhere (Tylmann and Wysota, 2011; Tylmann et al., 2014). Here, we

85


focus on a brief description of the main sedimentary units and luminescence dating of glaciofluvial deposits and fossil periglacial sand wedges. ¹⁰Be surface exposure dating was applied to large erratic boulders resting on ~~the~~ glacial landforms. Location of dated boulders is presented in Fig. 1.

90 2.2 Glacial record

2.2.1 Landforms

The most characteristic elements of the glacial relief in the study area are numerous ridges of ~~a~~ well-preserved terminal moraines and deeply incised valleys of various origin (Fig. 2a). Elevations of terminal moraine ridges ranges from about 160 m a.s.l. to above 300 m a.s.l., and the elevations of valley floors is-range between 90 m a.s.l. and about 280 m a.s.l. Terminal moraines occur mainly in the central, relatively highly elevated part of the Lubawa Upland as well as on its western and eastern slopes. On the western slope of the Lubawa Upland most ~~of~~ terminal moraines are oriented NE-SW, while on the eastern slope moraines orientation is much more diversified (Fig. 2a). Most ~~of the~~ terminal moraines have ~~an~~ typical asymmetric morphological cross-profile.

Valley systems are also clearly visible in the topography of the Lubawa Upland, ~~(especially in its relatively highly elevated central part), and-it~~ consists of three types of glacial valleys: subglacial, ice-marginal and proglacial valleys (*sensu* Greenwood et al., 2007). Subglacial valleys are almost entirely oriented NW-SE, and most of them are currently occupied by rivers or lakes. ~~They-Some of them~~ have undulating longitudinal profiles and ~~some of them others,~~ cutting elevated morainic areas, ~~—~~ having convex longitudinal profiles. Spatial distribution of these valleys indicates that they are mostly perpendicular or oblique to the terminal moraine ridges (Fig. 2a). The largest landforms have complex morphology and they may be classified as subglacial tunnel valleys, while others with simpler morphology are probably subglacial channels (*sensu* Clayton et al, 1999). Ice-marginal valleys are oriented NE-SW and they occur mostly on western and north-western slopes of the Lubawa Upland. These valleys are mostly parallel or oblique to the terminal moraine ridges, and they are perpendicular or oblique to subglacial valleys. On the western slope of the Lubawa Upland ice-marginal valleys occur in a ‘step-like’ morphological sequence with parallel valleys running along the slope (Fig. 2a). A few valleys which might be classified as routes of former proglacial meltwater outflow can be found on the southern and south-eastern slope of the highest elevated central part of the Lubawa Upland (Fig. 2a). Proglacial valleys are oriented N-S and NW-SE, and they run downslope towards ~~the~~ outwash plains which occur in the southern and south-eastern parts of the study area.




115 **Figure 2:** (a) High-resolution (1 m) digital elevation model (LiDAR) of the study area with the main glacial landforms. (b) Surface
 116 sediments of the study area draped over the digital terrain model. Distribution of surface sediments was compiled based on Detailed
 117 Geological Map of Poland (Gałazka and Marks, 1997; Gałazka, 2003, 2006, 2009; Welniak, 2002). The main moraine plateaux and
 118 outwash plains are indicated as well as locations of the Rożental site and sampled erratic boulders.

2.2.2 Sediments

120 Glacial till and fluvioglacial/fluvial sand and gravel dominate the surface lithology of the Lubawa Upland. Till and related
 121 deposits (unsorted “dirty” gravels with boulders) are associated with moraine plateaux and terminal moraines, and which
 122 occur mainly in the south-western, western and north-western parts/sectors, in the elevated central part/sector, as well as in
 123 south-eastern and eastern parts/sectors of the study area. Fluvioglacial sand and gravel are associated with outwash plains,
 124 which occur mostly on the southern, south-eastern and eastern slopes of the Lubawa Upland, as well as in association with
 125 terraces within wide ice-marginal valleys found in the north-western corner-sector of the study area and with large subglacial
 126 valleys (Fig. 2b). Outwash plains in south-eastern and eastern parts of the study area are usually narrow, elongated tracks of
 127 glacial meltwater runoff, located in between the higher moraine uplands and oriented NW-SE. Besides glacial till and
 128 fluvioglacial/fluvial sand and gravel, glaciolacustrine and lacustrine silt and clay also occur, mainly as a few isolated patches
 129 in south-western and southern part of the region. The spatial distribution of most of surface sediments is a result of the last
 130 (perimeter > 1 m) erratic boulders and extensive boulder fields, located on the moraine plateau, which commonly occur at the
 131 surface of moraine plateau, on moraine hillocks or within the glacial valleys. The largest of them were the subject of ¹⁰Be

dating (this study; Rinterknecht et al., 2005, 2006; Tylmann et al., 2019) (Fig. 2b). Fluvial sand and gravel are associated with river channels, while valleys and lake basins are filled with Late Glacial and Holocene peat ~~and-as well as alluvium and colluviumdeluvium~~ (Fig. 2b).

135 ~~Sequence-~~The sequence of Pleistocene glacial deposits exposed at the gravel pit in Rožental consists of fluvioglacial sand and gravel covered by glacial till layers (Fig. 3a). Fluvioglacial unit (Rz1) is dominated by medium- to large-scale sandy-gravelly and gravelly-sandy beds with horizontal stratification. Most of these beds ~~reveals-show~~ normal grading and contacts between particular lithofacies are erosional. Occasionally, sand beds and lithofacies with through-cross bedding also occur. Within sandy and sandy-gravelly beds oversized clasts are very common. Fluvioglacial unit Rz1 is covered by a 2.5 m thick
140 massive till (unit Rz2) with ~~a~~ fossil periglacial structures (sand wedges) occurring in two separate horizons – K1 and K2 (Fig. 3b). This indicates that unit Rz2 consists of three separate till subunits: Rz2a, Rz2b and Rz2c. Distinct features of tills such as: (1) sharp, planar contact with underlying deposits (Fig. 3c), (2) embedded clasts with flat upper surface and ploughing marks (Fig. 3d) and (3) glacial striations on clast surface (Fig. 3e), indicate that these are subglacial traction tills –
145 (Fig. 3b; Tylmann, 2014; Tylmann et al., 2014).



150 **Figure 3:** Sequence of the Pleistocene deposits exposed at the Rožental site. (a) Panoramic picture of the sequence with two main sedimentary units indicated: fluvioglacial sand and gravel (unit Rz1) and basal till (unit Rz2). (b) Upper part of the sequence with periglacial horizons K1 and K2 (yellow wedges), and till subunits Rz2a, Rz2b and Rz2c. (c) Sharp, planar contact between units Rz1 and Rz2a. (d) Clast with flattened upper surface embedded at the contact between units Rz1 and Rz2a. Ploughing mark (black arrow) and

diamicitic injection (white arrow) are visible below the clast. (e) Flattened upper surface of clast embedded at the bottom of unit Rz2b; glacial striations are marked with white arrows.

3. Methods

3.1 Luminescence dating and Bayesian analysis

155 Samples for OSL dating were taken from sandy beds of fluvio-glacial unit Rz1 (three samples) and from aeolian sand filling fossil periglacial wedges of horizons K1 and K2 (eight samples). Sediments were sampled with plastic tubes pressed into the vertical section of deposits and secured with black PEVC tape in order to protect samples from sunlight (Fig. 4a). Samples were analysed at the Gliwice Luminescence Laboratory (Moska et al., 2021) and only material taken from the middle parts of the plastic tubes was processed. For OSL measurements, grains of quartz (45–63 μm) were extracted from the sediments
160 by routine treatment with 20% hydrochloric acid (HCl) and 20% hydrogen peroxide (H_2O_2) to remove carbonates and organic matter formed in the samples. The final step of preparation was a treatment with concentrated (40%) hydrofluoric acid (HF) for 40 minutes to remove ~~remaining-of-all~~ other ~~non-quartz~~ minerals and ~~the~~ outer layer of ~~the~~ quartz grains (~10 μm , responsible for absorbing the alpha radiation; Aitken, 1985). All OSL measurements were performed using an automated Daybreak 2200 TL/OSL reader (Bortolot, 2000) fitted with a calibrated $^{90}\text{Sr}/^{90}\text{Y}$ beta source delivering about 2.7
165 Gy/min to grains at sample position. Daybreak 2200 uses blue diodes (470 ± 4 nm) delivering about $60 \text{ mW}/\text{cm}^2$ at the sample position after passing through BG39 filters. Equivalent doses were determined using the single-aliquot regenerative-dose (SAR) protocol (Murray and Wintle, 2000). The SAR dose response curves were best represented by a single saturating exponential function. Final equivalent dose (D_e) values were calculated using the Minimum Age Model (MAM) or Central Age Model (CAM) (Galbraith et al., 1999). To determine the most adequate statistical model for equivalent dose calculation
170 the overdispersion parameter (σOD) was calculated using the R package ‘Luminescence’ (Kreutzer et al., 2012). We applied the CAM model in calculations when σOD was below 20%, while the MAM model was applied when σOD did not meet this criterion. In order to assess the dose rates (D_r) that arise from decay chains ~~and-of~~ potassium we used high-resolution Canberra gamma spectrometry, calibrated with ~~the reference materials, namely~~ IAEA-RGU-1, IAEARGTh-1, and IAEA-RGK-1 obtained from International Atomic Energy Agency reference materials. The dry dose rates (Guerin et al., 2011)
175 were adjusted for water content, following Aitken (1985). The cosmic ray dose-rate to the site follows the calculations suggested by Prescott and Stephan (1982). The calculated OSL ages are reported in ka with 1σ uncertainties in Appendices (Table A1) as well as values of measured equivalent doses for individual aliquots in each sample (Table A2).

OSL ages were analysed with the Bayesian approach to modelling the chronology of the sediments sequence, which uses the lithostratigraphic record and numerical age of sediments. The *prior* model consists of ~~the~~ sequence of sediments units
180 arranged in stratigraphic order and inferred from lithostratigraphy. Numerical dating controls (OSL age probability distributions) constrain the possible time of sediments deposition. In Bayesian analysis, they represent the ~~likelihood~~ likelihood that any one sample has a particular age. Bayesian age modelling was performed using *Sequence* algorithms in OxCal (Bronk Ramsey, 2009a), ver. 4.4. The algorithms use Markov chain Monte Carlo (MCMC) sampling to build a distribution

of possible solutions and to generate a probability called the *posterior* density estimate for each sample. It is a combination of both the *prior* model and the likelihood probability. These density estimates take into account the lithostratigraphic order (*prior*) and typically reduce the uncertainty range in comparison to likelihood probabilities. The *Sequence* model in OxCal was divided into a series of *Phases*, each representing the stages of sediments deposition which may be correlated with particular dating controls. Thus, each *Phase* consists of a group of dating controls and is separated by *Boundary* commands, which delimit the duration of each *Phase* and generate an age posterior density estimate. Moreover, we used *Before* (“*terminus ante quem*”) command to constrain the chronology when stages evidently pre-dated a particular event. The whole *Sequence* is constrained by *Boundary* commands, which delimit the start and the end of the model. The *Sequence* begins with the *Boundary* “Start” command and the *Phase* “MIS 6”, which consists of three OSL ages of the Rz1 fluvioglacial sediments. Then, the “Rz2a till” was introduced with a *Boundary* command and subsequently the *Phase* “I periglacial phase”, consisting of a group of five OSL dating controls from aeolian sand filling fossil periglacial wedges of horizon K1, was defined. The next stage is *Boundary* command “Rz2b till” and above that the *Phase* “II periglacial phase”, consisting of three OSL dating controls from aeolian sand filling fossil periglacial wedge of horizon K2, was introduced. The uppermost till layer was defined with the *Boundary* command “Rz2c till” and the constraint was that it had to pre-date (*Before*) radiocarbon age of sample Gd-10818 ($16\,190 \pm 330$ cal yr BP – calibrated with the IntCal20 curve in OxCal ver. 4.4) of organic deposits at Stary Cieszyn coring site, because these deposits were very likely formed after deglaciation (Niewiarowski, 2003). The *Sequence* is closed with the *Boundary* “End” command. The notation of commands used to process the algorithms is available in the Appendices (Table A3).




Figure 4: (a) Sampling for OSL dating in Rz1 unit (left picture) and K2 periglacial wedge (right picture). Sandy deposits were sampled with plastic tubes protected with black PVC tape. (b) Sampling for ^{10}Be surface exposure dating. Upper surface of erratic boulder was sampled with a hammer and chisel.

3.2 ¹⁰Be surface exposure dating

Samples for ¹⁰Be surface exposure dating were collected from massive (perimeter \geq 1 m) and intact boulders resting on glacial landforms. Sampled boulders are large and stable (embedded into the ground) granitic rocks protruding above the ground surface (Fig. 4b). We selected the biggest erratic boulders which are available in the study area. Eleven out of 14 boulders are located on moraine surfaces, while three boulders are located in subglacial and proglacial valleys (Table A4 in the Appendices). We preferred the exposed position of boulders on moraine plateau and/or terminal moraines, as the best location for the surface exposure dating. Detailed geomorphological position of each boulder is presented in Fig. A1 in the Appendices. Samples were taken with a manual jackhammer or with a hammer and chisel from the upper surface of boulders. All boulders are characterized by quartz-rich lithologies such as granitoids, granite gneisses and gneisses, ~~thus and~~ 150–200 g of material per sample was enough for further preparation.

3.2.1 New samples

The first stages of ‘LUB’ samples (n = 5) preparation were conducted at the laboratory of the University of Gdańsk, Poland. Samples were crushed and sieved; the 0.25-0.71 mm quartz fraction was ~~decontaminated-separated~~ by heavy liquid (SPT) separation (to remove heavy minerals) and froth flotation (to remove feldspars). ~~Then successive~~ Several acid leachings (2% HF + HNO₃) in a hot ultrasonic bath ~~were~~ applied in order to purify the quartz. The ~~purity of~~ quartz purity was checked ~~with by~~ ICP-OES analysis for Al content. The next stages of preparation were conducted at the CALM laboratory (Cosmonucléides Au Laboratoire de Meudon) ~~Cosmonucléide Laboratory~~ at the Laboratoire de Géographie Physique (LGP) ~~in Meudon~~, France. Purified quartz was spiked systematically with ~460 mg of a commercial ⁹Be carrier solution (concentration of 998 mg/l \pm 3.7 mg/l) and then dissolved with concentrated HF. Beryllium was separated from remaining metals and purified in three stages: (1) anion column to remove Fe(III), (2) cation column to remove Ti, alkalis and separate Be from Al, and (3) hydroxide precipitation to remove residual alkalis, Mg and Ca. Samples were then dried, oxidized and mixed with niobium powder before being pressed in cathodes for AMS measurements. The ¹⁰Be/⁹Be ratios were measured by accelerator mass spectrometry (AMS) at the French National AMS Facility ASTER, Aix-en-Provence (Arnold et al., 2010). The measured ¹⁰Be/⁹Be ratios were normalized relative to the in-house standard STD-11 using an assigned ¹⁰Be/⁹Be ratio of $(1.191 \pm 0.013) \times 10^{-11}$ (Braucher et al., 2015) and a ¹⁰Be half-life of $(1.387 \pm 0.012) \times 10^{-6}$ years (Chmeleff et al., 2010; Korschinek et al., 2010). Analytical 1 σ uncertainties include uncertainties in AMS counting statistics, uncertainty in the standard ¹⁰Be/⁹Be, an external AMS error of 0.5% (Arnold et al., 2010), and a chemical blank measurement.

¹⁰Be ages were calculated using the most recent global production rate (Borchers et al., 2016) and the time dependent scaling scheme for spallation according to Lal (1991) and Stone (2000) (the ‘Lm’ scaling scheme). We corrected the ¹⁰Be production rate for sample thickness according to an exponential function (Lal, 1991) and assuming an average density of 2.7 g/cm³ for granitoid, granite gneiss and gneiss. ~~The An~~ appropriate correction for self-shielding (boulder geometry) was applied when the surface of the sampled boulder had a slope of more than 10°. No correction for surface erosion of boulders was applied,

as we interpret the ^{10}Be results as minimum ages. All calculations were performed using the online exposure age calculator
240 formerly known as the CRONUS-Earth online exposure age calculator – version 3 (<http://hess.ess.washington.edu/math/>;
accessed: 10.05.2023.), which is an updated version of the online calculator described by (Balco et al., 2008). Ages are
reported with 1σ uncertainties (including analytical uncertainties and the production rate uncertainty) in Table A4 in [the](#)
Appendices.

3.2.2 Recalculated samples

245 We recalculated ^{10}Be ages already published for the study area ($n = 9$) based on data available in Rinterknecht et al. (2005,
2006) and Tylmann et al. (2019). We followed the same procedure of exposure age calculations as described in the above
section. Recalculated ^{10}Be exposure ages are also reported with 1σ uncertainties (including analytical uncertainties and the
production rate uncertainty) in Table A4 (see Appendices).

4. Results


250 4.1 OSL ages

Three OSL samples from unit Rz1 reveal various distributions of equivalent doses measured for individual aliquots. Sample
GdTL-1351 has the most clustered, unimodal distribution with $\sigma\text{OD} = 12\%$. Samples GdTL-1352 and GdTL-1353 have
bimodal and trimodal distributions respectively, with σOD parameters over 20% (Fig. 5a). For all three samples [the](#) MAM
model was applied to calculate D_e value, as [the](#) Rz1 unit consists of [poorly sorted](#) fluvio-glacial ~~poorly sorted~~ sediments
255 which may contain populations of partially bleached grains. [This is especially visible in the aliquot distributions of it is](#)
~~visible especially within aliquots distribution of~~ samples GdTL-1352 and GdTL-1353. [Given the](#) OSL ages calculated for
Rz1 sediments ~~are~~: 148.9 ± 7.2 ka (GdTL-1351), 143.9 ± 9.1 ka (GdTL-1352) and 126.8 ± 11.0 ka (GdTL-1353). ~~Therefore,~~
depositions of [the](#) Rz1 unit during the cold Marine Isotope Stage (MIS) 6 is the most likely.

Deposits filling two fossil periglacial wedges of horizon K1 were sampled for OSL dating. Two samples (Gd-TL-1349 and
260 GdTL-1350) were taken from one wedge, and three samples (GdTL-1879, GdTL-1880 and GdTL-1881) were taken from
another one (Fig. 5a). Distributions of equivalent doses measured for individual aliquots in these samples are well clustered
with σOD parameters below 20% (from 5% to 16%). Unimodal distributions dominates and only one sample (GdTL-1350)
~~revealing shows a~~ bimodal ~~type of~~ probability curve. D_e values were determined with [the](#) CAM model, and OSL ages
calculated for aeolian sand filling K1 wedges are: 18.7 ± 1.0 ka (GdTL-1349), 14.5 ± 0.8 ka (GdTL-1350), 19.1 ± 0.9 ka
265 (GdTL-1879), 18.2 ± 0.8 ka (GdTL-1880) and 17.4 ± 0.9 ka (GdTL-1881). Therefore, the most likely timing of sand
deposition within K1 periglacial wedges is around 20–17 ka ago, and it may be correlated with MIS 2. [The whole succession](#)
[of the sedimentary units \(Fig. 3b\), shows clearly that periglacial wedges of horizon K1 must have been formed after](#)
[deposition of the Rz2a till and before deposition of the Rz2b till.](#)

Three OSL samples were taken from the fossil periglacial sand wedge K2 (GdTL-1346, GdTL-1347 and GdTL-1348).

270 Distributions of equivalent doses measured for individual aliquots in these samples are also well clustered and unimodal with σ_{OD} parameter from 9% to 11% (Fig. 5a). D_e values were determined with the CAM model, and OSL ages calculated for aeolian sand filling K2 wedge are: 18.5 ± 0.9 ka (GdTL-1346), 16.4 ± 0.8 ka (GdTL-1347) and 17.3 ± 0.8 ka (GdTL-1348). The most likely timing of sand deposition is around 19–16 ka ago, ~~so~~ and it may be correlated with MIS 2. Periglacial wedge K1 must have been formed after deposition of the Rz2b till and before deposition of the Rz2c till.



275 **Figure 5:** (a) Sediment profile of the entire exposed sequence with sedimentary features, OSL ages and distributions of equivalent doses measured for individual aliquots. (b) Spatial distribution of sampled boulders with ^{10}Be ages. New samples are indicated with white dots while recalculated samples are indicated with dark dots. Ages identified as outliers are marked in red, accepted ages are marked in blue. All ages are given in ka. Inset graph shows distribution of ^{10}Be ages with kernel density estimate curve and statistics before (red) and after (blue) excluding outliers. Bayesian ages of till layers Rz2a, Rz2b and Rz2c are also marked (blue lines) for comparison with ^{10}Be ages.

280

4.2 Bayesian modelling

The run of the *Sequence* model was conducted in the *Outlier* mode, which assumes that outliers are distributed according to a student T distribution with five degrees of freedom; the scale is allowed to lie anywhere between 10^0 to 10^4 years (Bronk Ramsey, 2009b). In the initial model, the dating controls were all entered with a prior probability of 0.05 of being an outlier. Ages having an agreement index with the initial model <60%, and exceeding the 0.05 threshold of probability of being outliers in the initial model results, were down-weighted by being assigned an adequate higher prior probability of being outliers. Then, a re-run of the same *Sequence* model was conducted for the chronological sequence with down-weighted ages. Finally, the agreement index for the re-run model (A_{model}) was used to evaluate the reliability of the chronological sequences obtained (Chiverrell et al., 2013). Both input ages and modelled ages were reported with 1σ uncertainty (68.2% probability).

The initial model based on the assumed sequence of events and all dating controls ~~showed~~ shows a rather poor agreement index (41.3%), which ~~suggested~~ suggests that the results of the initial *Sequence* ~~were~~ are not reliable and ~~some outliers and~~ problematic ages must occur among the dating controls. We identified an outlier with the individual agreement index <10%. One OSL age belonging to the *Phase* “I periglacial phase” (sample GdTL-1350) ~~showed~~ shows a low agreement index of 4.6% and the probability of being an outlier ~~was~~ is estimated at 85% by the model. The age of this sample is 14.5 ± 0.8 ka, and it is most probably too young for the periglacial horizon K1. Thus, it was down-weighted by being assigned a prior probability of 0.85 of being ~~an~~ outliers in the re-run model, which ~~showed~~ shows a much better agreement index (103.4%). The individual agreement index for the modeled ages ranges between 75.2% and 128.2%, which means that the model is consistent and reliable. The modeled age distribution for the Rz2a till is 19.2 ± 1.1 ka, for the Rz2b till is 17.8 ± 0.5 ka and for the Rz2c till is 16.9 ± 0.5 ka (Table A5 in [the Appendices](#)). ~~The results~~ Bayesian modelling based on OSL chronology and lithostratigraphy ~~show~~ suggests that timing of the ice advances associated with Rz2a, Rz2b and Rz2c basal tills may be constrained to millennial-scale cycles of the palaeo-ice margin fluctuations at ~19 ka, ~18 ka and ~17 ka.

4.3 ^{10}Be ages

Surface exposure ages of boulders located in the study area range between 5.8 ± 0.8 ka and 40.3 ± 3.9 ka (Fig. 5b). Distribution of ages ($n = 14$) is polymodal with the main mode occurring at ~18 ka. The reduced chi-squared test indicates that the ages are poorly clustered: $\chi_R^2 = 35.25$. We identify two of the oldest ages (40.3 ± 3.9 ka and 35.5 ± 3.7 ka) and one of the youngest ages (5.8 ± 0.8 ka) as deviating the most from the main mode. They do not fall into a confidence interval arithmetic average $\pm 1.5 \times \text{IQR}$ (interquartile range, which is the range between the third quartile – Q3 and the first quartile – Q1 of the population), and are thus identified as outliers. For the boulders that are “too old”, they most probably contain beryllium inherited from episodes of exposure pre-dating the last deglaciation, and ~~for the boulder that is~~ “too young”, ~~age-it~~ may be a result of boulder ~~exposition~~ exposure after deglaciation ~~and/or significant postglacial erosion of sampled surface~~. Relatively high relief of the study area promotes post-glacial erosional processes, i.e. rainfall washing and/or mass

315 movements along slopes, degradation of the moraine surfaces and possible exhumation of erratics from eroded deposits. This
could affect the scatter of the obtained ages, despite the fact that most of them were selected as boulders resting on moraine
surfaces, in a stable geomorphological position (Fig. A1). After excluding these outliers, the remaining eleven ages range
between 12.5 ± 1.2 ka and 25.8 ± 2.4 ka and reduced chi-squared test shows a much improved cluster: $\chi_R^2 = 6.31$. However,
the variability of the remaining ages is 24.1%, and with a $\chi_R^2 > 2$, the dataset can be described as poorly-clustered (Blomdin
et al., 2016). The arithmetic mean and the standard deviation for these eleven surface exposure ages is 18.0 ± 4.3 ka (Fig.
5b), and it could represent the minimum deglaciation age of the study area, however geomorphological processes could have
320 had large impact on the spread of exposure ages (Heyman et al., 2011).

5. Discussion

5.1 Timing and dynamics of the last FIS oscillations


The first ice sheet advance which deposited Rz2a till dated of the most likely age constrained at-to 19.2 ± 1.1 ka, corresponds
most likely to the local Last Glacial Maximum (LGM) ice advance associated with the maximum expansion of the last FIS in
325 this region (Fig. 6a). The age of the local LGM in north-central and north-eastern Poland was recently estimated at ~ 19.0 –
 18.5 ka based on OSL dating and re-interpretation of available cosmogenic ages (Wysota et al., 2009, Marks, 2012) or at the
most likely time interval 22–18 ka, based on new cosmogenic chronology interpreted together with available radiocarbon
and luminescence ages (Tylmann et al., 2019). After maximum expansion of the last FIS, the ice margin retreated and
periglacial conditions with frost contraction of the exposed ground surface and aeolian deposition of sand occurred, leading
330 to the formation of periglacial horizon K1 at the Rożental site (Fig. 6b). Moreover, mass movements and denudation
processes were also active at this stage, which is indicated by a partly eroded Rz2a till layer and the gravitational
deformation of fossil sand wedges of horizon K1 (Tylmann et al., 2014).

The second ice advance deposited Rz2b till of the most likely age constrained to dated-at 17.8 ± 0.5 ka. The extent of this ice
advance is not unequivocally determined, however the ice most likely covered the locality of the Rożental site. Based on
335 spatial distribution of glacial landforms and sediments, i.e. outlets of subglacial valleys and proximal edges of narrow
outwash plains located on south and south-eastern slopes of the Lubawa Upland (Fig. 2), we argue that this ice advance
could have covered the highly elevated central part of the study area. The ice margin probably reached the south-eastern and
eastern slopes of the Lubawa Upland (Fig. 6c). After ~ 18 ka the ice sheet retreated again and the minimum deglaciation age
of the study area inferred from surface exposure dating of boulders (18.0 ± 4.3 ka) probably represents this stage of the ice
margin oscillations. However, the scatter of ^{10}Be ages is large (from 12.5 ± 1.2 ka to 25.8 ± 2.4 ka after excluding outliers)
340 and various factors, such as: inherited ^{10}Be signal, redeposition of boulders; and degradation of moraines and erosion of
boulders surface, may have had significant impact on the spread of reported exposure ages (Heyman et al., 2011; Blomdin et
al., 2016). ^{10}Be surface exposure age of a boulder located in the vicinity of the study area and most likely in the same
morphostratigraphic zone (sample LGM-11, 17.5 ± 1.6 ka), also suggests ice margin recession in this region immediately

345 after ~18 ka (Fig. 1b). The ice margin retreated to the north and north-west of the Rožental site study area and periglacial conditions occurred again, at least in the locality of the Rožental site where periglacial wedge K2 was formed (Fig. 6d).

The third ice advance which deposited the Rz2c till at Rožental (of the most likely age constrained to 16.9 ± 0.5 ka), was probably the least extensive (Fig. 6e). The ice sheet covered only the north-western edge of the Lubawa Upland and the ice margin was probably located along the ice-marginal valleys (Fig. 2a), which drained glacial meltwater south-westwards. The

350 final deglaciation of the study area occurred after ~17 ka.



355 **Figure 6:** Reconstruction of palaeo-ice margin oscillations in the study area and millennial cycles recorded in marine sediments from the eastern edge of the North Atlantic with and in ice core record from Greenland. a) Maximum extent of the last FIS around 19 ka ago. (b) Ice-free conditions around 19-18 ka ago. (c) Ice sheet advance around 18 ka ago. (d) Ice-free conditions around 18-17 ka ago. (e) Ice sheet advance around 17 ka ago. (f) Variations of $\delta^{18}\text{O}$ signature in NGRIP ice core (NGRIP-members, 2004), ϵ_{Nd} isotopic composition, turbidite frequency and sediments load in marine sediments from the Bay of Biscay (for details see Toucanne et al., 2008, 2010 and 2015). Episodes of the Channel River large meltwater discharge (R-events) are marked as well as Heinrich event 1 (HE 1) and the most likely age of till ages for Rz2a, Rz2b and Rz2c.

360 5.2 Correlation with regional glacial phases

Our results ~~indicate-suggest~~ millennial-scale oscillations of the last FIS in northern Poland between ~19 and ~17 ka. These cycles of ice sheet advances and retreats probably occurred in the late stage of the local LGM and during the subsequent deglaciation of this region. Timing of the maximum extent of the last FIS in its southern sector was recently constrained to ~24–23 ka in western Poland and north-eastern Germany during the Brandenburg (Leszno) Phase and to ~19 ka in north-central and north-eastern Poland during the Frankfurt (Poznań) Phase (Wysota et al., 2009; Ehlers et al., 2011; Marks, 2012; Marks et al., 2022). Based on the recent ¹⁰Be surface exposure dating and comparison to the available radiocarbon and luminescence ~~chronology~~chronologies, the most likely time intervals for the local LGM are 25–21 ka in western Poland and 22–18 ka in north-eastern Poland (Tylmann et al., 2019). ~~Therefore, T~~the Rz2a till dated based on our Bayesian modelling at 19.2 ± 1.1 ka ~~is~~may be thus correlated with the local LGM ice advance. In north-central Poland timing of the ice advance which reached the maximum limit of the last FIS was constrained based on OSL dating of the Upper Weichselian glacial sequence to ~18.5 ka (Wysota et al., 2009), which ~~might-could~~ also be correlated with our age constraint for the Rz2a till (19.2 ± 1.1 ka). However, based on apparent OSL ages obtained for the Rz1 unit and periglacial wedges of horizon K1, the possible time window for deposition of the Rz2a till is wide ~~and-as it~~ ranges between ~150 ka and ~19–17 ka (Fig. 5a). This suggests that the Rz2a basal till may be correlated with a MIS 6 ice advance (the Late Saalian glaciation) or with MIS 4/MIS 2 ice advances occurring before 19–17 ka. We argue that sediments of the Rz1 unit ~~the~~ most likely represents a recession phase of the MIS 6 ice sheet, as they consists of relatively coarse-grained, horizontally bedded lithofacies associated with intensive ablation cycles. ~~Therefore, I~~in our opinion, a deposition of the Rz2a till after MIS 6 is the most likely scenario. ~~and~~ This is supported by our Bayesian modelling, which takes into account the whole sedimentary sequence and, shows which provides the most probable age of ~~the~~is till correlated with MIS 2 (19.2 ± 1.1 ka).

380 The second ice advance, constrained with our modelling to 17.8 ± 0.5 ka, is comparable to one of the ice-marginal formations formed during the last deglaciation in the north-eastern corner-region of Poland: (Łopuchowo 2 and Gulbieniszki moraines) ~~that are~~ dated at 17.9 ± 1.3 ka with-using cosmogenic ³⁶Cl (ages reported in Dzierżek and Zreda, 2007). This ice advance may also be related to a regional ~~be also related to regional~~ sub-phase distinguished in northern Poland based on geomorphology between maximum extent of the last FIS and the Pomeranian Phase – the Kujawy-Dobrzyń subphase (Kozarski, 1995; Niewiarowski et al., 1995). However, a broad correlation along the palaeo-ice margin ~~over-a~~ large distances is ~~impeded-speculative~~ and uncertain, as various sections of ice-marginal formations at the southern fringe of the last FIS were usually formed asynchronously (e.g., Dzierżek and Zreda, 2007; Lüthgens and Böse, 2012; Tylmann et al., 2022).

The last ice advance in the study area was dated with our Bayesian modelling at 16.9 ± 0.5 ka and may be correlated with the Pomeranian Phase of the last deglaciation, which age was recently constrained to 17–16 ka (e.g., Marks, 2012, Marks et al., 2022) or 18–17 ka (Stroeven et al., 2016). However, new studies showed that the age of ice-marginal formations at the southern fringe of the last FIS traditionally correlated with a discrete time interval during the Pomeranian Phase, covers in fact a wide time window between 20 ka and 15 ka (Tylmann et al., 2022). ~~Thus, W~~we thus argue that ~17 ka ~~and~~ ice re-

advance occurred on the north-western slope of the Lubawa Upland, and this re-advance could be correlated with ice advances and/or ice margin stillstands within the Mazury Ice Stream which are dated at 18–17 ka (Tylmann et al. 2022).

395 5.3 Millennial-scale fluctuations of the last FIS

Our results ~~show-suggest~~ very dynamic oscillations of one particular segment of the FIS's southern front. The last FIS advanced and retreated over a relatively short period of time (2–3 thousands ~~of~~-years), leaving lithostratigraphic records (basal tills) of three ice advances, most likely at a millennial-scale cycle: ~19 ka, ~18 ka and ~17 ka. Millennial-scale fluctuations of the southern fringe of the last FIS have already been ~~already~~-explored ~~based-on~~by linking properties of marine
400 deposits from the eastern ~~edge-of~~-North Atlantic and precisely constrained by a radiocarbon chronology, with dynamics of the terrestrial palaeo-ice sheet margin in Europe (e.g., Zaragossi et al, 2001, 2006; Toucanne et al., 2008, 2010, 2015). During the last deglaciation, meltwater from the southern front of the FIS transported terrigenous deposits along the Channel River network (including ice-marginal valleys system – urstromtal – in the North European Plain) towards the Bay of Biscay. It was a key depocenter for far-travelled sediments released from the European ice sheets, including the southern
405 FIS. Properties of sediment~~s~~ sequences deposited in the Bay of Biscay, such as turbidite ~~deposits~~-frequency (Zaragossi et al, 2006; Toucanne et al., 2008) or sediment~~s~~ accumulation ratio (Toucanne et al., 2010), indicate increased meltwater discharge and enhanced ice sheet decay between ~20 and ~17 ka. After 20 ka sediments loading within the Bay of Biscay depocenter rose significantly in comparison to lower sediments accumulation ratio and turbidity activity between ~30 ka and ~20 ka (Fig. 6f). Between ~19 ka and 18.5 ka there is a sudden reduction of turbidity activity (Fig. 6f), however this could be a
410 result of the first well-known abrupt sea level rise – meltwater pulse at ~19 ka – the 19-ka MWP (Clark et al., 2004). This ~~could reflects-correspond to~~ a significant retreat of the southern FIS ice margin after the LGM period (Rinterknecht et al., 2006), which in our results is indicated after the first ice advance dated at 19.2 ± 1.1 ka. Maximum turbidity activity and sediment load, which occurred at ~18.3–17.0 ka, correspond~~s~~ to the main phase of the FIS melting in the North European Plain (Toucanne et al., 2008). The latter could be roughly correlated with an ice margin retreat after the second ice advance
415 in our study area, dated at 17.8 ± 0.5 ka. After ~17.5–17.0 ka the meltwater discharge from the southern FIS significantly decreased in response to the initiation of a deglacial pause and a global re-advance of glaciers and ice sheets in Europe corresponding to Heinrich event 1 (HE1) (Zaragossi et al., 2001; Toucanne et al., 2009). This event ~~is-correlated~~might be recorded in our results ~~aste~~ the last ice advance ~~recorded in our study area and which deposited the Rz2c till~~ dated at 16.9 ± 0.5 ka (Fig. 6f).

420 Coupling between the southern FIS fluctuations and the Channel River meltwater discharge was also investigated by Toucanne et al. (2015), ~~who-They~~ used the neodymium isotopic composition of sediments, a powerful tracer for terrigenous sediments geographical provenance, cored from the Bay of Biscay seafloor and sampled from moraines, ice-marginal valleys and proglacial lakes alongside the FIS southern margin. ~~As a results,They found that~~ episodes of the Channel River large meltwater discharges (R-events) ~~were-could be distinguished-identified~~ and correlated with the FIS dynamics (Fig. 6f). The

425 first ice advance in our study area (19.2 ± 1.1 ka) probably corresponds to the millennial-scale intervals of Channel River
shutdowns (i.e. pauses in deglaciation) between 21.3 ± 0.2 ka (i.e., end of the R3 event) and 20.3 ± 0.2 ka (i.e., onset of the
R4 event) or between 18.7 ± 0.3 ka (i.e., end of the R4 event) and 18.2 ± 0.2 ka (i.e., onset of the R5 event). The second ice
advance in our study area, constrained to 17.8 ± 0.5 ka, falls within an episode of substantial ice marginal retreat recorded by
Toucanne et al. (2015) between 18.2 ± 0.2 ka and 16.7 ± 0.2 ka (R5 event, just before HE1). ~~However~~ Finally, the third ice-
430 advance in our study area (16.9 ± 0.5 ka) potentially correlates well with a pause in the overall ice margin retreat between
 16.7 ± 0.2 ka and 15.7 ± 0.3 ka (HE1) according to Toucanne et al. (2015) or between 17.2 ± 0.4 ka and 15.7 ± 0.3 ka
according to the reconstruction of the FIS dynamics in the East European Plain (Soulet et al. 2013).

6. Conclusions

Our results ~~indicate-suggest~~ millennial-scale oscillations of the last FIS in northern Poland between ~19 and ~17 ka. Based
435 on OSL chronology and Bayesian modelling, combined luminescence and supplemented with ^{10}Be surface exposure dating,
we show that the last FIS advanced and retreated over a relatively short period of time (2–3 ~~thousands of years~~ka), leaving
lithostratigraphic records (basal tills) of three ice re-advances at-over a millennial-scale cycle: 19.2 ± 1.1 ka, 17.8 ± 0.5 ka
and 16.9 ± 0.5 ka. This is the first terrestrial record of possible millennial-scale palaeo-ice margin oscillations at the southern
fringe of the FIS during the last glacial cycle. Cycles of ice sheet re-advances and retreats occurred most likely in the late
440 stage of the local LGM and during the subsequent deglaciation of this region. The first ice re-advance ~~which~~ deposited the
Rz2a till (19.2 ± 1.1 ka) and is-might be correlated with the local LGM ice advance. The second ice re-advance constrained
to 17.8 ± 0.5 ka (Rz2b till) is comparable to one of the ice-marginal formation deposited in the north-eastern region of
Poland and dated at 17.9 ± 1.3 ka with-using cosmogenic ^{36}Cl . The last ice re-advance dated at 16.9 ± 0.5 ka (Rz2c till) is
could be correlated with ice advances and/or ice margin stillstands in-of the Mazury Ice Stream during the Pomeranian
445 Phase.

Possible mMillennial-scale palaeo-ice margin oscillations at the southern fringe of the FIS inferred from terrestrial record
~~was-were~~ linked to cycles recorded in marine deposits from the eastern North Atlantic andwith precisely constrained
radiocarbon chronologies ics-from-the-eastern-edge-of-the-North-Atlantic. The first ice advance (~~was dated at~~ 19.2 ± 1.1 ka) and
is-reflected in-could be correlated to a sudden reduction of turbidity activity between ~19 ka and 18.5 ka recorded in marine
450 sediments from the Bay of Biscay. The subsequent ice margin retreat ~~is-reflected in-might be connected to~~ the first well-
known abrupt sea level rise – meltwater pulse at ~19 ka (19-ka MWP). Timing of A-a second ice re-advance in our study
area was ~~dated-constrained at~~ 17.8 ± 0.5 ka. The following ice margin retreat is roughly correlated with the maximum
turbidity activity and sediment load at ~18.3–17.0 ka in the Bay of Biscay. The third and last ice re-advance recorded in our
study area ~~was dated at~~ (16.9 ± 0.5 ka) and may potentially corresponds to a significant drop of meltwater discharge from the
455 southern FIS, reflecting a pause in the overall deglaciation dynamics the initiation of a deglacial pause and a global re-
advance of glaciers and ice sheets in Europe related to ~~the~~ HE1.

Data Availability

The data that support findings of this study are available upon the reasonable request.

Team list

- 460 Georges Aumaître, Didier L. Bourlès and Karim Keddadouche (Aix Marseille Univ, CNRS, IRD, INRAE, CEREGE, Aix-en-Provence, 13545, France).

Author Contribution

- KT was responsible for conceptualisation of the study, fieldwork, sample preparation for ^{10}Be dating, data analysis and interpretation, figures preparation, writing and editing of the manuscript. WW contributed to the fieldwork, sampling for
465 OSL dating, analysing and interpreting data, editing and proof-reading of the manuscript. VR was responsible for sample preparation for ^{10}Be dating, contributed in editing and proof-reading of the manuscript. PM was responsible for OSL dating and contributed to data analysis and proof-reading of the manuscript. ABG was also responsible for ICP-OES analysis. ASTER Team preformed AMS measurements of $^{10}\text{Be}/^9\text{Be}$ ratios.

Competing interests

- 470 The corresponding author has declared that none of the authors has any competing interests.

Acknowledgements

- This work was supported by the National Science Centre in Poland [grant no. 2011/01/N/ST10/05880 to KT], the Polish Ministry of Science and Higher Education [grant no. N N306 316835 to WW] and funding from the Faculty of Oceanography and Geography, University of Gdańsk. KT was also supported with scholarship from The French Embassy in
475 Poland and Campus France to conduct one-month research stay in Meudon. The ASTER AMS national facility (CEREGE, Aix-en-Provence) is supported by the INSU/CNRS, the ANR through the “Projets ~~thématiques~~thématiques d'excellence” program for the “Equipements d'excellence” ASTER-CEREGE action and IRD.

References

- Aitken, M.J.: Thermoluminescence Dating. Academic Press, London. 359 pp., 1985.*
- 480 *Arnold, M., Merchel, S., ~~Bourlès~~Bourlès, D.L., Braucher, R., Benedetti, L., Finkel, R.C., Aumaître, G., Gott dang, A. and Klein, M.: The French accelerator mass spectrometry facility ASTER: Improved performance and developments. Nuclear Instruments and Methods in Physics Research B 268, 1954–1959, doi.org/10.1016/j.nimb.2010.02.107, 2010.*

- Balco, G., Stone, J.O., Lifton, N.A. and Dunai, T.J.: A complete and easily accessible means of calculating surface exposure ages or erosion rates from ^{10}Be and ^{26}Al measurements. *Quaternary Geochronology* 3, 174–195, doi.org/10.1016/j.quageo.2007.12.001, 2008.
- 485
- Blomdin, R., Stroeve, A.P., Harbor, J.M., Lifton, N.A., Heyman, J., Gribenski, N., Petrakov, Caffee, M.W., Ivanov, M.N., Hättestrand, C., Rogozhina, I. and Usabaliev, R.: Evaluating the timing of former glacier expansions in the Tian Shan: A key step towards robust spatial correlations. *Quaternary Science Reviews* 153, 78–96, doi.org/10.1016/j.quascirev.2016.07.029, 2016.
- Borchers, B., Marrero, S., Balco, G., Caffee, M., Goehring, B., Lifton, N., Nishiizumi, K., Philips, F., Schaefer, J. and Stone, J.: Geological calibration of spallation production rates in the CRONUS-Earth project. *Quaternary Geochronology* 31, 188–198, doi.org/10.1016/j.quageo.2015.01.009, 2016.
- 490
- Bortolot, V.J.: A new modular high capacity OSL reader system. *Radiation Measurements* 32, 751–757, doi.org/10.1016/S1350-4487(00)00038-X, 2000.
- Box, J. E., Fettweis, X., Stroeve, J. C., Tedesco, M., Hall, D. K. and Steffen, K.: Greenland ice sheet albedo feedback: Thermodynamics and atmospheric drivers, *Cryosphere*, 6(4), 821–839, doi:10.5194/tc-6-821-2012, 2012.
- Braucher, R., Guillou, V., Boulès, D. L., Arnold, M., Aumaître, G., Keddadouche, K. and Nottoli, E.: Preparation of ASTER in-house $^{10}\text{Be}/^9\text{Be}$ standard solutions. *Nuclear Instruments and Methods in Physics Research B* 361, 335–340, doi.org/10.1016/j.nimb.2015.06.012, 2015.
- 500
- Brodzikowski, K. and van Loon, A.J.: A systematic classification of glacial and periglacial environments, facies and deposits. *Earth Sci. Rev.* 24, 297–381, doi.org/10.1016/0012-8252(87)90061-4, 1987.
- Bronk Ramsey, C.: Bayesian analysis of radiocarbon dates. *Radiocarbon* 51, 337–360, doi.org/10.1017/S0033822200033865, 2009a.
- Bronk Ramsey, C.: Dealing with outliers and offsets in radiocarbon dating. *Radiocarbon* 51, 1023–1045, doi.org/10.1017/S0033822200034093, 2009b.
- 505
- Chmeleff, J., von Blanckenburg, F., Kossert, K. and Jakob, D.: Determination of the ^{10}Be half-life by multicollector ICP-MS and liquid scintillation counting. *Nuclear Instruments and Methods in Physics Research Section B: Beam Interactions with Materials and Atoms* 268, 192–199, doi.org/10.1016/j.nimb.2009.09.012, 2010.
- Chiverrell, R.C., Thrasher, I.M., Thomas, G.S.P., Lang, A., Scourse, J.D., van Landeghem, K.J.J., Mccarroll, D., Clark, C.D., O’Cofaigh, C., Evans, D.J.A. and Ballantyne, C.K.: Bayesian modelling the retreat of the Irish Sea Ice Stream. *Journal of Quaternary Science* 28, 200–209, doi.org/10.1002/jqs.2616, 2013.
- 510

- Clark, P. U., Alley, R. B. and Pollard, D.: Northern Hemisphere Ice-Sheet Influences on Global Climate Change, *Science*, 286, 1104–1111, doi:10.1126/science.286.5442.1104, 1999.
- 515 Clark, C.D., Sejrup, H.P., Bigg, G., Stocker, M., Lonergan, L., Raunholm, S. and Hafliðason, H.: Did the punctuated demise of glacial ice in the North Sea affect thermohaline circulation of the ocean? *Eos Trans. AGU* 85, doi:10.1029/2004EO310006, 2004.
- Clayton, L., Attig, J.W. and Mickleson, D.M.: Tunnel channels formed in Wisconsin during the last glaciations. In: Mickelson D.M. and Attig J.W. (Eds.) *Glacial Processes Past and Present. Geological Society of America Special Paper* 337, 69-82, 1999.
- 520 Davis, B.J.: Cryospheric Geomorphology: Dating Glacial Landforms II: Radiometric Techniques. In: Shroder J.F. (Ed.), *Treatise on Geomorphology (Second Edition)*, Academic Press, 249–280, doi.org/10.1016/B978-0-12-818234-5.00040-7, 2022.
- Dzierżek, J. and Zreda, M.: Timing and style of deglaciation of north-eastern Poland from cosmogenic ^{36}Cl dating of glacial and glaciofluvial deposits. *Geological Quarterly* 51, 203–216, 2007.
- 525 Ehlers, J., Grube, A., Stephan, H.-J. and Wansa, S.: Pleistocene glaciations of north Germany – new results. In: Ehlers, J., Gibbard, P.L. and Hughes, P.D. (Eds.), *Quaternary Glaciations - Extent and Chronology: A Closer Look*. Elsevier, Amsterdam, 149–162, doi.org/10.1016/B978-0-444-53447-7.00013-1, 2011.
- Ely, J. C., Clark, C. D., Small, D. and Hindmarsh, R. C. A.: ATAT 1.1, the Automated Timing Accordance Tool for comparing ice-sheet model output with geochronological data, *Geoscientific Model Development*, 12, 933–953, 2019.
- 530 Fuchs, M. and Owen, L.A.: Luminescence dating of glacial and associated sediments: review, re-recommendations and future directions. *Boreas* 37, 636–659, doi:10.1111/j.1502-3885.2008.00052.x., 2008.
- Fyke, J. G., Sergienko, O. V., Lofverstrom, M., Price, S. F. and Lenaerts, J.: An overview of interactions and feedbacks between ice sheets and the Earth system, *Rev. Geophys.*, 56, 361–408, doi:10.1029/2018RG000600, 2018.
- Galbraith, R.F., Roberts, R.G., Laslett, G.M., Yoshida, H. and Olley, J.M.: Optical dating of single and multiple grains of quartz from Jinmium Rock Shelter, Northern 12 Australia. Part I, experimental design and statistical models. *Archaeometry* 41, 1835–1857, doi.org/10.1111/j.1475-4754.1999.tb00988.x, 1999.
- Guerin, G., Mercier, N., Adamiec, G., 2011. Dose-rate conversion factors: update. *Ancient TL* 29: 5-8
- Galązka, D.: Detailed Geological Map of Poland at the scale 1:50 000, sheet Hawa. CAG PIG-PIB, Warszawa, 2003.
- Galązka, D.: Detailed Geological Map of Poland at the scale 1:50 000, sheet Lubawa. CAG PIG-PIB, Warszawa, 2006.
- 540 Galązka, D.: Detailed Geological Map of Poland at the scale 1:50 000, sheet Rybno. CAG PIG-PIB, Warszawa, 2009.

- Galązka, D. and Marks, L.: *Detailed Geological Map of Poland at the scale 1:50 000, sheet Dąbrówno. CAG PIG-PIB, Warszawa, 1997.*
- Galązka, D., Rychel, J., Krysiak, Z.: *Glaciotectonic structures and dynamics of Weichselian ice-sheet, western slope of Lubawa Hummock (in Polish). Prace Państwowego Instytutu Geologicznego 194, 27–34, 2009.*
- 545 Greenwood, S.L., Clark, C.D. and Hughes, A.L.C.: *Formalising an inversion methodology for reconstructing ice-sheet retreat patterns from meltwater channels: application to the British Ice Sheet. Journal of Quaternary Science 22, 637–645, doi.org/10.1002/jqs.1083, 2007.*
- Greve, R. and Blatter, H.: *Dynamics of Ice Sheets and Glaciers. Advances in Geophysical and Environmental Mechanics and Mathematics. Springer, Berlin, Heidelberg, doi.org/10.1007/978-3-642-03415-2, 2009.*
- 550 Guerin, G., Mercier, N. and Adamiec, G.: *Dose-rate conversion factors: update. Ancient TL 29, 5-8, 2011.*
- Hahn, L., Ummenhofer, C.C. and Kwon Y.-O.: *North Atlantic Natural Variability Modulates Emergence of Widespread Greenland Melt in a Warming Climate, Geophysical Research Letters, 45, 9171–9178, doi.org/10.1029/2018GL079682, 2018.*
- Heyman, J., Stroeven, A.P., Harbor, J.M. and Caffee, M.W.: *Too young or too old: Evaluating cosmogenic exposure dating based on an analysis of compiled boulder exposure ages. Earth and Planetary Science Letters 302, 71–80, doi:10.1016/j.epsl.2010.11.040, 2011.*
- 555 Hughes, A.L.C., Winsborrow, M.C.M. and Greenwood, S.L.: *European Ice Sheet Complex evolution during the Last Glacial Maximum (29–19 ka). In: Palacios, D., Hughes, P.D., García-Ruiz, J.M. and Andrés, N. (Eds.) European Glacial Landscapes. Maximum Extent of Glaciations. Elsevier, 361–372, doi.org/10.1016/B978-0-12-823498-3.00038-8, 2022.*
- 560 King, G.E., Robinson, R.A.J. and Finch, A.A.: *Towards successful OSL sampling strategies in glacial environments: deciphering the influence of depositional processes on bleaching of modern glacial sediments from Jostedal, Southern Norway. Quaternary Science Reviews 89, 94–107, doi.org/10.1016/j.quascirev.2014.02.001, 2014.*
- Korschinek, G., Bergmaier, A., Faestermann, T., Gerstmann, U.C., Knie, K., Rugel, G., Wallner, A., Dillmann, I., Dollinger, G. and von Gostomski, C.L.: *A new value for the half-life of ¹⁰Be by Heavy-Ion Elastic Recoil Detection and liquid scintillation counting. Nuclear Instruments and Methods in Physics Research Section B: Beam Interactions with Materials and Atoms 268, 187–191, doi.org/10.1016/j.nimb.2009.09.020, 2010.*
- 565 Kozarski, S.: *Deglaciation of northwestern Poland: environmental conditions and geosystem transformation (20 ka–10 ka BP). Dokumentacja Geograficzna 1, 1–82, 1995. (in Polish with English summary)*
- Kreutzer, S., Schmidt, C., Fuchs, M.C., Dietze, M., Fischer, M. and Fuchs, M.: *Introducing an R package for luminescence dating analysis. Ancient TL 30, 1–8, 2012.*

- Kurjański, B., Rea, B.R., Spangnolo, M., Cornwell, D.G., Howell, J. and Archer, S.: A conceptual model for glaciogenic reservoirs: from landsystems to reservoir architecture. *Mar. Petrol. Geol.*, 115, doi.org/10.1016/j.marpetgeo.2019.104205, 2020.
- Lal, D.: Cosmic ray labeling of erosion surfaces: In situ nuclide production rates and erosion models. *Earth Planetary Science Letters* 104, 424–439, doi.org/10.1016/0012-821X(91)90220-C, 1991.
- Levy, L. B., Kelly, M. A., Applegate, P. A., Howley, J. A. and Virginia R. A.: Middle to late Holocene chronology of the western margin of the Greenland Ice Sheet: A comparison with Holocene temperature and precipitation records, Arctic, Antarctic, and Alpine Research, 50, doi.org/10.1080/15230430.2017.1414477, 2018.
- Lüthgens, C. and Bose, M.: From morphostratigraphy to geochronology – on the dating of ice marginal positions. *Quaternary Science Reviews* 44, 26–36, doi.org/10.1016/j.quascirev.2010.10.009, 2012.
- Marks, L.: Foreland influence on Ice-Sheet Movement during the Vistulian (Würn) Glaciation: the Case of the Lubawa Elevation (Mazury Lakeland). *Bulletin de L'academe Polonaise des Sciences* 26 (3-4), 203-213, 1979.
- Marks, L.: Timing of the Late Vistulian (Weichselian) glacial phases in Poland. *Quaternary Science Reviews* 44, 81–88, doi.org/10.1016/j.quascirev.2010.08.008, 2012.
- 585 [Marks, L., Ber, A., Gogołek, W. and Piotrowska, K. \(eds.\): Geological Map of Poland 1:500 000. Ministerstwo Środowiska, PIG-PIB, Warszawa, 2006.](#)
- Marks, L., Bitinas, A., Blaszkiewicz, M., Börner, A., Guobyte, R., Rinterknecht V. and Tylmann, K.: Northern Central Europe: glacial landforms from the Last Glacial Maximum. In: Palacios, D., Hughes, P.D., García-Ruiz, J.M. and Andrés, N. (Eds.) *European Glacial Landscapes. Maximum Extent of Glaciations*. Elsevier, 381–388, doi.org/10.1016/B978-0-12-823498-3.00054-6, 2022.
- 590
- Moska, P., Bluszcz, A., Poręba, G., Tudyka, K., Adamiec, G., Szymak, A. and Przybyła, A.: Luminescence dating procedures at Gliwice luminescence dating laboratory. *Geochronometria* 48, 1-15, doi.org/10.2478/geochr-2021-0001, 2021.
- Murray, A.S. and Wintle, A.G.: Luminescence dating of quartz using an improved single-aliquot regenerative-dose protocol. *Radiation Measurements* 32, 57–73, doi.org/10.1016/S1350-4487(99)00253-X, 2000.
- 595
- Nawrocki, J., Bogucki, A. B., Gozhik, P., Łanczont, M., Pańczyk, M., Standzikowski, K., Komar, M., Rosowiecka, O. and Tomeniuk, O.: Fluctuations of the Fennoscandian Ice Sheet recorded in the anisotropy of magnetic susceptibility of periglacial loess from Ukraine, *Boreas*, 48, 940–952, doi.org/10.1111/bor.12400, 2019.
- NGRIP-members: High resolution climate record of the northern hemisphere reaching into the last interglacial period. *Nature* 431, 147–151, doi.org/10.1038/nature02805, 2004.

- 600 Niewiarowski, W.: *Pleni- and Late Vistulian glacial lakes, their sediments and landforms: a case study from the young glacial landscape of Northern Poland. Prace Geograficzne* 128, 133–142, 2003.
- Niewiarowski, W., Olszewski, A. and Wysota W.: *The role of subglacial features in glacial morphogenesis of Kujawy-Dobrzyń subphase area in the southern and eastern part of the Chelmino-Dobrzyń Lakeland. Quaternary Studies in Poland* 13, 65–76, 1995.
- 605 Noble, T.L., Rohling, E.J., Aitken, A.R.A., Bostock, H.C., Chase, Z., Gomez, N., Jong, L.M., King, M.A., Mackintosh, A.N., McCormack, F.S., McKay, R.M., Menviel, L., Phipps, S.J., Weber, M.E., Fogwill, C.J., Gayen, B., Golledge, N.R., Gwyther, D.E., Hogg, A. McC., Martos, Y.M., Pena-Molino, B., Roberts, J., van de Flierdt, T. and Williams, T.: *The Sensitivity of the Antarctic Ice Sheet to a Changing Climate: Past, Present, and Future. Reviews of Geophysics* 58, doi.org/10.1029/2019RG000663, 2020.
- 610 Prescott, J.R. and Stephan, L.G.: *The contribution of cosmic radiation to the environmental dose for thermoluminescence dating. Latitude, altitude and depth dependencies. TLS II-1*, 16–25, 1982.
- Rea, B. R., Newton, A. M. W., Lamb, R. M., Harding, R., Bigg, G. R., Rose, P., Spagnolo, M., Huuse, M., Cater, J. M. L., Archer, S., Buckley, F., Halliyeva, M., Huuse, J., Cornwell, D. G., Brocklehurst, S. H. and Howell, J. A., *Extensive marine-terminating ice sheets in Europe from 2.5 million years ago, Science Advances* 4, doi.org/10.1126/sciadv.aar8327, 2018.
- 615 ~~Rignot, E., Mouginot, J., Scheuchl, B., van den Broeke, M., van Wessem, M. J. and Morlighem, M.: *Four decades of Antarctic Ice Sheet mass balance from 1979–2017. Proceedings of the National Academy of Sciences of the United States of America*, 116, 1095–1103, doi.org/10.1073/pnas.1812883116, 2019.~~
- Rinterknecht, V.R., Clark, P.U.M., Raisbeck, G.M., Yiou, F., Bitinas, A., Brook, E.J., Marks, L., Zelcs, V., Lunkka, J.P., Pavlovskaya, I.E., Piotrowski, J.A. and Raukas, A. *The last deglaciation of the southeastern sector of the Scandinavian Ice Sheet. Science* 311, 1449–1452, 10.1126/science.1120702, 2006.
- 620 Rinterknecht, V.R., Marks, L., Piotrowski, J.A., Raisbeck, G.M., Yiou, F., Brook, E.J. and Clark, P.U.: *Cosmogenic ¹⁰Be ages on the Pomeranian moraine, Poland. Boreas* 34, 186–191, doi.org/10.1111/j.1502-3885.2005.tb01014.x, 2005.
- Soulet, G., Menot, G., Bayon, G., Rostek, F., Ponzevera, E., Toucanne, S., Lericolais, G. and Bard, E.: *Abrupt drainage cycles of the Fennoscandian Ice Sheet. PNAS* 110, 6682–6687, doi.org/10.1073/pnas.1214676110, 2013.
- 625 Stone, J.: *Air pressure and cosmogenic isotope production. Journal of Geophysical Research* 105, 23753–23760, doi.org/10.1029/2000JB900181, 2000.
- Stroeven, A.P., Hattestrand, C., Kleman, J., Heyman, J., Fabel, D., Fredin, O., Goodfellow, B.W., Harbor, J.M., Jansen, J.D., Olsen, L., Caffee, M.W., Fink, D., Lundqvist, J., Rosqvist, G.C., Stromberg, B. and Jansson, K.N., 2016. *Deglaciation of Fennoscandia. Quaternary Science Reviews* 147, doi.org/10.1016/j.quascirev.2015.09.016, 91–121.

630 ~~Thomas, R.H. Remote sensing reveals shrinking Greenland ice sheet. *Eos Science News* 82, 369–373, doi.org/10.1029/01EO00226, 2001.~~

Toucanne, S., Soulet, G., Freslon, N., Jacinto, R.S., Dennielou, B., Zaragosi, S., Eynaud, F., Bourillet, J.-F. and Bayon, G.: Millennial-scale fluctuations of the European Ice Sheet at the end of the last glacial, and their potential impact on global climate. *Quaternary Science Reviews* 123, 113–133, dx.doi.org/10.1016/j.quascirev.2015.06.010, 2015.

635 Toucanne, S., Zaragosi, S., Bourillet, J.F., Cremer, M., Eynaud, F., Turon, J.L., Fontanier, C., Van Vliet Lanoë, B. and Gibbard, P.: Timing of massive ‘Fleuve Manche’ discharges over the last 350 kyr: insights into the European Ice Sheet oscillations and the European drainage network from MIS 10 to 2. *Quaternary Science Reviews* 28, 1238–1256, doi.org/10.1016/j.quascirev.2009.01.006, 2009.

640 Toucanne, S., Zaragosi, S., Bourillet, J.-F., Marieu, V., Cremer, M., Kageyama M., Van Vliet-Lanoë, B., Eynaud, F., Turon, J.-F. and Gibbard, P.L.: The first estimation of Fleuve Manche palaeoriver discharge during the last deglaciation: evidence for Fennoscandian ice sheet meltwater flow in the English Channel ca 20-18 ka ago. *Earth Planet. Sci. Lett.* 290, 459–473, doi:10.1016/j.epsl.2009.12.050, 2010.

645 Toucanne, S., Zaragosi, S., Bourillet, J.F., Naughton, F., Cremer, M., Eynaud, F., Dennielou, B.: Activity of the turbidite levees of the Celtic-Armorican margin (Bay of Biscay) during the last 30,000 years: imprints of the last European deglaciation and Heinrich events. *Marine Geology* 247, 2008, 84–103.

Tylmann, K.: Dynamics of glacial processes in the area of the Lubawa Upland. PhD thesis, Nicolaus Copernicus University Archive, Toruń, 156 pp., 2014.

650 Tylmann, K., Rinterknecht, V.R., Woźniak, P.P., Boulès, D., Schimmelpfennig, I., Guillou, V., and ASTER Team: The Local Last Glacial Maximum of the southern Scandinavian Ice Sheet front: Cosmogenic nuclide dating of erratics in northern Poland. *Quaternary Science Reviews* 219, 36–46, doi.org/10.1016/j.quascirev.2019.07.004, 2019.

Tylmann, K., Rinterknecht, V., Woźniak, P.P., Guillou V. and ASTER Team: Asynchronous dynamics of the last Scandinavian Ice Sheet along the Pomeranian ice-marginal belt: A new scenario inferred from surface exposure ¹⁰Be dating. *Quaternary Science Reviews* 294, 107755, doi.org/10.1016/j.quascirev.2022.107755, 2022.

655 Tylmann, K., Wysota, W.: Origin and transformation of morainic landscape in NW part of Lubawa Upland (north Poland) (in Polish). *Przegląd Geologiczny* 59, 739–750, 2011.

Tylmann, K., Wysota, W., Piotrowski, J.A.: Palimpsest terminal moraines in NW part of Lubawa Upland – structure and mechanisms of formation. *Landform Analysis* 25: 143–157, dx.doi.org/10.12657/landfana.025.013, 2014.

Welniak, A.: Detailed Geological Map of Poland at the scale 1:50 000, sheet Nowe Miasto Lubawskie. CAG PIG-PIB, Warszawa, 2002.

- 660 Wysota, W., Molewski, P. and Sokołowski, R.J.: *Record of the Vistula ice lobe advances in the Late Weichselian glacial sequence in north-central Poland. Quaternary International* 207, 26–41, doi.org/10.1016/j.quaint.2008.12.015, 2009.
- Zaragosi, S., Bourillet, J.F., Eynaud, F., Toucanne, S., Denhard, B., Van Toer, A., and Lanfume, V.: *The impact of the last European deglaciation on the deep-sea turbidite systems of the Celtic–Armorican margin (Bay of Biscay). Geo-Marine Letters* 26, 317–329, doi.org/10.1007/s00367-006-0048-9, 2006.
- 665 Zaragosi, S., Eynaud, F., Pujol, C., Auffret, G.A., Turon, J.L. and Garlan, T.: *Initiation of the European deglaciation as recorded in the northwestern Bay of Biscay slope environments (Meriadzek Terrace and Trevelyan Escarpment): a multi-proxy approach. Earth Planetary Science Letters* 188, 493–507, doi.org/10.1016/S0012-821X(01)00332-6, 2001.

Table A1: OSL samples with laboratory data and parameters used during OSL age calculation.

Lab. Code	Th (Bq/kg)	U (Bq/kg)	K (Bq/kg)	D _r (Gy/ka)	σOD (%)	D _e (Gy)	OSL age (ka)
GdTL-1346	8.7 ± 0.4	10.3 ± 0.3	295 ± 13	1.25 ± 0.05	9	23.1 ± 0.7	18.5 ± 0.9
GdTL-1347	9.7 ± 0.6	12.9 ± 0.4	320 ± 15	1.38 ± 0.06	11	22.7 ± 0.7	16.4 ± 0.8
GdTL-1348	9.8 ± 0.5	12.0 ± 0.4	314 ± 15	1.36 ± 0.06	10	23.8 ± 0.7	17.3 ± 0.8
GdTL-1349	8.2 ± 0.6	10.4 ± 0.4	297 ± 16	1.27 ± 0.06	11	23.2 ± 0.7	18.7 ± 1.0
GdTL-1350	10.9 ± 0.5	13.3 ± 0.4	340 ± 15	1.44 ± 0.06	16	21.1 ± 0.8	14.5 ± 0.8
GdTL-1351	8.3 ± 0.4	8.9 ± 0.4	330 ± 10	1.26 ± 0.05	12	186.5 ± 5.5	148.9 ± 7.2
GdTL-1352	14.1 ± 0.5	12.0 ± 0.4	344 ± 10	1.45 ± 0.05	25	209.0 ± 11.3	143.9 ± 9.1
GdTL-1353	9.7 ± 0.5	9.4 ± 0.4	318 ± 10	1.30 ± 0.05	24	165.3 ± 12.8	126.8 ± 11.0
GdTL-1879	7.3 ± 0.3	5.9 ± 0.2	327 ± 10	1.25 ± 0.05	10	24.0 ± 0.8	19.1 ± 0.9
GdTL-1880	7.5 ± 0.3	6.4 ± 0.2	327 ± 10	1.27 ± 0.05	5	23.2 ± 0.5	18.2 ± 0.8
GdTL-1881	7.5 ± 0.3	6.8 ± 0.3	332 ± 10	1.35 ± 0.05	12	23.6 ± 0.8	17.4 ± 0.9

Table A2: Equivalent doses (D_e) measured for individual aliquots in OSL samples. All values are given in Gy.

GdTL-1346 (n = 20)		GdTL-1347 (n = 20)		GdTL-1348 (n = 20)		GdTL-1349 (n = 22)		GdTL-1350 (n = 24)		GdTL-1351 (n = 31)		GdTL-1352 (n = 19)		GdTL-1353 (n = 28)		GdTL-1879 (n = 23)		GdTL-1880 (n = 22)		GdTL-1881 (n = 23)	
D _e	±	D _e	±	D _e	±	D _e	±	D _e	±	D _e	±	D _e	±	D _e	±	D _e	±	D _e	±	D _e	±
19.07	2.00	19.83	1.50	20.79	1.97	16.61	1.85	26.53	2.00	134.76	13.48	172.30	17.23	148.38	14.84	18.50	1.50	20.87	1.50	19.58	1.50
19.15	2.00	22.25	1.50	21.34	1.50	18.33	1.50	24.04	2.00	140.90	14.09	183.50	18.35	148.40	14.84	19.72	1.50	20.95	1.50	20.03	1.50
19.31	2.00	23.84	1.50	21.54	1.50	18.55	1.50	26.14	2.00	143.30	14.33	183.66	18.37	148.41	14.84	20.99	1.50	22.12	1.50	20.22	1.50
19.40	2.00	23.96	1.50	23.50	1.50	19.61	1.50	22.07	2.00	152.70	15.27	184.60	18.46	152.55	15.26	21.05	1.50	22.25	1.50	21.59	1.50
22.06	2.00	24.18	1.50	23.52	1.50	19.79	1.50	24.83	2.00	157.00	15.70	196.35	19.64	154.80	15.48	21.91	1.80	22.33	1.50	21.83	1.50
22.72	2.00	24.78	1.50	23.66	1.50	21.88	1.50	21.11	2.00	167.05	16.71	203.57	20.36	160.80	16.08	21.91	1.50	22.53	1.50	22.95	1.50
22.72	2.00	24.81	1.50	23.82	1.50	25.09	1.50	18.62	2.00	167.08	16.71	210.27	21.03	160.80	16.08	23.30	1.50	22.69	1.50	23.09	1.50
23.04	2.00	25.01	1.50	23.97	1.50	25.10	1.50	21.37	2.00	170.60	17.06	211.91	21.19	161.04	16.10	23.31	1.50	23.10	1.50	23.43	1.50
24.93	2.00	26.76	1.50	27.08	1.50	26.87	1.50	18.39	2.00	172.18	17.22	212.96	21.30	162.14	16.21	24.38	1.50	23.45	1.50	23.43	1.50
27.49	2.00	23.13	1.50	27.97	1.50	28.01	2.00	15.29	1.50	173.97	17.40	215.50	21.55	168.14	16.81	24.43	1.80	24.24	1.50	23.64	1.50
28.12	2.00	19.51	1.50	27.25	1.50	30.39	4.83	15.48	1.50	174.40	17.44	225.30	22.53	182.04	18.20	24.70	1.80	24.64	1.50	24.08	1.50
21.25	2.00	24.57	1.50	27.46	1.50	21.09	1.50	15.61	1.50	177.40	17.74	227.35	22.74	188.13	18.81	24.79	1.50	24.86	1.50	24.17	1.50
24.46	2.00	17.43	1.50	19.71	1.50	23.65	1.50	17.37	1.50	178.07	17.81	230.61	23.06	201.60	20.16	25.18	1.80	24.87	1.50	24.20	1.50
24.99	2.00	25.55	1.50	24.38	1.50	23.40	1.50	17.64	1.50	183.60	18.36	249.00	24.90	201.60	20.16	25.28	1.50	24.89	1.50	24.24	1.50
27.44	2.00	18.30	1.50	19.55	1.50	25.45	2.00	18.37	1.50	186.10	18.61	262.18	26.22	205.29	20.53	25.30	1.80	25.04	1.50	25.00	1.50
25.56	2.00	26.71	1.50	19.89	1.50	23.24	1.50	18.78	1.50	187.65	18.77	281.90	28.19	208.20	20.82	25.97	1.80	25.30	1.50	25.41	1.50
21.81	2.00	21.87	1.50	22.54	1.50	27.30	2.00	19.17	1.50	188.93	18.89	379.80	37.98	209.70	20.97	26.21	1.80	25.37	1.50	26.23	1.50
24.27	2.00	20.91	1.50	22.49	1.50	22.20	1.50	19.26	1.50	189.47	18.95	414.40	41.44	209.81	20.98	26.58	1.80	25.54	1.50	26.76	1.50
20.13	2.00	22.33	1.50	26.42	1.50	26.53	2.00	21.46	1.50	190.75	19.08	443.90	44.39	233.27	23.33	26.69	1.80	26.07	1.50	27.27	1.50
21.27	2.00	17.76	1.50	26.77	1.50	24.04	2.00	22.43	1.50	192.88	19.29			237.53	23.75	28.33	1.80	26.09	1.50	27.99	1.50
						26.14	2.00	26.26	2.00	195.83	19.58			239.03	23.90	28.48	1.80	26.80	1.50	28.62	1.50
						22.07	1.50	26.49	2.00	198.91	19.89			245.30	24.53	28.73	1.80	28.67	1.50	29.37	1.50
								26.88	2.00	207.66	20.77			284.18	28.42	29.59	1.80			30.06	1.50

								26.95	2.00	212.71	21.27			286.80	28.68						
										214.46	21.45			307.95	30.80						
										220.60	22.06			309.45	30.95						
										220.90	22.09			311.11	31.11						
										222.30	22.23			322.73	32.27						
										231.12	23.11										
										238.94	23.89										
										257.70	25.77										

Table A3: The notation of commands used to process the *Sequence* algorithms in OxCal.

```
Options()
{
  BCAD = FALSE;
  kIterations = 100;
  PlusMinus = FALSE;
  SD1 = FALSE;
  SD2 = TRUE;
  SD3 = FALSE;
};
Plot()
{
  Outlier_Model("FIS",T(5),U(0.4),"t");
  Sequence("FIS_oscillations")
  {
    Boundary("START");
    Phase("MIS 6")
    {
      C_Date("GdTL-1351", 148900, 7200)
      {
        Outlier(0.05);
      };
      C_Date("GdTL-1352", 143900, 9100)
      {
        Outlier(0.05);
      };
      C_Date("GdTL-1353", 126800, 11000)
      {
        Outlier(0.05);
      };
    };
    Boundary("Rz2a_till");
    Phase("I_periglacial phase")
    {
      C_Date("GdTL-1349", 18700, 1000)
      {
        Outlier(0.05);
      };
      C_Date("GdTL-1350", 14500, 800)
      {
        Outlier(0.05);
      };
      C_Date("GdTL-1879", 19100, 900)
      {
        Outlier(0.05);
      };
      C_Date("GdTL-1880", 18200, 800)
      {
        Outlier(0.05);
      };
      C_Date("GdTL-1881", 17400, 900)
      {
        Outlier(0.05);
      };
    };
  };
};
```

```

};
Boundary("Rz2b_till");
Phase("II_periglacial_phase")
{
  C_Date("GdTL-1346", 18500, 900)
  {
    Outlier(0.05);
  };
  C_Date("GdTL-1347", 16400, 800)
  {
    Outlier(0.05);
  };
  C_Date("GdTL-1348", 17300, 800)
  {
    Outlier(0.05);
  };
};
Boundary("Rz2c_till");
Before(Age("Gd-10818", 16190, 330));
Boundary("END");
};
};

```

675


Table A4: Surface exposure ^{10}Be ages of erratic boulders. The list consists of five new ^{10}Be ages (LUB samples) and nine ages recalculated from the original data of Rinterknecht et al. (2006) and Tylmann et al. (2019). All ^{10}Be exposure ages are calculated with ‘Lm’ time-dependent scaling scheme for spallation according to Lal (1991) and Stone (2000) and the global production rate according to Borchers et al. (2016).

Sample ID	Latitude N DD	Longitude E DD	Elevation (m a.s.l.)	Boulder lithology	Landform	Sample thickness (cm)	Shielding factor ¹	Quartz (g)	[^{10}Be] (10^4 at g^{-1})	Age (ka)
New samples										
LUB-01	53.5346	19.8096	192	granite	moraine	1.1	0.9999	11.296	13.11 ± 0.74	25.8 ± 2.4
LUB-02	53.5196	19.8593	254	gneiss	moraine	2.0	1.0000	20.414	9.87 ± 0.46	18.4 ± 1.6
LUB-03	53.5252	19.8643	263	granitic gneiss	moraine	4.0	0.9874	14.790	7.42 ± 0.47	14.1 ± 1.4
LUB-04	53.4983	19.8601	204	granite	proglacial valley	3.3	1.0000	19.685	6.31 ± 0.37	12.5 ± 1.2
LUB-05	53.5383	19.9283	286	gneiss	moraine	1.5	0.9976	18.573	11.58 ± 0.85	20.9 ± 2.2
Recalculated samples²										
LES-5	53.5792	20.0944	180	granite	moraine	2.0	1.0000	40.000	19.24 ± 1.16	40.3 ± 3.9
LES-6	53.6006	20.0611	151	gneiss	edge of subglacial valley	2.0	1.0000	40.000	8.08 ± 0.58	17.4 ± 1.8
LES-7	53.6250	20.0417	132	granite	subglacial valley	2.0	1.0000	60.509	2.64 ± 0.33	5.8 ± 0.8
LES-8	53.5111	19.9000	255	granite	moraine	2.0	1.0000	40.001	10.14 ± 1.10	19.7 ± 2.6
LES-10	53.5764	19.9417	270	granite	moraine	2.0	1.0000	40.007	6.78 ± 0.57	13.0 ± 1.5
LES-11	53.5222	19.8375	218	gneiss	moraine	2.0	1.0000	39.993	7.94 ± 0.77	16.0 ± 2.0
LES-12	53.5625	19.9528	275	granite	moraine	2.0	1.0000	40.007	8.46 ± 0.70	16.1 ± 1.8
LES-13	53.5530	19.9250	302	granite	moraine	2.0	1.0000	40.005	19.15 ± 1.33	35.5 ± 3.7
LGM-12	53.3874	19.752	130	granite	moraine	1.2	1.0000	15.070	11.50 ± 0.53	24.1 ± 2.1

680 AMS $^{10}\text{Be}/^9\text{Be}$ results are standardized to NIST SRM 4325 (samples LES) and STD-11 (samples LUB). $^{10}\text{Be}/^9\text{Be}$ ratios were corrected for a process blank values of 3.80×10^{-15} (samples LES), 3.38×10^{-15} (sample LGM-12) and 4.44×10^{-15} (samples LUB).

¹ Corresponding to self-shielding (direction and angle of surface dip).

² Based on original data from Rinterknecht et al (2005, 2006) and Tylmann et al. (2019).



685

Figure A1: Location of erratic boulders used in this study against the high-resolution digital elevation model (LiDAR). Green stars indicate position of boulders, sample symbols and surface exposure ages (ka) are also given.

Table A5: OSL dating controls and results of the Bayesian age modelling.

Phase/Boundary	Sample	Age (ka)	Initial model ($A_{\text{model}} = 41.3\%$)		Model with down-weighted age ($A_{\text{model}} = 103.4\%$)	
			Modeled age (ka)	A index (%)	Modeled age (ka)	A index (%)
<i>Rz2c till</i>					16.9 ± 0.5	-
II periglacial phase	GdTL-1348	17.3 ± 0.8	17.3 ± 0.5	126.6	17.3 ± 0.4	128.2
	GdTL-1347	16.4 ± 0.8	17.2 ± 0.4	87.9	17.3 ± 0.4	83.5
	GdTL-1346	18.5 ± 0.9	17.4 ± 0.5	69.4	17.5 ± 0.5	75.2
<i>Rz2b till</i>					17.8 ± 0.5	-
I periglacial phase	GdTL-1881	17.4 ± 0.9	18.1 ± 0.5	97.6	18.2 ± 0.5	94.2
	GdTL-1880	18.2 ± 0.8	18.3 ± 0.5	121.5	18.3 ± 0.5	123.2
	GdTL-1879	19.1 ± 0.9	18.5 ± 0.6	99.7	18.5 ± 0.6	102.9
	GdTL-1350*	14.5 ± 0.8	18.2 ± 0.8	4.6	18.4 ± 0.7	108.1
	GdTL-1349	18.7 ± 1.0	18.4 ± 0.6	119.6	18.4 ± 0.6	122.7
<i>Rz2a till</i>					19.2 ± 1.1	-
MIS 6	GdTL-1353	126.8 ± 11.0	126.7 ± 10.9	100.4	126.7 ± 11.0	100.4
	GdTL-1352	143.9 ± 9.1	142.9 ± 8.8	102.0	142.9 ± 8.8	102.1
	GdTL-1351	148.9 ± 7.2	147.6 ± 7.1	100.5	147.6 ± 7.1	100.5

690

* age identified in the initial *Sequence* as outlier; the age was down-weighted in the re-run *Sequence* to a prior probability of 0.85 of being an outlier